



Dewberry Engineers Inc.

4805 LAKE BROOK DRIVE
SUITE 200
GLEN ALLEN, VA 23060
804.290.7957 (PHONE)
804.290.7928 (FAX)

ANSMISSION LINE REBUIL
PROJECT TL 550
CONSTRUCTION DOCUMENTS

EAL

PRELIMINARY
NOT FOR CONSTRUCTION

SCALE

0' 50' 100'

HORIZONTAL SCALE

0' 25' 50'

VERTICAL SCALE

REVISIONS

DRAWN BY

APPROVED BY

CHECKED BY

DATE

JDE

ARB


05/21/21


DOM 16 PLAN & PROFILE


PROJECT NO. 50106442

DOM16-01

SHEET NO.










Dewberry Engineers Inc.

4805 LAKE BROOK DRIVE
SUITE 200
GLEN ALLEN, VA 23060
804.290.7957 (PHONE)
804.290.7928 (FAX)

## TRANSMISSION LINE REBUILD PROJECT TL 550 CONSTRUCTION DOCUMENTS

SEAL





DRAWN BY

APPROVED BY
CHECKED BY
DATE

JDE

ARB

05/21/21


TITLE

DOM 16 CROSS SECTIONS

PROJECT NO. 50106442

DOM16-02

SHEET NO.






Dewberry Engineers Inc.

4805 LAKE BROOK DRIVE
SUITE 200
GLEN ALLEN, VA 23060
804.290.7957 (PHONE)
804.290.7928 (FAX)

NSMISSION LINE REBUIL
PROJECT TL 550
ONSTRUCTION DOCUMENTS

EAL

PRELIMINARY NOT FOR CONSTRUCTION



DRAWN BY

APPROVED BY
CHECKED BY
DATE


TITLE

DOM16 ESC PLAN

PROJECT NO. 50106442

DOM16-03

SHEET NO



DOM 16 INSTALLATION PLAN EARTHWORK CALCULATIONS				
	CUT (CY)	FILL (CY)	NET (CY)	
DOM 16 IMPROVEMENT	309.7	286.1	23.6 (CUT)	
INSTALL PULLER PAD AT STR. #163	1275.6	38.7	1236.9 (CUT)	
INSTALL CRANE PAD AT STR. #163	100	218.7	118.7 (FILL)	
INSTALLATION TOTALS	1685.3	543.5	1141.8 (CUT)	

DOM 16 RESTORATION PLAN EARTHWORK CALCULATIONS					
	CUT (CY)	FILL (CY)	NET (CY)		
DOM 16 IMPROVEMENT	284.2	307	22.8	(FILL)	
RESTORE PULLER PAD AT STR. #163	39.3	1272.9	1233.6	(FILL)	
RESTORE CRANE PAD AT STR. #163	220.4	98.8	121.6	(CUT)	
RESTORATION TOTALS	543.9	1678.7	1134.8	(FILL)	

FINAL EARTHWORK BALANCE				
	NET (	CY)		
DOM 16 INSTALLATION	1141.8	(CUT)		
DOM 16 RESTORATION	1134.8	(FILL)		
DOM 16 TOTAL	7	(CUT)		

## EARTHWORK NOTES


- EXCESS MATERIALS SHALL BE STORED IN TEMORARY STOCKPILE AREAS AS SHOWN ON ROAD PLANS FOR CE47.
   WHERE ADDITIONAL FILL MATERIAL IS REQUIRED, SUITABLE EXCESS MATERIALS
- 2. WHERE ADDITIONAL FILL MATERIAL IS REQUIRED, SUITABLE EXCESS MATERIALS FROM INSTALLATION AND RESTORATION OF OTHER ROADS WITHIN THE GWNF MAY BE USED.
- 3. OVERALL EARTHWORK BALANCES FOR DOM 16 WILL BE PROVIDED IN SUMMARY TABLE.


## RESTORATION PLAN NOTES

PACKAGE.

- PLAN SHOWN HERE REPRESENTS "RESTORATION PLAN". SEE SHEET DOM16-01
  FOR "INSTALLATION PLAN"
- FOR SHENANDOAH CREST ZONE MITIGATION MEASURES, REFER TO ENVIRONMENTAL ASSESSMENT (EA), DESIGN ELEMENTS AND THREATENED & ENDANGERED SPECIES SECTIONS.
- 3. FIELD MODIFICATIONS WITHIN THE PERMITTED CONSTRUCTION LIMITS (AS SHOWN ON THE PROJECT MAPS) MAY BE APPROVED BY THE CONSTRUCTION COORDINATOR/CERTIFIED LAND DISTURBER AND NOTED ON THE DRAWING. FIELD MODIFICATIONS THAT EXTEND OUTSIDE OF PERMITTED CONSTRUCTION LIMITS (AS SHOWN ON THE PROJECT MAPS) REQUIRE APPROVAL BY THE GWNF PRIOR TO IMPLEMENTATION.
- 4. CRANE PADS ARE TO BE STABILIZED AS SHOWN ON RESTORATION PLAN. DUE TO PRESENCE OF ROCK, SITE CONTRACTOR AND ENVIRONMENTAL COMPLIANCE COORDINATOR MAY USE GEOTECHNICAL DATA TO DETERMINE SOIL STABILITY AT CRANE PADS AFTER INSTALLATION.
- 5. NARROWED ROAD WIDTH AS SHOWN ON RESTORATION PLAN IS BASED ON THE AVERAGE EXISTING ROAD WIDTH DETERMINED BY LIDAR SURVEY.
- 6. IN ADDITION TO TEMPORARY AND PERMANENT SEEDING, JUTE MATTING MAY BE REQUIRED TO ENSURE STABILIZATION.
- 7. REFER TO GEORGE WASHINGTON NATIONAL FOREST FORESTWIDE STANDARDS
  AND EROSION AND SEDIMENT CONTROL STANDARD NOTES AND DETAILS
  INCLUDED AT THE FRONT OF THE TL 550 PHASE 3 CONSTRUCTION DOCUMENT
- 8. EXISTING GRADES SHOWN ON CROSS SECTIONS AND PLAN & PROFILE ARE BASED
- ON LIDAR DATA PROVIDED BY DOMINION ENERGY.

  OF PROFILE SHOWS RET DESSETS TO LEFT AND RIGHT OF CENTERLINE TO
- 9. PROFILE SHOWS 8FT OFFSETS TO LEFT AND RIGHT OF CENTERLINE TO ILLUSTRATE EXISTING GRADE ON EDGE OF ROADWAY WITH 16FT WIDTH.







Dewberry Engineers Inc.

4805 LAKE BROOK DRIVE
SUITE 200
GLEN ALLEN, VA 23060
804.290.7957 (PHONE)
804.290.7928 (FAX)

NSMISSION LINE REBUI PROJECT TL 550 ONSTRUCTION DOCUMENTS

\_\_\_

PRELIMINARY
NOT FOR CONSTRUCTION

SCALE

0' 50' 100'

HORIZONTAL SCALE

REVISIONS	
DRAWN BY	JDE
APPROVED BY	
CHECKED BY	ARB
DATE	05/21/21

DOM 16 RESTORATION PLAN

PROJECT NO. 50106442

DOM16-R1

SHEET NO.