

## 811 SURFACE MAINTENANCE

### 811.01

#### Service Required

Smooth and shape native or aggregate surfaced roads including traveled way, shoulders, turnouts, and intersections. Reshape or recondition ditches, waterbars, and drain dips.

### 811.02

#### Performance Standards

##### **A. *Maintenance Level 2 through 5 Roads***

A road surface is maintained to standard when the travel way is free of washboards, potholes, or other irregularities. The surface is smooth, compact, crowned or sloped to drain, without segregation of the surfacing materials. Suitable materials have been recovered and incorporated. Unsuitable materials have been removed. Ditches and road surface drainage structures function efficiently. Unpaved shoulders are shaped to provide a smooth transition from the paved surface and drain efficiently.

##### **B. All Roads**

When ordered by the Contracting Officer to work in a weed infested area the contractor will be required to prevent spreading the infestation into un-infested areas by cleaning vehicles and equipment. The contractor will use wash stations approved by the Contracting Officer.

### 811.03

#### Location of Work

As specified on roads listed on the road listing, shown on the plans, marked on the ground, or as ordered by the Contracting Officer. Locations of weed-infested areas are marked on the ground. Do not operate in the weed-infested areas unless ordered to do so by the Contracting Officer.

### 811.04

#### Measurement

Measurement under this Section will be made by the total number of units for each item listed in the SCHEDULE OF ITEMS completed and accepted.

A. Single Lane Roads: Surface maintenance will be measured along the centerline of the roadway. Turnouts are incidental. Measurement will be to the nearest one-tenth (0.1) mile.

B. Double Lane Roads: Surface maintenance will be measured along the centerline of the roadway. Measurement will be to the nearest one-tenth (0.1) mile.

C. Road Mile: Work activity will be measured along the centerline of the road regardless of the number of lanes.

#### 811.05

##### Payment

The accepted quantities will be paid at the contract price per unit of measurement for the Section 811 pay items listed in the schedule of items. Payment will be full compensation for the work prescribed in this Section.

Mobilization and Log Out (*Typical: LOGOUT*) are incidental to pay item.

<u>Pay Item</u>	<u>Pay Unit</u>
811(01) Surface Maintenance Level ALL roads	Mile

#### 811.06

##### Acceptable Quality Levels

Acceptance will be determined by visual inspection. If visual inspection finds that all work conforms to performance standards (811.02) the work will be acceptable. If visual inspection finds that occasional work elements do not completely conform to performance standards but non-conforming work elements are not representative of an overall quality of work problem the work will be acceptable. If visual inspection finds that non-conforming work is representative of an overall quality of work problem, rework will be required.