

### **3.0 SITE SAMPLING AND TEST RESULTS**

A Niton XLt, 700 Series was used to assess the material from the wasterock dump for potential contamination.

- In Situ testing was performed per EPA Method 6200.
- Surface soils were removed to approximately 4 to 6 inches below grade in order to get below highly oxidized surface layers and to create a flat surface to place the Niton.
- Rocks, debris and other deleterious materials were removed.

Refer to Appendix A for a listing of elements that were detected as well as those that exceeded any regulatory requirements.