

**GYPSY STEWARDSHIP
SPECIFIED ROAD SCHEDULE OF ITEMS**

| Item Number | Item Description & Milepost | C or R ¹ | Unit & M of M ² | Quantity | Road Std. (W,D,S) ³ | Unit Allowance | Estimated Allowance |
|-------------|---|---------------------|----------------------------|----------|--------------------------------|----------------|---------------------|
| | | | | | | | |
| | | | | | | DATE: | 6/24/2015 |
| | FR 4745-B1 | C | | | S | | |
| | M.P. 0.0-0.12 | | | | | | |
| 249(02) | Composite Road Construction Work includes clearing, grubbing and shaping road to crown or out slope. Construct outlet ditches to allow for drainage and construct turnaround left at the end of the road as directed by the Forest Service. | | DQ Mile | 0.12 | | 4500 | \$ 540.00 |
| | | | | | | | |
| | Grand Total Gypsy Timber Sale Specified Road Schedule of Items | | | | | | \$ 540.00 |
| | | | | | | | |

¹C = Construction, R = Reconstruction

²Method of Measure

³W = Winter, D = Dry Summer, S = Summer

GYPSY STEWARDSHIP Specified Road Notes

- NOTE:** The construction requirements for composite road construction slash disposal shall be Method A as described in the Supplemental Specification Item 249.
- NOTE:** Construct the road bed to conform to the typical detail as noted in the narrative description.
- NOTE:** During clear and grub operations all slash resulting from purchaser's operations shall be treated as per **KT-GT 6.7#**.