

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
CONTINUATION TEMP INTO PU #04							
	0.00 - 0.01	Haul and place 45 CY (58.5 CY loose) pit run borrow, from North Jay Bird pit, to surface road entrance (150'L x 12'W x 8"D).		C.Y.	45	\$ 12.00	\$ 540.00
Total temp into PU #04 US-45							\$ 1,940.00

TEMP INTO PU #06							
	0.00 - 0.06	Construct road and L turn around to Left to temp road standard. Shape road to drain and improve/widen entrance.	S	LS	1	\$ 550.00	\$ 550.00
	0.00 - 0.01	Furnish, haul, and place 15 CY crushed aggregate material to surface entrance (19.5 CY loose)		C.Y.	15	\$ 25.00	\$ 375.00
Total temp into PU #06							\$ 925.00

TEMP INTO PU #07							
	0.0 - 0.06	Improve existing road with minor shaping to temp road standard. (Milepost 0.0 - 0.03 is a continuation of FR 5241). Improve T-turn around at the POE.	S	LS	1	\$ 150.00	\$ 150.00
	0.06	Haul and place 45 CY (58.5 CY loose) pit run borrow, from North Jay Bird pit, 15 CY for each leg of turnaround.		C.Y.	45	\$ 12.00	\$ 540.00
Total temp into PU #07							\$ 690.00

Grand Total Temp Roads							\$ 5,755.00
-------------------------------	--	--	--	--	--	--	--------------------

Prepared by: Mary Zelinski/Engineering Technician

QUEEN BEE STEWARDSHIP

TEMP ROAD PLAN -- APPRAISAL COSTS ESTIMATES

PAGE 1 OF 2

DATE:

7/7/2015

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
TEMP ROAD INTO PU #01							
	0.0 - 0.03	Clear and grub temporary access into payment unit #01 to allow truck to park parallel to FR 5260 "Linear Landing" 158' L x 13' W	S	LS	1	\$ 500.00	\$ 500.00
		Untreated aggregate courses furnish/haul, and place 15 CY (19.5 CY loose) crushed aggregate on each end of "Linear Landing" to surface and reinforce road. (50'L x 12'W x 8"D at two locations)		C.Y.	30	\$ 25.00	\$ 750.00
		Total temp into PU #01					\$ 1,250.00
TEMP ROAD INTO PU #04 off of FR 5260							
	0.0 - 0.09	South from FR 5260 into Unit #4 improve existing road to temp road standard with clearing, shaping, and grubbing. Construct L turn around to the left at POE.	S	LS	1	\$ 500.00	\$ 500.00
	0.01	Remove Berm		LS	1	\$ 75.00	\$ 75.00
	0.00 - 0.01	Untreated aggregate courses furnish/haul, and place 15 CY (19.5 CY loose) crushed aggregate, surfacing at jct FR 5260. (50'L x 12'W x 8"D)		C.Y.	15	\$ 25.00	\$ 375.00
		TOTAL temp into PU #04 off FR 5260					\$ 950.00
TEMP ROAD INTO PU #04 off of Old US-45							
	0.00 - 0.04	Construct "Back-In" off of Old US-45 into Unit #04 clear and grub to a temp road standard.	S	LS	1	\$ 400.00	\$ 400.00
	0.00 - 0.03	Excavate (100'L x 18'W x 3'D) right slightly up hill and place 200 CY material from road side to fill in low area and build entrance for the "Back-In" spur.		C.Y.	200	\$ 5.00	\$ 1,000.00