

BRIAR PATCH

TEMP ROAD COSTS

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
TEMP INTO PU 02			S				
	0.0-0.17	Improve existing unauthorized road into Northern segment of PU 02 .Includes berm removal. Minor shaping		LS	1	340	\$ 340.00
Total temp access into North PU 02						\$	340.00

TEMP INTO PU 02			S				
	0.0-0.06	Improve existing unauthorized road into southern segment of PU 02 .Includes berm removal and shaping of turnaround.		LS	1	350	\$ 350.00
Total temp access South PU 02						\$	350.00

BACK INTO PU 05			S				
	0.0-0.02	Construct temp back in spur into PU 05		LS	1	450	\$ 450.00
	0.01	Furnish, haul, and place 15 C.Y crushed aggregate surfacing to place at entrance.(19.5 loose material)		C.Y.	15	25	\$ 375.00
Total access into PU 05						\$	825.00

TEMP ACCESS BETWEEN PU's 05 and 06			S				
	0.0-0.17	Improve existing unauthorized road between PU 05/06.Includes berm removal and shaping of turnaround.		LS	1	500	\$ 500.00
Total access between PU's 05 and 06						\$	500.00

TEMP INTO NORTHERN PART OF PU 07

	0.0-0.04	Construct temp back in spur into PU 07 North off of FR 5010C and outside of powerline clearing		LS	1	400	\$ 400.00
Total access into northern PU 07						\$	400.00

BRIAR PATCH**TEMP ROAD COSTS**

PAGE 2 OF 2

DATE:

2/1/2016

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
TEMP INTO FR 5010-C EAST of PU 07			S				
	0.0-0.23	Improve existing unauthorized road. Includes berm removal and shaping temp road to intersection of FR 5010-C.(conserve topsoil)		LS	1	805	\$ 805.00
	0.01	Furnish, haul, and place 15 C.Y crushed aggregate surfacing to place at entrance.(19.5 loose material)		C.Y.	15	25	\$ 375.00
	0.01	Furnish and install 12" x 44' high density polyethylene dual walled culvert		LF	44	8	\$ 352.00
	0.01	Use material from roadway adjacent material to backfill and		L.S.	1	150	\$ 150.00
	0.01	reshape slopes to restore and match existing terrain and purchaser retains culvert		L.S.	1	200	\$ 200.00
	0.0-0.23	Haul and place from Pit lake Pit 60 C.Y pit run gravel as directed by the Forest Service. (78 loose material)		C.Y.	60	15	\$ 900.00
Total temp to FR 5010-C							\$ 2,782.00

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
BACK INTO PU 08			S				
	0.0-0.02	Improve existing back in spur into South end of PU 08 from Old Military Road		LS	1	200	\$ 200.00
	0.01	Furnish, haul, and place 15 C.Y crushed aggregate surfacing to place at entrance.(19.5 loose material)		C.Y.	15	25	\$ 375.00
Total access between PU 08							\$ 575.00
Total Temp Access Briar Patch Timber Sale							\$ 5,772.00