

**BRIAR PATCH**  
**SPECIFIED ROAD SCHEDULE OF ITEMS**

10/13/2015

Item Number	Item Description & Milepost	C or R <sup>1</sup>	Unit & M of M <sup>2</sup>	Quantity	Road Std. (W,D,S) <sup>3</sup>	Unit Allowance	Estimated Allowance	
	<b>5010-C1</b>							
	M.P. 0.00 - 0.26	R			S			
249 02	Composite Road Construction. Re-construct existing road to crown or out slope to match typical drawing include all excavation and travel way widening. (conserve topsoil and overburden)		Mile DQ	0.26		4500	\$ 1,170.00	
	<b>FR 5010-C1 SPECIFIED ROAD RECONSTRUCTION TOTAL</b>							<b>\$ 1,170.00</b>
	<b>5030-L</b>							
	M.P. 0.00 - 0.35	R			S			
249 02	Composite Road Construction Reconstruct road to crown or out slope left to match typical drawing and allow for cross drainage. Minor entrance widening. Construct turnaround left at the end of the road. (Conserve topsoil/overburden)		Mile DQ	0.35		4800	\$ 1,680.00	
	M.P. 0.00 - 0.01							
301 01	Untreated Aggregate Courses. Furnish, haul, and place 15 CY crushed aggregate surfacing (19.5 C.Y. loose) on approach and radii.		CY DQ	15		25	\$ 375.00	
	<b>FR 5030-L SPECIFIED ROAD RECONSTRUCTION TOTAL</b>							<b>\$ 2,055.00</b>
	<b>GRAND TOTAL SPECIFIED ROAD SCHEDULE OF ITEMS</b>							<b>\$ 3,225.00</b>

<sup>1</sup>C = Construction; R = Reconstruction

<sup>2</sup>Method of Measure

<sup>3</sup>W = Winter; D = Dry Summer; S = Summer

## **BRIAR PATCH TIMBER SALE SPECIFIED ROAD NOTES**

- NOTE:** There may be underground utility lines in unknown locations on this project. Call **MISS DIG THREE** full working days before any work begins. Phone 1-800-482-7171.
- NOTE:** Construct the road bed to conform to the typical detail as noted in the narrative description.
- NOTE:** Additional outlet or lead out ditches may be required at road segment locations to allow for proper drainage needs. Locations for placement shall be determined by the Forest Service and are included in appraised allowance for clearing and shaping.
- NOTE:** During clear and grub operations **all slash** resulting from purchasers operations shall be treated per Special Provision **CT6.7#**.
- NOTE:** All finished roadbeds shall be 12' as shown in the typical details for crowned roads with no ditches, 1' ditches and out sloped roads.
- NOTE:** There are **15 CY of crushed aggregate** surfacing to be placed as directed on FR 5030-L. This volume plus the normal compaction factor of 130% computes to a loose volume of 19.5 CY. **There is no government source available for this project.** Furnished material shall meet gradation requirements for the Michigan Department of State Highway Transportation-Designation 22A. Compact the aggregate by operating spreading and hauling equipment over the full width.
- NOTE:** During gravel hauling operations, "safety signs" shall be placed as directed by the Forest Service. See Sale Area Map for specific sign locations and Traffic Control Plan for sign size and type.