

WORK LIST

STATION	DESCRIPTION OF WORK / PRE-HAUL MAINTENANCE
0.0	Begin road Surface Blading (Motor Grader) at intersection of FM 2262 and NFSR 509. Begin Spot Surface Course Placement of 1197 tons of aggregate along NFSR 509, working West toward NFSR 541 junction. Place aggregate 4 inches deep and 12 feet wide as needed.
1.70	End of road Surface Blading. End of Spot Surface Course Placement. End of pre-haul maintenance. E.O.P.
<ul style="list-style-type: none">• 1030 Surface Blading (Motor Grader) – 1.70 miles @ \$ 1,000 per mile = \$1,700.00• 1040 Spot Surface Course Placement – 1197 tons of aggregate @ \$ 35.00 per ton = \$41,888.00	
Total Pre-Haul Maintenance Cost NFSR 509 = \$43,588.00	