

## WORK LIST

STATION Sta./Mi.	DESCRIPTION OF WORK / PRE-HAUL MAINTENANCE
<b>0.0</b>	Begin road Surface Blading (Motor Grader) at intersection of FM 357/FM 2262 and NFSR 531. Begin <b>Spot</b> Surface Course Placement of 1,288 tons of aggregate along NFSR 531, working north toward NFSR 541. Place aggregate 4 inches deep and 12 feet wide as needed.
<b>1.83</b>	End of road Surface Blading. End of Spot Surface Course Placement. End of pre-haul maintenance. E.O.P.
<ul style="list-style-type: none"><li>• <b>1030 Surface Blading (Motor Grader) – 1.83 miles @ \$ 1,000 per mile = \$1,830.00</b></li><li>• <b>1040 Spot Surface Course Placement – 1288 tons of aggregate @ \$ 35.00 per ton = \$45,089.00</b></li></ul>	
<b>Total Pre-Haul Maintenance Cost NFSR 531= \$46,919.00</b>	