

**CAMP PORI TIMBER SALE**  
**TEMPORARY ROAD PLAN-APPRAISAL ALLOWANCE**

Pg. 1 of 3

DATE: 3/24/2016

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
<b>Turnout lane for PU 3 (west)</b>		<b>Wayside landing off of Pori Road</b>	<b>D</b>				
	0.00-0.03	Construct turnout lane to allow truck to park parallel to Pori Road. Work includes clearing, grubbing and all excavation (allow log truck to park and load completely off of travel way)		L.S.	1	700	\$700
	0.00	Furnish, haul and place 30 cy (39 cy loose) 22-A crushed gravel for approaches and parking surface area. Compaction Method-A.		C.Y./ DQ	30	30	\$900
		<b>Total West temp access PU 03</b>					<b>\$1,600</b>
<b>Back-In to PU 3 (east)</b>		<b>Off of Pori Road</b>	<b>D</b>				
	0.00-0.03	Construct Back-in Landing off of Pori Road to PU 3. Use old existing roadbed.		Each	1	\$350	\$ 350.00
	0.00	Maintain shallow(drivable) ditch along Pori Road. Excavate 40 cy local borrow from approach/radii and place in T-turn roadbed.		L.S.	1	150	\$ 150.00
	0.00	Furnish haul and place 20 cy (26 cy loose) pit run @ approach/radii and use to harden drivable ditch.		C.Y./ DQ	20	30	\$600
	0.00	Furnish haul and place 15 cy (20 cy loose) 22-A crushed gravel at approach/radii-4" depth. Maintain drivable ditch.		C.Y./ DQ	15	30	\$450
		<b>Total for BIL to PU 3 West</b>					<b>\$1,550</b>

**CAMP PORI TIMBER SALE**  
**TEMPORARY ROAD PLAN-APPRAISAL ALLOWANCE**

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
pg. 2 of 3 <b>Back-In to PU 4</b>							
		<b>Off of Pori Road</b>	<b>D</b>				
	0.00-0.03	Construct Back-in Landing off of Pori Road to PU 4.		Each	1	\$350	\$350
	0.00	Furnish haul and place 15 cy (20 cy loose) 22-A crushed gravel at approach/radii-4" depth. Maintain drivable ditch.		C.Y./ DQ	15	30	\$450
		<b>Total for BIL to PU 4</b>					<b>\$800</b>
<b>Temp Rd to PU 6</b>		<b>Off of FFH-16</b>	<b>D</b>				
	0.00-0.05	Construct Back-in Landing off of FFH-16 to PU 6. Construct light ditch to pipe inlet/outlet parallel to FH-16.		Each	1	\$500	\$500
	0.00	Furnish and install 15"x40' CMP (riveted) at approach/radii. Place in ditch line of FFH-16.		LinFt/ DQ	40	14	\$560
	0.00	Remove CMP and approach/radii upon completion of logging operations. Place gravel and fill material on back slope of FFH-16 as berm material. (Purchaser retains possession and must remove pipe from location)		L.S.	1	250	\$250
	0.00	Haul and place 100 cy (130 cy loose) sand fill from Bob Lk pit for construction of approach/radii. Compaction Method-A.		C.Y. DQ	100	10	\$1,000
	0.00	Furnish haul and place 15cy (20cy loose) 22-A crushed gravel for surfacing of appr/radii. Compaction Method-A.		C.Y. DQ	15	30	\$450
	0.00-0.05	Construct roadside ditch left to drain from MP 0.05 to 0.00 to inlet of temp CMP culvert. Out slope entire length of Temp Rd to the right.		L.S.	1	250	\$250
		<b>Total for BIL to PU 6</b>					<b>\$3,010</b>

**CAMP PORI TIMBER SALE**  
**TEMPORARY ROAD PLAN-APPRAISAL ALLOWANCE**

Pg. 3 of 3

DATE: 1/6/2016

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
<b>Typical T-turns</b>	0.03	Construct a total of 3 Typical T-turns at the end of Temp roads and/or System roads throughout the timber sale.		Each	3	250	<b>\$750</b>
<b>T-turn @ end of FR 1639-A</b>	0.03	Construct a T-turn at the end of the road. Additional shaping required and included in cost.		Each	1	350	<b>\$350</b>
<b>T-turn @ end of FR 1640-D</b>	0.03	Construct a T-turn at the end of the road. Additional shaping required and included in cost.		Each	1	350	<b>\$350</b>
<b>T-turn @ end of FR 1670-Z</b>	0.03	Construct a Double T-turn at the end of the road. Additional shaping required and included in cost.		Each	1	450	<b>\$450</b>
<b>Camp Pori Timber Sale Total Temporary Development Work</b>							<b>\$8,860</b>