NOTES:
1. CONTRACTOR SHALL SWEEP ENTIRE AREA TO BE SEALED, CRACK SEAL CRACKS OVER ⅜" WIDTH AND THEN PLACE TYPE 2 SLURRY SEAL OVER ENTIRE SHADED AREA. CARE SHALL BE TAKEN TO KEEP NEW ASPHALT OFF OF EXISTING STRUCTURES AND CONCRETE SURFACES.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR WARNING SIGNAGE ALONG CITY ROAD 500 EAST ACCORDING TO MUTCD STANDARDS.
3. AREA TO RECEIVE SLURRY SEAL APPROX. 4,535 SY
4. PROJECT LOCATION: 500 EAST 256 SOUTH, VERNAL, UTAH.

15' 0 15' 30'
SCALE IN FEET

U. S. Department of Agriculture
FOREST SERVICE
Intermountain Region 4 Engineering
ASHLEY NATIONAL FOREST

DESIGN BY: T.TOUCHARD
CHECK: V.MORTENSON
DRAWING BY: S.BINGHAM
CHECK: V.MORTENSON

APPROVED: ENGINEERING STAFF OFFICER DATE

VERNAL WAREHOUSE PARKING LOT SLURRY SEAL PROJECT

SITE PLAN

PROJECT No.
DRAWING S1
SHEET 1 OF 1