

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT REQUIREMENTS
(02/2002)

Whole Tree Yarding (WTY)

Except for normal breakage, tops and limbs shall be skidded/yarded to the landing attached to the bole. WTY units include: Payment Units: **2 and 4**.

Oversize trees that will be hand felled can be bucked on site.
Payment Units: 5a, 5b, 6

Pile Landing Slash (PL): Slash resulting from harvesting operations and debris accumulated on landings which is from 1 inch in diameter up to 8 inches in diameter, or any piece exceeding 8 feet shall be piled, unless agreed otherwise. Piles shall contain little or no soil. Slash shall not be skidded through groups of reproduction or piled near enough to residual trees to cause damage from pile burning. Payment Units: **All**.

Clean Slash From System Roads

Keep road prism clear of slash. Payment Units: **All**.