

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT
REQUIREMENTS (02/2002)

DESIGNATED PURCHASER WORK
Grouse Salvage TIMBER SALE
SLASH PLAN AND SPECIFICATIONS
Umatilla National Forest Revision 08/09

Spec Cross Ref Nos.	Work Item Identification	Map Symbol	ESTIMATED Amount of Work/Areas to be treated.
4	Whole Tree Yard	WTY	330.2 acres within designated areas
6	Treatment of Landing Slash (described by a map statement)	Map note	All landings used or constructed by Purchaser
7	Treatment of logging slash with-in Existing Roads	Map note	All logging slash within road clearing limits

SPECIFICATIONS PURSUANT TO C6.74# - SLASH TREATMENT REQUIREMENTS
(02/2002)

SLASH PLAN AND SPECIFICATIONS
(UMATILLA NATIONAL FOREST 6/9/08)

4. WHOLE TREE YARDING

Tops and limbs will be left attached to the tree and yarded to the landing or other locations designated by the Forest Service and piled after being severed from the tree. All trees felled shall be yarded to landing.

6. LANDING SLASH

All slash created through the construction and use of the landing area will be machine or hand piled. All slash within 25 feet of the landing clearing will be included landing slash and piled. Machine piles will be constructed with a brush blade or loader. Piles will be compact and free of soil. Piles will be located at least 50 feet from the dripline of live trees or regeneration.

7. SPECIFIED EXISTING ROADS

Logging slash located within the clearing limits of Specified roads will be treated in accordance with slash cleanup methods of the Specified Road Plans. Logging slash within clearing limits of existing roads will be hand or machine piled at locations approved by the Forest Service.