

**NORTH 16 STEWARDSHIP**  
**ROADWORK MAINTENANCE PLAN-APPRAISAL ALLOWANCE**

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
<b>1842-A</b>			<b>D</b>				
	0.00-0.09	Clear, Grub and Reshape road to a Crown or Out slope per the typical drawings.		LS	1.00	\$ 500.00	\$ 500.00
	0.00	Furnish haul and place 20 CY of crushed aggregate to surface entrance. (26 CY loose material)		CY	20	\$ 25.00	\$ 500.00
	0.06	Construct hardened dip with 20 CY pitrun. (26 CY loose material)		LS	1	\$ 600.00	\$ 600.00
	0.08	Furnish haul and place 30 CY of pitrun. (39 CY loose material)		CY	30	\$ 25.00	\$ 750.00
<b>FR 1842-A TOTAL MAINTENANCE</b>							<b>\$ 2,350.00</b>
<b>NORTH 16 STEWARDSHIP TOTAL MAINTENANCE</b>							<b>\$ 2,350.00</b>

S=Summer  
D=Dry Summer  
W=Winter

1 of 1  
Prepared By: Tom Roberts 5/4/2016  
Civil Engineering Technician