

USDA FOREST SERVICE, R-4  
KIGALIA WAREHOUSE DEMOLITION

## SECTION 024100 - WASTE MATERIAL DISPOSAL

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes the loading, handling, hauling, and placing of excess excavation material, unsuitable excavation material, clearing and grubbing debris, and construction and demolition debris.

#### 1.2 MEASUREMENT AND PAYMENT

- A. No payment will be made on this specification as it is included as lump sum in Section 024102.

### PART 2 - PRODUCTS – NOT APPLICABLE

### PART 3 - EXECUTION

#### 3.1 WASTE MATERIAL TO BE HAULED TO A LANDFILL

- A. All demolition materials, garbage, and other refuse generated shall be removed from the project site and legally disposed off of Government property in an approved landfill.
- B. The contractor is responsible for all costs and permits associated with landfill disposal.
- C. The Government is not responsible for waste material upon its departure from the project site.

END OF SECTION 024100

May 2016

## SECTION 024102 - REMOVAL AND DISPOSAL OF STRUCTURES AND OBSTRUCTIONS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Includes removal disposal, and backfilling of existing buildings, concrete pads, and all other items to the extent shown on the Drawings. This item also includes scarifying and re-grading the area around features and structures removed.
- B. Related Sections Include the Following:
  - 1. Section 024100 "Waste Material Disposal."

#### 1.2 MEASUREMENT AND PAYMENT

- A. Payment will be lump sum for removal and disposal of structures and obstructions, including demolition, excavation, backfill, removal, hauling and all incidentals and work required to complete this item.

### PART 2 - PRODUCTS

#### 2.1 SELECT BACKFILL

- A. Select backfill shall be native soil free of stones larger than 6 inches in greatest dimension.

### PART 3 - EXECUTION

#### 3.1 GENERAL

- A. The contractor is responsible for removing any items inside of the warehouse with approval from the COR.
- B. Topsoil stripping and storage, if required, shall comply with the applicable specification.
- C. The Contractor may use any means he may elect to remove the structure or items shown on the drawings to be removed, as long as he provides for the safety of the public and preservation of the surrounding site and structures.
- D. All of a substructure shall be demolished to a depth of 1 foot below the present ground level. All wood, concrete, and metal materials to be removed shall be broken into sufficiently small pieces to enable handling and disposal. All other structures shall be backfilled and the surrounding ground restored to as near normal conditions as practicable in accordance with these specifications.

#### 3.2 DISPOSAL

- A. Disposal of debris shall comply with Section 024100 "Waste Material Disposal."

#### 3.3 FINISHING AND CLEANUP

- A. After the area has been backfilled, the disturbed area shall be finish graded to present a natural appearance and cleaned up by removing all debris and materials left from the removal of items in this Section.