

SCHEDULE OF ITEMS					
		ROAD NUMBER	2600275		
		SEGMENT	0.41-0.93		
		CONSTRUCTION			
		RECONSTRUCTION	X		SPECIFIED
		PROJECT LENGTH (Miles)	0.52		ROADS
ITEM NO.	DESCRIPTION	Pay Unit	QTY	UNIT COST	TOTAL
20304	Removal of corrugated metal pipes and timber bridge.	Lump Sum	All	\$457.29	\$457.29
21201	Linear grading	Mile	0.52	\$17,756.10	\$9,233.17
60803	Paved waterway, type 5	Each	2	\$8,477.06	\$16,954.12
* Designates Contract Quantities				Total	\$26,644.58

SCHEDULE OF ITEMS					
		ROAD NUMBER	2600280		
		SEGMENT	2.14-4.34		
		CONSTRUCTION			
		RECONSTRUCTION	X		SPECIFIED
		PROJECT LENGTH (Miles)	2.20		ROADS
ITEM NO.	DESCRIPTION	Pay Unit	QTY	UNIT COST	TOTAL
15101	Mobilization	Lump Sum	All	\$8,021.64	\$8,021.64
15755	Erosion control & pollution prevention	Each	3	403.84	\$1,211.52
20103	Clearing and grubbing, disposal of tops and limbs (f), logs (f), stumps (f)	Mile	2.20	\$1,121.72	\$2,467.78
20207	Removal of individual trees, disposal of tops and limbs (f), logs (f), stumps (f)	Each	24	\$49.25	\$1,182.00
20253	Removal of individual trees, miscellaneous: disposal of tops & limbs (f) & logs (f)	Each	107	\$54.81	\$5,864.67
20302	Removal of culvert inlet/outlet	Foot	1	\$23.18	\$23.18
20358	Removal of corrugated metal pipe, disposal method (a)	Each	8	\$355.40	\$2,843.20
20419A	Drainage excavation, type culvert outlet ditch	Foot*	200	\$4.67	\$934.00
20419B	Drainage excavation, type culvert inlet channel	Foot*	10	\$7.68	\$76.80
20420	Drainage excavation, type culvert catchbasin	Each	3	\$77.34	\$232.02
20462	Unclassified borrow, compaction method E	Cubic Yard*	1	\$116.33	\$116.33
25101	Placed riprap, class 3	Cubic Yard*	2	\$98.25	\$196.50
30359	Roadway reconditioning, compaction method E	Mile	2.20	\$2,426.47	\$5,338.23
32450	Crushed aggregate surfacing, compaction method B	Cubic Yard*	500	\$41.91	\$20,955.00
60276A	18-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	52	\$32.54	\$1,692.08
60276B	24-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	168	\$38.49	\$6,466.32
60276C	36-inch corrugated aluminized steel pipe, 0.079-inch thickness, method B	Foot	48	\$83.20	\$3,993.60
60710	Reconditioning drainage structures, culvert inlet or outlet	Each	2	\$68.75	\$137.50
62509	Mulching, dry method	Lump Sum	All	\$3,075.17	\$3,075.17
				Total	\$64,827.54

* Designates Contract Quantities

SCHEDULE OF ITEMS					
		ROAD NUMBER	2633700		
		SEGMENT	2.88-3.32		
		CONSTRUCTION			
		RECONSTRUCTION	X		SPECIFIED
		PROJECT LENGTH (Miles)	0.44		ROADS
ITEM NO.	DESCRIPTION	Pay Unit	QTY	UNIT COST	TOTAL
20103	Clearing and grubbing, disposal of tops and limbs (f), logs (f), stumps (f)	Mile	0.44	\$1,121.72	\$493.56
20253	Removal of individual trees, miscellaneous: disposal of tops & limbs (f) & logs (f)	Each	6	\$54.81	\$328.86
20419A	Drainage excavation, type culvert outlet ditch	Foot*	20	\$4.67	\$93.40
30359	Roadway reconditioning, compaction method E	Mile	0.44	\$2,426.47	\$1,067.65
32450	Crushed aggregate surfacing, compaction method B	Cubic Yard*	90	\$41.91	\$3,771.90
60710	Reconditioning drainage structures, culvert inlet or outlet	Each	1	\$68.75	\$68.75
* Designates Contract Quantities				Total	\$5,824.12

SCHEDULE OF ITEMS					
		ROAD NUMBER	2633704		
		SEGMENT	0.00-0.72		
		CONSTRUCTION			
		RECONSTRUCTION	X		SPECIFIED
		PROJECT LENGTH (Miles)	0.72		ROADS
ITEM NO.	DESCRIPTION	Pay Unit	QTY	UNIT COST	TOTAL
15755	Erosion control & pollution prevention	Each	2	\$403.84	\$807.68
20103	Clearing and grubbing, disposal of tops and limbs (f), logs (f), stumps (f)	Mile	0.72	\$1,121.72	\$807.64
20253	Removal of individual trees, miscellaneous: disposal of tops & limbs (f) & logs (f)	Each	9	\$54.81	\$493.29
20358	Removal of corrugated metal pipe, disposal method (a)	Each	2	\$355.40	\$710.80
20419A	Drainage excavation, type culvert outlet ditch	Foot	10	\$4.67	\$46.70
20420	Drainage excavation, type culvert catchbasin	Each	2	\$77.34	\$154.68
25101	Placed riprap, class 3	Cubic Yard*	6	\$98.25	\$589.50
30359	Roadway reconditioning, compaction method E	Mile	0.72	\$2,426.47	\$1,747.06
32450	Crushed aggregate surfacing, compaction method B	Cubic Yard*	320	\$41.91	\$13,411.20
60276B	24-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	56	\$38.49	\$2,155.44
60276D	48-inch corrugated aluminized steel pipe, 0.079-inch thickness, method B	Foot	48	\$83.20	\$3,993.60
60710	Reconditioning drainage structures, culvert inlet or outlet	Each	1	\$68.75	\$68.75
* Designates Contract Quantities				Total	\$24,986.34

SCHEDULE OF ITEMS					
		ROAD NUMBER	2633706		
		SEGMENT	0.00-0.93		
		CONSTRUCTION			
		RECONSTRUCTION	X		
		PROJECT LENGTH (Miles)	0.93		SPECIFIED ROADS TOTAL
ITEM NO.	DESCRIPTION	Pay Unit	QTY	UNIT COST	TOTAL
15755	Erosion control & pollution prevention	Each	1	\$403.84	\$403.84
20103	Clearing and grubbing, disposal of tops and limbs (f), logs (f), stumps (f)	Mile	0.93	\$1,121.72	\$1,043.20
20207	Removal of individual trees, disposal of tops and limbs (f), logs (f), stumps (f)	Each	3	\$49.25	\$147.75
20253	Removal of individual trees, miscellaneous: disposal of tops & limbs (f) & logs (f)	Each	7	\$54.81	\$383.67
20358	Removal of corrugated metal pipe, disposal method (a)	Each	4	\$355.40	\$1,421.60
20419A	Drainage excavation, type culvert outlet ditch	Foot*	60	\$4.67	\$280.20
20419B	Drainage excavation, type culvert inlet channel	Foot*	12	\$7.68	\$92.16
20420	Drainage excavation, type culvert catchbasin	Each	3	\$77.34	\$232.02
20462	Unclassified borrow, compaction method E	Cubic Yard*	8	\$116.33	\$930.64
25101	Placed riprap, class 3	Cubic Yard*	4	\$98.25	\$393.00
30359	Roadway reconditioning, compaction method E	Mile	0.93	\$2,426.47	\$2,256.62
32450	Crushed aggregate surfacing, compaction method B	Cubic Yard*	420	\$41.91	\$17,602.20
60276A	18-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	160	\$32.54	\$5,206.40
* Designates Contract Quantities				Total	\$30,393.30