

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT REQUIREMENTS
(02/2002)

DESIGNATED PURCHASER WORK
TIMBER SALE
SLASH PLAN AND SPECIFICATIONS
Umatilla National Forest Revision 08/01/03

Spec Cross Ref Nos.	Work Item Identification	Map Symbol	ESTIMATED Amount of Work/Areas to be treated.
1	Treatment of Landing Slash	N/A	All landings used or constructed by Purchaser
2	Whole Tree Yard	WTY	<u>820</u> acres.
3	Treatment of logging slash with-in Specified and Existing Roads	Map Note	All logging slash within road clearing limits

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT REQUIREMENTS
(02/2002)

1. Landing Slash

All slash created through the construction and use of the landing area will be machine or hand piled. Machine piles will be constructed with a tractor equipped with a brush blade or loader/excavator. Piles will be compact and free of soil. Piles will be located at least 25 feet from the dripline of live trees or regeneration.

2. WHOLE TREE YARDING (WTY)

Tops and limbs will be left attached to the tree and yarded to the landing or other locations designated by the Forest Service and piled after being severed from the tree

3. Specified and Existing Roads

Logging slash located within the clearing limits of Specified roads will be treated in accordance with the slash cleanup methods of the Specified Road Plans. Logging slash within clearing limits of existing roads will be hand piled at locations approved by Forest Service.