SLEEPY HOLLOW TIMBER SALE

TEMP ROAD COSTS

DATE: 3/29/2016

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
High speed skid trail into #05 to access			**S**				
North section of PU #06							
PU 05/06	0.0-0.45	Clear, grub, and shape to conform to terrain, a high speed skid trail between FR 6994 and PU 5 .		Mile	0.45	$ 2,500.00	$ 1,125.00
		Total Skid Trail PU #05 / #06					**$ 1,125.00**
High Speed Skid trail #06 to access							
the south section of PU 06			**S**				
PU#06	0.00-0.20	Improve footprint of existing non system road for use as a high speed skid trail. Clear, grub, and shape to conform to terrain located between the end of FR6996 and PU 6 .		Mile	0.20	$ 1,500.00	$ 300.00
		Total Temp into South PU #06					**$ 300.00**
TEMP ROAD INTO PU #08 from FR6992-B			**W/DS**				
PU#08	**0.00-0.25**	Contruct temp road into Payment Unit 8 off of FR 6992-B at mp 0.15. . Clear, grub, and shape road to crown or out slope to confrom to terrain. Construct T turn around at point of end.		Mile	0.25	$ 4,000.00	$ 1,000.00
		Total Temp PU #08 from FR 6992-B					**$ 1,000.00**
TEMP ROAD INTO PU #08 from FR6992			**W/DS**				
PU #08	0.00- 0.15	Contruct temp road into North end of Payment Unit 8 off of FR 6992. Clear, grub, and shape road to crown or out slope to confrom to terrain. Construct L turn around at point 100' from point of end to the left.		Mile	0.15	$ 4,000.00	$ 600.00
		Total Temp PU #08 from FR 6992					**$ 600.00**

Prepared by: Mary T. Zelinski/Engineering Technician

SLEEPY HOLLOW TIMBER SALE

TEMP ROAD COSTS

DATE: 3/29/2016

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
TEMP ROAD INTO PU #09			S				
PU #09	0.0-0.04	Clear light brush and small tress. Conserve all topsoil/overburden. Shape existing landing location to t-turnaround		L.S.	1	$ 250.00	$ 250.00
	0.00.00	Furnish haul and place 15 C.Y.crushed aggregate surfacing.(19.5 loose material) and place on entrance and improve radius.		C.Y.	15	$ 28.00	$ 420.00
	0.01	Haul and place 30 C.Y. pit run gravel from North Jaybird Pit.(39 loose material)		C.Y.	30	$ 15.00	$ 450.00
		Total Temp ACCESS into PU #09					**$ 1,120.00**
HIGH SPEED SKID TRAIL INTO PU #10			S				
North Secton of PU #10							
PU #10	0.0-0.14	Clear, grub, and shape to conform to terrain, a high speed skid trail from FR 6992 TO PU 10 .		Mile	0.14	$ 2,000.00	$ 280.00
		Total Skid Trail into PU #10					**$ 280.00**
HIGH SPEED SKID TRAIL INTO PU #10			S				
South secton of PU #10							
PU #10	0.0-0.14	No work required use existing road from FR 6992 TO PU 10					
		Total Skid Trail into PU #10					**$ -**
HIGH SPEED SKID TRAIL INTO PU #11			S				
PU #10	0.0-0.18	Clear, grub, and shape to conform to terrain, a high speed skid trail from FR 6996 and PU 11 .		Mile	0.18	$ 2,000.00	$ 360.00
		Total Skid Trail into PU #11					**$ 360.00**

TOTAL TEMP Road and HIGH SPEED SKID DEVELOPMENTS	**$ 4,785.00**

Prepared by: Mary T. Zelinski/Engineering Technician