Schedule of Items
Cold Springs Salvage Specified Road Package
Klamath National Forest
Siskiyou County, California

Item No	Description	Method of Measure	Unit	Estimated Quantity	Unit Price	Total Cost
Project 45N19						
15101	Mobilization	LSQ	LS	ALL	$ 2,400.00	$ 2,400.00
15714	Soil Erosion & Pollution Prevention Plan	LSQ	LS	ALL	$ 500.00	$ 500.00
20701	Geotextile, Type II-B, without gravel cushion, Function J, Non-woven Neddle Punched	DQ	SY	140	$ 5.00	$ 700.00
25101	Machine Placed Riprap, Class III	DQ	CY	20	$ 65.00	$ 1,300.00
30304	Roadbed Reconditioning, Repair Roadway, Repair Dips, Grade Road	DQ	MILE	5.15	$ 800.00	$ 4,120.00
30311	Aggregate, Type 1-1/2" Minus Surface Aggregate, Commercial Source, Grading C, Compaction C	DQ	CY	60	$ 48.00	$ 2,880.00
60209	Corrugated Metal Elbow for 18" Dia Culvert	AQ	EA	1	$ 800.00	$ 800.00
60211	18" Diameter Corrugated Metal Pipe, 0.079-in thick, 14 -gauge Galvanized Steel, Method A	AQ	LF	40	$ 80.00	$ 3,200.00
60708	Clean/Maintain Culverts in Place	AQ	EA	2	$ 250.00	$ 500.00
					TOTAL THIS PROJECT =	**$ 16,400.00**