

High Thin Timber Sale

SCHEDULE OF ITEMS					
ROAD NUMBER			1928-190		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			0.70		
ITEM NO.	DESCRIPTION	PAY UNIT	QTY	UNIT COST	TOTAL
20253	Removal of individual trees, miscellaneous: disposal of tops & limbs (f) & logs (f)	Each	2	\$89.75	\$179.50
20401	Roadway excavation, compaction method E, finishing method B	Cubic Yard*	26	\$24.10	\$626.60
32207	Aggregate subbase, grading A, compaction method B	Cubic Yard*	600	\$42.15	\$25,290.00
* Designated Contract Quantities				Total	\$26,096.10
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

High Thin Timber Sale

SCHEDULE OF ITEMS					
ROAD NUMBER			1928-210		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			2.68		
ITEM NO.	DESCRIPTION	PAY UNIT	QTY	UNIT COST	TOTAL
15101	Mobilization	Lump Sum	All	\$9,500.00	\$9,500.00
20253	Removal of individual trees, miscellaneous: disposal of tops & limbs (f) & logs (f)	Each	5	\$48.90	\$244.50
20358	Removal of corrugated metal pipe, disposal method (a)	Each	2	\$151.50	\$303.00
20404	Unclassified borrow, compaction method B	Cubic Yard*	50	\$31.75	\$1,587.50
20419	Drainage excavation, type culvert outlet ditch	Foot	225	\$2.60	\$585.00
21201	Linear Grading	Mile	2.68	\$10,757.50	\$28,830.10
25104	Keyed riprap, class 4	Cubic Yard*	3	\$311.50	\$934.50
32207	Aggregate subbase, grading A, compaction method B	Cubic Yard*	1,515	\$41.25	\$62,493.75
60276A	18-inch aluminized steel pipe, 0.064-inch thickness, method B	Foot	172	\$49.30	\$8,479.60
60651	18-inch full circle outlet pipe	Foot	20	\$36.15	\$723.00
62558	Seeding and mulching, dry method	Lump Sum	All	\$1,500.00	\$1,500.00
* Designated Contract Quantities				Total	\$115,180.95
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

High Thin Timber Sale

SCHEDULE OF ITEMS					
ROAD NUMBER			2400-029		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			0.70		
ITEM NO.	DESCRIPTION	PAY UNIT	QTY	UNIT COST	TOTAL
15755	Dewatering structure	Each	5	\$107.00	\$535.00
20253	Removal of individual trees, miscellaneous: disposal of tops & limbs (f) & logs (f)	Each	2	\$90.00	\$180.00
20358	Removal of corrugated metal pipe, disposal method (a)	Each	5	\$325.50	\$1,627.50
20419	Drainage excavation, type culvert outlet ditch	Foot	200	\$1.75	\$350.00
30359	Roadway reconditioning, compaction method E	Mile	0.70	\$3,615.00	\$2,530.50
32207	Aggregate subbase, grading A, compaction method B	Cubic Yard*	125	\$34.00	\$4,250.00
60276A	18-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	40	\$45.50	\$1,820.00
60276B	24-inch corrugated aluminized steel pipe, 0.079-inch thickness, method B	Foot	234	\$39.75	\$9,301.50
60651	18-inch full-circle outlet pipe	Foot	10	\$35.50	\$355.00
* Designated Contract Quantities				Total	\$20,949.50
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

High Thin Timber Sale

SCHEDULE OF ITEMS					
ROAD NUMBER		2404			
CONSTRUCTION					
RECONSTRUCTION		X			
PROJECT LENGTH (MILES)		0.42			
ITEM NO.	DESCRIPTION	PAY UNIT	QTY	UNIT COST	TOTAL
15755	Dewatering structure	Each	2	\$108.00	\$216.00
20253	Removal of individual trees, miscellaneous: disposal of tops & limbs (f) & logs (f)	Each	2	\$90.00	\$180.00
20358	Removal of corrugated metal pipe, disposal method (a)	Each	2	\$307.00	\$614.00
32207	Aggregate subbase, grading A, compaction method B	Cubic Yard*	20	\$35.00	\$700.00
60276B	24-inch corrugated aluminized steel pipe, 0.079- inch thickness, method B	Foot	82	\$40.75	\$3,341.50
* Designated Contract Quantities				Total	\$5,051.50
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					