

SCHEDULE OF ITEMS					
ROAD NUMBER			1928-000		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			0.67		
ITEM NUMBER	DESCRIPTION 1928-000	UNIT	QUANTITY	UNIT COST	TOTAL
20253	Removal of individual trees, miscellaneous: disposal of tops and limbs: (f) and logs: (f)	Each	2	\$ 60.00	\$ 120.00
30311A	Roadway reconditioning, surfacing, compaction method B	Mile	0.67	\$ 5,017.00	\$ 3,361.39
32207	Subbase grading A, compaction method B	Cubic Yard*	30	\$ 59.00	\$ 1,770.00
* Denotes contract quantity				TOTAL	\$ 5,251.39
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

Road 1928-000

SCHEDULE OF ITEMS					
ROAD NUMBER			1928-102		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			0.22		
ITEM NUMBER	DESCRIPTION 1928-102	UNIT	QUANTITY	UNIT COST	TOTAL
21201	Linear grading	Mile	0.22	\$ 18,470.00	\$ 4,063.40
32207	Subbase grading A, compaction method B	Cubic Yard*	10	\$ 58.00	\$ 580.00
32222	Pit run, maximum size 3-inches, compaction method B	Cubic Yard*	510	\$ 45.00	\$ 22,950.00
60276A	18-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	30	\$ 43.00	\$ 1,290.00
* Denotes contract quantity				TOTAL	\$ 28,883.40
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

Road 1928-102

SCHEDULE OF ITEMS					
ROAD NUMBER			1928-195		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			0.65		
ITEM NUMBER	DESCRIPTION 1928-195	UNIT	QUANTITY	UNIT COST	TOTAL
20253	Removal of individual trees, miscellaneous: disposal of tops and limbs: (f) and logs: (f).	Each	5	\$ 130.00	\$ 650.00
20420	Drainage excavation, type catch basin	Each	2	\$ 122.30	\$ 244.60
20426	Grade dips, rolling dip	Each	1	\$ 1,105.00	\$ 1,105.00
20701	Earthwork geotextile type II-A	Square Yard*	48.0	\$ 5.00	\$ 240.00
21201	Linear grading	Mile	0.65	\$ 13,590.00	\$ 8,833.50
25104	Keyed riprap, class 4	Cubic Yard*	2	\$ 78.00	\$ 156.00
32222	Pit run, maximum size 3-inches, compaction method B	Cubic Yard*	820	\$ 36.00	\$ 29,520.00
* Denotes contract quantity				TOTAL	\$ 40,749.10
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

SCHEDULE OF ITEMS					
ROAD NUMBER			1928-210		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			2.82		
ITEM NUMBER	DESCRIPTION 1928-210	UNIT	QUANTITY	UNIT COST	TOTAL
20253	Removal of individual trees, miscellaneous: disposal of tops and limbs: (f) and logs: (f)	Each	5	\$ 188.00	\$ 940.00
20419B	Drainage excavation, type culvert outlet ditch	Foot	30	\$ 10.30	\$ 309.00
20420	Drainage excavation, type catch basin	Each	1	\$ 130.00	\$ 130.00
25104	Keyed riprap, class 4	Cubic Yard*	2	\$ 106.00	\$ 212.00
30311B	Roadway reconditioning, surfacing, compaction method B	Mile	2.82	\$ 2,050.00	\$ 5,781.00
32207	Subbase grading A, compaction method B	Cubic Yard*	100	\$ 60.00	\$ 6,000.00
60652	18-inch full-circle outlet pipe with aluminized coating	Foot	10	\$ 58.00	\$ 580.00
* Denotes contract quantity				TOTAL	\$ 13,952.00
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

SCHEDULE OF ITEMS					
ROAD NUMBER			1931-000		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			1.13		
ITEM NUMBER	DESCRIPTION 1931-000	UNIT	QUANTITY	UNIT COST	TOTAL
15101	Mobilization	Lump Sum	All	\$ 15,243.00	\$ 15,243.00
15755	Dewatering structure	Each	2	\$ 1,129.00	\$ 2,258.00
20253	Removal of individual trees, miscellaneous: disposal of tops and limbs: (f) and logs: (f)	Each	4	\$ 190.00	\$ 760.00
20358	Removal of corrugated metal pipe, disposal method (a)	Each	3	\$ 210.00	\$ 630.00
20404	Unclassified borrow, compaction method B	Cubic Yard*	100	\$ 16.00	\$ 1,600.00
20419A	Drainage excavation, type culvert inlet ditch	Foot	10	\$ 10.30	\$ 103.00
25104	Keyed riprap, class 4	Cubic Yard*	16	\$ 44.00	\$ 704.00
32207	Subbase grading A, compaction method B	Cubic Yard*	1,000	\$ 49.00	\$ 49,000.00
60276B	24-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	42	\$ 54.00	\$ 2,268.00
60276C	36-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	126	\$ 73.00	\$ 9,198.00
62558	Seeding and mulching, dry method	Lump Sum	All	\$ 2,440.00	\$ 2,440.00
* Denotes contract quantity				TOTAL	\$ 84,204.00
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

Road 1931-000

SCHEDULE OF ITEMS					
ROAD NUMBER			1931-101		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			0.13		
ITEM NUMBER	DESCRIPTION 1931-101	UNIT	QUANTITY	UNIT COST	TOTAL
20419A	Drainage excavation, type inlet ditch	Foot	120	\$ 1.80	\$ 216.00
21201	Linear grading	Mile	0.13	\$ 14,820.00	\$ 1,926.60
32222	Pit run, maximum size 3-inches, compaction method B	Cubic Yard*	300	\$ 45.00	\$ 13,500.00
60276A	18-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	30	\$ 38.00	\$ 1,140.00
* Denotes contract quantity				TOTAL	\$ 16,782.60
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

Road 1931-101

SCHEDULE OF ITEMS					
ROAD NUMBER			1931-209		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			0.27		
ITEM NUMBER	DESCRIPTION 1931-209	UNIT	QUANTITY	UNIT COST	TOTAL
15755	Dewatering structure	Each	1	\$ 380.00	\$ 380.00
20103	Clearing and grubbing, disposal of tops and limbs (f), logs (i), stumps (f)	Mile	0.27	\$ 10,621.00	\$ 2,867.67
20253	Removal of individual trees, miscellaneous; disposal of tops & limbs (f) & logs (f).	Each	4	\$ 188.00	\$ 752.00
20358	Removal of corrugated metal pipe, disposal method (a).	Each	1	\$ 110.00	\$ 110.00
25104	Keyed riprap, class 4	Cubic Yard*	1	\$ 265.00	\$ 265.00
30359	Roadway reconditioning, compaction method E	Mile	0.27	\$ 3,805.00	\$ 1,027.35
32207	Subbase grading A, compaction method B	Cubic Yard*	250	\$ 51.00	\$ 12,750.00
60276A	18-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	30	\$ 54.00	\$ 1,620.00
* Denotes contract quantity				TOTAL	\$ 19,772.02
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

SCHEDULE OF ITEMS					
ROAD NUMBER			2409-000		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			1.08		
ITEM NUMBER	DESCRIPTION 2409-000	UNIT	QUANTITY	UNIT COST	TOTAL
20419B	Drainage excavation, type culvert outlet ditch	Foot	40	\$ 11.30	\$ 452.00
20420	Drainage excavation, type catch basin	Each	1	\$ 130.30	\$ 130.30
32207	Subbase grading A, compaction method B	Cubic Yard*	50	\$ 62.00	\$ 3,100.00
* Denotes contract quantity				TOTAL	\$ 3,682.30
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

Road 2409-000