

**ADDITIONAL SALE PREPARATION INFORMATION:** This timber sale contains seven (7) Payment Units. Payment Units 1, 3, 4, and 7 are Cut Tree Marked (CTM). In Payment units 1, 3, 4, and 7 the timber to be cut is designated by **Blue** paint marks at the base and eye level Sawtimber trees are designated with 2 base spots and softwood-other (small roundwood trees) with 1 base spot. Payment units 2,5 and 6 are regeneration Clear Cut unit (CC) all pine trees meeting utilization standards in AT2 are designated for cutting. No hardwood is to be removed. All boundaries are marked with Orange paint. **Unless designated by the Forest Service, trees will not be removed outside these designated boundaries.**

**VOLUME AND SAMPLING INFORMATION:** Sawtimber volumes are based on the CCF tree measurement rule. Sawtimber and pulpwood/topwood volume were determined from tree measurement volume equations for the Angelina National Forest. Sawtimber volume to be sold reflects reduction for defect and is graded. The pine sawtimber is approximately 89% Loblolly Pine, 8% Shortleaf Pine, 3% Longleaf Pine and 0% Slash.

The following methods were used to estimate timber volume and data:

**Cut Tree Marking (CTM)** – Payment Units 1,3,4 and 7 were cruised and volumes estimated utilizing the Sample Tree Measurement method. Sampling intervals for the various products/diameter classes are as follows:

Payment Unit	Species/Product	<b><u>Sample Tree Measurement</u></b>		<b><u>100% TreeMeasurement</u></b>
		DBH Range Sampled	Sample Interval	DBH Range
1,3,4,7	Softwood-Other	5.0 – 10.9”	1 in 125	11.0”+
1,3,4,7	Pine Sawtimber	11.0”+	(See Cruise)	26.0”+

**Clear Cut (CC)** – Payment Units 2,5 and 6 was cruised and volumes estimated utilizing the Point Count Measure Tree method. Measurements were taken on thirty-four (34) variable radius plots using a 10 BAF prism and volume estimated on 123 acres.

Payment Unit	Species/Product	<b><u>PCMTRE Measurement</u></b>		<b><u>100% TreeMeasurement</u></b>
		DBH Range Sampled	Sample Interval	DBH Range
2,5,6	Softwood-Other	5.0 – 10.9”	Variable Radius Plot	N/A
2,5,6	Pine Sawtimber	11.0”+	Variable Radius Plot	N/A

**RELEASE OF PAYMENT UNITS FOR CUTTING.** Contractor must get a written release from the Forest Service before entering any payment unit. Before a payment unit can be accepted as completed, cutting and all other contract obligations must be completed. Unless otherwise agreed, no more than two (2) payment units may be operated at one time.

**EQUIPMENT CLEANING:** Prior to moving Off-Road equipment onto the Sale Area, contractor shall inform the Forest Service of the most recent area of equipment use due to the presence of invasive species (Cogon Grass) within Jasper County and western Louisiana. If equipment has been used within areas containing Cogon Grass or other invasive species of concern, cleaning of Off-Road equipment will be required prior to moving on the Sale Area. Off-Road equipment includes all logging and construction equipment, **EXCEPT** for log trucks, chip vans, service vehicles, water trucks, pickup trucks, cars and similar vehicles. **See contract provision KT-GT.3.5 for additional information.**

**USE OF ROADS.** Trucks used in hauling timber from this sale over roads under Forest Service jurisdiction are subject to State and County load, weight, length, height and width limitations. Any exceptions to these limitations are posted by individual road or road segment. Prospective bidders are urged to check out any questions on haul route with the District Ranger before submitting bids. **In addition, road use permits may be required by the State or County for use of roads under their jurisdiction. Purchaser is responsible for obtaining proper authorization for use of roads.**

**ROAD MAINTENANCE.** The purchaser will be required to perform road maintenance on roads used, which the Forest Service maintains, commensurate with purchaser's use of such roads. Road maintenance requirements are estimated for a proposed haul route. Any change from the proposed haul route may necessitate a change in the roads to be maintained or in the amount of required deposit for road maintenance. The estimated cost of road maintenance has been allowed for the appraisal. **SEE SPECIAL PROVISIONS KT-FT.3.1#**

**TEMPORARY ROADS.** The location and clearing widths of all temporary roads and landings shall be approved by the Forest Service before construction or use is started. The estimated quantity of timber in this sale does not include timber within the clearing limits of Temporary Roads. Any additional timber requiring removal will be designated by the Forest Service and paid for at contract rates prior to cutting.

Contractor shall maintain all erosion control structures such as waterbars and broad-based dips in a functional condition during operations. Contractor shall reshape road surface and close all Temporary Roads prior to prolonged periods of non-use or when use is completed. Outside berms shall be removed by pulling the material back onto the road surface. Prior to final road closure, unless otherwise agreed, the road surface shall be ripped or scarified to reduce runoff and aid in revegetation.

**EROSION CONTROL.** Contractor will install waterbars as logging in a payment unit and use of roads is completed. At this time, temporary and skid roads will be bladed to pull outside berms, reshape road surface to assure adequate surface drainage, construct waterbars where designated, and install barricades to block temporary roads to normal vehicular traffic where designated.

The Forest Service will **not** agree to perform the waterbarring and road blocking work for the purchaser. The purchaser shall also install temporary waterbars if logging operations are stopped for prolonged periods prior to completing a payment unit. The Forest Service will **not** perform such temporary waterbarring work.

Where waterbars or similar measures won't provide satisfactory erosion control, purchaser shall vegetate areas where soil disturbance will result in soil losses from erosion. Areas specified by the Forest Service will be fertilized with 300 pounds of 13-13-13 commercial fertilizer (or equivalent) per acre and seeded in accordance with the sample contract Special Provision KT-GT.6.0.1# specifications.

The Forest Service will **not** agree to perform the seeding and fertilizing work for the Contractor.

**NORMAL OPERATING SEASON.** The normal operating season is From **January 1<sup>st</sup> - December 31<sup>st</sup>**.

**SLASH DISPOSAL/TREATMENT.** Contractor will be required to remove all logging slash and other debris resulting from logging operations off cleared pipelines and powerline rights-of-way, off road surfaces, shoulders, and draining ditches, off trails, and out of protected streamcourses shown on the Sale Area Map.

If slash is deposited on other ownership, Contractor shall promptly remove such logging slash.

**PROTECTION OF STREAMCOURSES.** Culverts or temporary bridges will be required where temporary and skid roads cross protected streamcourses shown on Contract Area Map unless otherwise agree. The location of these crossings shall be approved in advance by the Forest Service. Contractor shall furnish and install such culverts or temporary bridges and shall remove them upon completion of operations.

Unless otherwise agreed, all vehicles are prohibited within a **Orange**-marked boundary along either side of protected streamcourses, or wet areas, except as necessary to construct or remove streamcrossing structures. The KT-GT.5# Streamcourse Protection provision discusses this in detail.

**PRE-WORK CONFERENCE.** A pre-work conference will be held with the designated representatives before contractor begins operations. The purpose of the conference is to ensure designated representatives have a clear understanding of the contract requirements and obligations. The time and place for conference will be arranged by Forest Service.