

# Little Falls Timber Sale

## TEMP DEVELOPMENT PLAN

PAGE 1 OF 1

DATE:

8/11/2016

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
<b>Temporary back in INTO PU 01</b>			<b>S</b>				
PU #01	0.0 - 0.03	Construct temp back in off of FR 5250 into Payment Unit 01		LS	1	\$ 500.00	\$ 500.00
	0.0 - 0.01	Haul, and place 30 cubic yards pit run gravel from North Jaybird Pit. (39 CY loose)		CY	30	\$ 15.00	\$ 450.00
<b>Total Temp into PU 01</b>							<b>\$ 950.00</b>
<b>Construct high speed skid from PU 05 into PU 02</b>			<b>S</b>				
PU #2	0.0 - 0.07	Construct High speed skid trail from pu 05 into Southeast pu 02		Mile	0.07	\$ 2,500.00	\$ 175.00
<b>Total High Speed Skid Trail into PU 02</b>							<b>\$ 175.00</b>
<b>Construct Tempory Road into Payment unit #06</b>			<b>S</b>				
PU #6	0.0 - 0.13	Start on unauthorized road and construct temporary road into PU 06		Mile	0.13	\$ 3,800.00	\$ 494.00
	0.07-0.09	Haul, and place 30 cubic yards pit run gravel from North Jay Bird Pit to surface hill. (39 CY loose)		CY	30	\$ 15.00	\$ 450.00
<b>Total Temp into PU 06</b>							<b>\$ 944.00</b>
<b>Construct Tempory Road into Payment unit #11</b>			<b>S</b>				
PU #11	0.0 - 0.16	Improve existing road to temporary road standard into PU 11		Mile	0.16	\$ 4,000.00	\$ 640.00
	0.0-0.02	Widen and improve entrance including excavation		L.S.	1	\$ 200.00	\$ 200.00
	0.0-0.02	Haul, and place 45 cubic yards pit run gravel to surface entrance from North Jaybird Pit. (58.5 CY loose)		CY	45	\$ 15.00	\$ 675.00
<b>Total Temp into PU 11</b>							<b>\$ 1,515.00</b>
<b>Construct Tempory Road into Payment unit #12</b>			<b>S</b>				
	0.0-0.26	Construct temporary road into payment unit 12 from FR 5255-L		Mile	0.26	\$ 3,400.00	\$ 884.00
<b>Total Temp into PU # 12</b>							<b>\$ 884.00</b>
<b>Temporary road into PU 15</b>			<b>S</b>				
PU #15	0.0 - 1.80	Improve existing road with minor spot blading/shaping as directed by the Forest Service.includes constion spur into FS lands.		L.S.	1	\$ 2,000.00	\$ 2,000.00
	0.57-0.58	Haul and place 45 cubic yards pit run. (58.5 loose material)		C.Y..	45	\$ 15.00	\$ 675.00
<b>Total Temp into PU 15</b>							<b>\$ 2,675.00</b>
		Haul and place 100 cubic yards pit run surfacing used on any temporary segment.		C.Y.	100	15	\$ 1,500.00
<b>LITTLE FALLS TOTAL TEMP DEVELOPMENTS</b>							<b>\$ 8,643.00</b>

Prepared by: Michael Jarvi/Civil Engineering Technician