



1. LOCATION AND ORIENTATION OF ALL STRUCTURES AND HANDPUMPS SHALL BE APPROVED BY THE CONTRACTING OFFICER PRIOR TO INSTALLATION.
2. THE LOCATION OF ALL FAMILY UNITS AND TENT PADS SHALL BE STAKED BY THE CONTRACTOR AND APPROVED BY THE CONTRACTING OFFICER PRIOR TO CONSTRUCTION. IF POSSIBLE, FAMILY UNITS AND TENT PADS SHALL BE LOCATED TO AVOID REMOVAL OF TREES.
3. AN EXTENSIVE EFFORT HAS BEEN MADE TO LOCATE ALL POSSIBLE EXISTING UTILITY LINES FROM RECORDS AND EVIDENCE IN THE FIELD, HOWEVER, THE COMPLETENESS OR ACCURACY OF THE LOCATIONS SHOWN CANNOT BE GUARANTEED. THE CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING THE LOCATION OF ALL EXISTING UTILITIES. ANY LOCATION STAKED OR SHOWN IS APPROXIMATE. CALL 811 TO HAVE UTILITIES MARKED BEFORE BEGINNING CONSTRUCTION. IF CONFLICTS ARE FOUND, NOTIFY THE CONTRACTING OFFICER.
4. INSTALL THE WATER SYSTEM WELLS ACCORDING TO APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS FOR PUBLIC DRINKING WATER SYSTEMS.
5. WELL LOCATION WILL BE STAKED BY THE CONTRACTING OFFICER.
6. HARVEST TOPSOIL FROM AREAS OF NEW CONSTRUCTION ACCORDING TO THE SPECIFICATIONS AND REUSE TO REVEGETATE DISTURBED AREAS.
7. SEE "C" SHEETS FOR ROADWAY DESIGN, INCLUDING CULVERTS.
8. SEE "P" SHEETS FOR PATHWAY DESIGN, INCLUDING CULVERTS.
9. SEE SHEET D17 FOR SIGN TABLE AND DETAILS.
10. TREE CUTTING IS NOT ALLOWED FROM MAY 15 TO AUGUST 15 DUE TO BIRD NESTING AND MIGRATING PERIOD.
11. ALL CAMPSITE SPURS TO HAVE AGGREGATE SURFACE.

- REMOVE BARRIER ROCKS AS NECESSARY TO ACCESS NATIVE SURFACE ROAD. REPLACE BARRIER ROCKS WHEN WORK IS COMPLETE.

