

Schedule of Items

FR 216

Pay items	Description	Pay Unit	Estimated Quantity	Unit Price	Extended Total	Engineer's Estimated Unit Price	Engineer's Extend Total
15101	Mobilization (Lump Sum)	All	1	\$1,550.00	\$1,550.00	\$1,736.00	\$1,736.00
20301	Removal Of Culvert	Each	4	\$110.00	\$440.00	\$120.00	\$480.00
25102	Placed Riprap, class R-3 limestone	Ton	10	\$54.00	\$540.00	\$59.00	\$590.00
30103	Aggregate Base , grading DSA limestone, method A	Ton	4	\$25.00	\$100.00	\$28.00	\$112.00
30103	Aggregate Base , grading PA- 2A, compaction method A	Ton	207	\$23.00	\$4,761.00	\$26.00	\$5,382.00
30318	Road reconditioning	Mile	1.1	\$1,200.00	\$1,320.00	\$1,350.00	\$1,485.00
60202	73" span, 55"rise, alumized type 2, corrugated steel pipe, .138 inch thickness, method A	Linear Foot	30	\$216.00	\$6,480.00	\$223.00	\$6,690.00
60263	18 inch aluminized type 2, corrugated steel pipe, 0.064 inch thickness, method A	Linear Foot	90	\$31.50	\$2,835.00	\$35.50	\$3,195.00
62503	Seeding, hydraulic or dry method (lump sum)	All	1	\$1,300.00	\$1,300.00	\$1,520.00	\$1,520.00
TOTAL					\$19,326.00		\$21,190.00