

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT REQUIREMENTS

SLASH PLAN AND SPECIFICATIONS
(Umatilla National Forest 6/9/08)

1. MACHINE SLASH PILING SPECIFICATIONS—LANDINGS AND DECKS (MP)

Landing Slash is required to be piled in all Cutting Units

Purchaser shall machine pile slash within the designated cutting area as indicated on the Sale Area Map.

Piles shall be constructed using any machine with the ability to construct piles that will meet CT6.74# specification as described below.

1.) Piles will be located at least 25 feet from the drip line of live trees. Piles shall not be located on road surfaces or ditchlines unless approved by Forest Service.

2) The Purchaser shall pile all slash located within the used landing area that is greater than 2 inch in diameter and 3 feet long. Any material protruding more than 6 feet from the perimeter of the pile will be cut off and placed in the pile.

3) As is practical, all piles shall be free of dirt and the duff layer will not be disturbed during piling operations. Unacceptable piles will be disassembled and repiled, at the discretion of the Forest Service.

3) The Forest Service may approve substitution of any of the above terms, if deemed necessary by the timber sale administrator through consultation with Ranger District fuels person

2. WHOLE TREE YARDING (WTY)

In all Cutting Units, the Purchaser shall leave all limbs attached to logs and also leave the top attached to the top log. Limbs and tops shall be removed at the landing.

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT REQUIREMENTS
(02/2002)

DESIGNATED PURCHASER WORK
 Wilkins TIMBER SALE
 SLASH PLAN AND SPECIFICATIONS
 Umatilla National Forest Revision 08/09

Spec Cross Ref Nos.	Work Item Identification	Map Symbol	ESTIMATED Amount of Work/Areas to be treated.
1	Machine Slash Piling of decks and landings	Map Note	<u>962</u> acres within designated areas
2	Whole Tree Yard	Map Note	<u>962</u> acres within designated areas