

813 – Spot Surfacing  
Umatilla National Forest  
(04/10)

813.01

Service Required

Furnish specified surfacing materials, and place and compact as shown on the work list.

813.02

Performance Standard

***Spot Surfacing***

Spot surfacing is complete when:

- all specified surfacing materials have been placed, processed, and compacted (as shown on the work list or drawings),
- oversized materials have been removed from the finished course,
- damages to haul routes have been repaired.

***Requirement for Non-native Invasive Plant Species Control***

Prior to entering National Forest lands, all road maintenance equipment shall be cleaned to minimize the potential spread of non-native invasive plant species. Prudent actions, such as washing or using compressed air, shall be taken to clean equipment, prior to moving from one project area to another within the National Forest, to ensure that these species are not spread.

813.03

Location of Work

Work will apply to those areas shown on the work list. Additional work may be ordered by the Contracting Officer.

813.04

Measurement

Measurement will be made of each item or unit of work, as shown in the Schedule of Items, completed and accepted in accordance with the contract provisions, specifications, and drawings.

- Cubic Yard: The quantity will be the number of cubic yards measured in the vehicles.
- Ton: The quantity will be measured as shown on certified scale tickets.

813.05  
Payment

Accepted quantities will be paid at the contract price per unit of measurement for the Section 813 pay items listed in the Schedule of Items. Payment will be full compensation for the work prescribed in this section.

***NOTE: Mobilization is incidental to pay items.***

<u>Pay Item</u>		<u>Pay Unit</u>
813(01)	Spot Surfacing, Gradation _____	Cubic Yard
813(03)	Spot Surfacing, Gradation _____	Ton

## 813.06

## Acceptable Quality Levels

Description	<u>Major Defect</u>	Allowable Major Defects	Action Required to Correct Non-allowable Major Defects	<u>Minor Defect</u>	Allowable Minor Defects	Action Required to Correct Non-allowable Minor Defects
Aggregate Quality	Does not meet specified requirements	None	Replace with aggregate meeting specified requirements	<b>Oversized rocks</b>	<b>1, no larger than 3" in any dimension, in any 5,000 square-foot area</b>	<b>Remove oversized rock</b>
	Contaminated with unsuitable materials	None	Replace with untainted aggregate			
Aggregate Placement	Placed in locations other than those designated	None	Remove aggregate from non-designated locations			
	Uniform, compacted thickness is greater than specified	None	Reduce thickness and re-compact until the specified uniform, compacted thickness is attained	<b>Compacted thickness is not uniform</b>	<b>Minor intermittent irregularities</b>	<b>Blade and re-compact until a uniform compacted thickness is attained, as specified</b>
Aggregate Processing	Material segregation is visibly apparent	None	Adjust moisture content of aggregate until suitable for effective mixing, then process until segregation is no longer apparent			
Compaction (when required)	Visual displacement is detectable beneath spreading equipment	None	Adjust moisture content of aggregate until suitable for compaction, then compact until visual displacement ceases			