

*Sale Name: Burton Tract WMA Habitat Improvement Project*

**Sam Houston N.F.**

NFSR 2033 WORK LIST

STATION

MP DESCRIPTION OF WORK

0.0	Begin project at the junction NFSR 2033 and Hidden Forest Rd. (NFSR 2002) Start blading (Dozer). Place 12 tons road base (limestone).
0.027	Begin placing 12 tons road base (limestone).Clean existing lead off ditch left.
0.081	Clean existing lead off ditch right.
0.126	Clean existing lead off ditch right.
0.150	Clean existing lead off ditch right.
0.175	Clean existing lead off ditch left.
0.213	Clean existing lead off ditch left.
0.358	Clean existing lead off ditch left.
0.418	Clean existing lead off ditch left.
0.820	Begin placing 25 tons 1"X 3" oversize road base (limestone).
1.102	Begin placing 50 tons 1"X 3" oversize road base (limestone).
1.222	E.O.P.

1040-Spot Surface Course Placement 75 tons @ \$38.00:	\$2,850.00
1"X 3" oversize (Limestone)	
1040- Spot Surface Course Placement 25 tons @ \$29.50:	\$737.50
(Limestone)	
<u>1020- Blading (Grader, Dozer)1 .222 @ \$1,000.00 mile:</u>	<u>\$1,222.00</u>

**Total Prehaul Maintenance Cost for NFSR 2033: \$4,809.50**