Thor Thin Timber Sale

	SCHEDULE O	F ITEMS			
ROAD NUMBER			1919		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			3.70		
ITEM NO.	DESCRIPTION	PAY UNIT	QTY	UNIT COST	TOTAL
15101	Mobilization	Lump Sum	All	\$4,158.50	\$4,158.50
20103	Clearing and grubbing, disposal of tops and limbs (f), logs (i), stumps (f)	Mile	0.78	\$2,474.96	\$1,930.47
20358	Removal of corrugated metal pipe, disposal method (a)	Each	2	\$119.53	\$239.06
20419	Drainage excavation, type culvert outlet ditch	Foot	90	\$1.74 -	\$156.60
23051	Roadside brushing, disposal method (1)	Mile	3.70	\$2,582.72	\$9,556.06
30359	Roadway reconditioning, compaction method E	Mile	3.70	\$2,739.48	\$10,136.08
32203	Aggregate base, grading A, compaction method B	Cubic Yard*	40	\$36.55	\$1,462.00
60276A	18-inch corrugated aluminized steel pipe, 0.079 inch thickness, method B	Foot	54	\$30.02	\$1,621.08
60276B	24-inch corrugated aluminized steel pipe, 0.079 inch thickness, method B	Foot	46	\$38.12	\$1,753.52
62509	Mulching, dry method	Lump Sum	All	\$825.00	\$825.00
* Designated Contract Quantities				Total	\$31,838.37
Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					

Thor Thin Timber Sale

	SCHEDULE O	FITEMS			
ROAD NUMBER			1920		
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			1.30		
ITEM NO.	DESCRIPTION	PAY UNIT	QTY	UNIT COST	TOTAL
15755	Erosion control and pollution prevention	Each	1	\$148.85	\$148.85
20358	Removal of corrugated metal pipe, disposal method (a)	Each	3	\$212.17	\$636.51
20419	Drainage excavation, type culvert outlet ditch	Foot	20	\$1.96	\$39.20
23051	Roadside brushing, disposal method (1)	Mile	0.69	\$789.14	\$544.51
30359	Roadway reconditioning, compaction method E	Mile	0.69	\$1,980.86	\$1,366.79
32203	Aggregate base, grading D, compaction method B	Cubic Yard*	210	\$31.76	\$6,669.60
60276A	18-inch corrugated aluminized steel pipe, 0.079 inch thickness, method B	Foot	40	\$31.69	\$1,267.60
60276B	24-inch corrugated aluminized steel pipe, 0.079 inch thickness, method B	Foot	82	\$38.63	\$3,167.66
* Designated Contract Quantities Total \$13,840. Payment will be made on actual work performed as described in FP-03 109.01 unless otherwise noted.					\$13,840.72 ed

Thor Thin Timber Sale

	SCHEDULE O	F ITEMS			
ROAD NUMBER			1920-660		
CONSTRUCTION					
RECONSTRUCTION			X		
PROJECT LENGTH (MILES)			0.74		
ITEM NO.	DESCRIPTION	PAY UNIT	QTY	UNIT COST	TOTAL
15755	Erosion control and pollution prevention	Each	1	\$254.51	\$254.51
20358	Removal of corrugated metal pipe, disposal method (a)	Each	1	\$230.29	\$230.29
20419	Drainage excavation, type culvert outlet ditch	Foot	60	\$2.00	\$120.00
23051	Roadside brushing, disposal method (1)	Mile	0.74	\$1,236.31	\$914.87
30359	Roadway reconditioning, compaction method E	Mile	0.74	\$1,711.26	\$1,266.33
32203	Aggregate base, grading A, compaction method B	Cubic Yard*	10	\$32.82	\$328.20
60276	24-inch corrugated aluminized steel pipe, 0.079 inch thickness, method B	Foot	40	\$39.27	\$1,570.80
* Designate	 d in FP-03 10	9.01 unless	Total otherwise not	\$4,685.00 ed.	