ROAD NO.	STATION	ITEM NO.	QUAN	UNIT	DESCRIPTION OF WORK	REMARKS
693B	5+10	32232B	280	CY	Start Base Course Aggregate, Furnish and Place, Grading D, Compaction Method B	Place 4 inches of base course aggregate on existing traveled way and turnouts; in place compacted depth.
	20+00	32232B			End Base Course Aggregate	
	30+25	32232B	1260	CY	Start Base Course Aggregate, Furnish and Place, Grading D, Compaction Method B	
	98+00	32232B			End Base Course Aggregate	
	99+25	32232B	70	CY	Start Base Course Aggregate, Furnish and Place, Grading D, Compaction Method B	
	102+65	32232B			End Base Course Aggregate	
	115+25	32232B	140	CY	Start Base Course Aggregate, Furnish and Place, Grading D, Compaction Method B	
	122+50	32232B			End Base Course Aggregate	
	128+50	32232B	60	CY	Start Base Course Aggregate, Furnish and Place, Grading D, Compaction Method B	
	131+40	32232B			End Base Course Aggregate	
		32232B	**1810**	**CY**	**Total required volume of in-place compacted base course aggregate**	

U. S. Department of Agriculture
FOREST SERVICE
Boise National Forest
Engineering
REGION 4

DESIGN BY: D.Harris CHECK: D.Woras
DRAWING BY: D.Harris CHECK: D.Woras
DRAWING NUMBER:

Description of Work NFSR #693B for Stewardship Projects K-G.9#

Pinney Slope Stewardship

SHEET