

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT REQUIREMENTS

DETAILED SLASH DISPOSAL PLAN
TC Timber Sale
Malheur National Forest

I. Landing, Temporary Road and Road Surface Piling

All subdivisions have slash to be piled.

Temporary road slash from all Subdivisions will be piled at landings or designated areas agreed to by Forest Service.

A. Slash to be Yarded and/or Piled

1. All bark, limbs and other logging debris shall be removed from road surfaces and ditches.
2. All landing slash that is over 1 inch in diameter and/or 3 feet or more in length shall be piled.
3. Stumps excavated from temporary road construction will be scattered. All other slash will be grapple piled along temporary road utilizing future landings and natural openings.

B. Location of Piles

1. All yarded unutilized material will be piled at landings or other areas agreed to in writing by Forest Service.
2. All bark, limbs and logging debris from road surfaces and ditches will be piled at landings or other areas agreed to in writing by Forest Service.
3. Piles shall be at least 15 feet from standing timber.

C. Construction of Piles

1. Piles shall be as compact as possible with logs and pieces placed parallel to each other.
2. Piles shall contain a minimum amount of soil and other non-burnable material.

E. Acceptable Equipment

1. In the areas designated for grapple piling a machine will be required of Size that will not cause damage to the standing green trees when operating. Machines used to pile slash will be equipped with a brush blade having a minimum of five teeth which project at least 12 inches below the lower edge of the blade.

II. Grapple and Roadside Grapple Piling

Purchaser is responsible for Grapple piling slash in all units.