C2.2# - MINIMUM PIECE SIZE FOR SAWTIMBER *(02/2009)*

Purchaser is not required to pay for or remove minimum sawtimber pieces as described in A2 if said pieces have a net scale of less than **20** board feet.

C2.3# - RESERVE TREES *(04/2004)*

Notwithstanding the designations for cutting under B2.31, B2.32, B2.33, or B2.34, live or dead **Sugar Pine** reserve trees or groups of reserve trees within such cutting units or clearings shall be left uncut. Reserve trees are identified by **red painted bands and/or wide metal bands around the bole of the tree** and shall be protected in accordance with C6.32#. Units with reserve trees are shown on Sale Area Map.

C2.35# - DESIGNATION OF TIMBER, CUTTING UNIT BOUNDARIES, AND SUBDIVISION/PAYMENT UNIT BOUNDARIES *(06/2012)*

Trees are designated for cutting under B2.35 only if designated as shown in the Timber Designation table below. The boundaries of Subdivisions/Payment Units and Cutting Units are designated as shown in the Boundary Designation table below. Trees used for boundary designation are not to be cut.

SPECIFICATIONS PURSUANT TO C2.35# - DESIGNATION OF TIMBER. CUTTING UNIT BOUNDARIES, AND SUBDIVISION/PAYMENT UNIT BOUNDARIES

C2.35# - DESIGNATION OF TIMBER AND SUBDIVISION/PAYMENT UNIT BOUNDARIES (08/2007)

Table A.

SPECIFICATIONS PURSUANT TO C2.35# - DESIGNATION OF TIMBER AND SUBDIVISION/PAYMENT UNIT BOUNDARIES

Timber Designation Table

Unit/ Subdivision/Area/Payment Unit	Tree Paint Color	Designation or Specification
All Cutting Units	White	Roadside Hazard Tree. Notwithstanding B2.32 all dead and unstable live trees which are leaning towards a road or are otherwise hazardous to a road, and are sufficiently tall to reach Purchaser's landings or the roadbed of National Forest System roads within Sale Area, shall be felled by Purchaser when Marked in the specified paint color above and below stump height by Forest Service in advance of felling any other timber in the vicinity. Pieces meeting Utilization Standards from such dead and unstable live trees shall be removed unless Purchaser is notified in writing that removal would cause unacceptable damage to areas requiring special protection such as residual timber, roads, administrative sites, streamside management zones, and areas identified on Sale Area Map or on the ground.
N/A		Individual Tree Mark. Individual trees are designated for cutting only if Marked above and below stump height with the specified paint color.
N/A		Leave Tree Mark. All live < > are designated for cutting unless Marked as leave trees. Leave trees are Marked above and below stump height with the specified paint color. Sale Area Map indicates areas plainly identified on the ground where leave trees are Marked to be left uncut.
N/A		Salvage Area. In addition to Roadside Hazard Trees, other dead and dying timber standing or down that meets the size specification in A2, may be designated for cutting in Salvage Areas shown on the Sale Area Map when Marked with the specified paint color in advance of felling other timber in the vicinity.
N/A		Wildlife Trees. Notwithstanding the designation for cutting under B2.3l, B2.33, B2.34,or B2.35, trees which are identified by standard Forest Service metal wildlife tree sign or painted with the specified paint color on the uphill and downhill side, shall be left uncut. In event such trees are destroyed in Purchaser's Operations, Forest Service may designate alternate trees to be saved.
N/A		Designation by Spacing C2.351#
N/A		Designation by Species and Diameter, C2.352#
All subdivisions		Designation by Damage Class, C2.353#
N/A		Designation by Row Spacing, C2.354#

Subdivision/Payment Unit Boundary Designation Table

Subdivision/Payment Unit	Boundary Paint Color	Boundary Designation
N/A		

C2.353# - DESIGNATION BY DAMAGE CLASS *(04/2004)*

Within Subdivision(s) or cutting unit(s) **ALL** , as shown on Sale Area Map, the following criteria are used to designate trees and other products for cutting and removal:

(a) **Subject to C6.315# any tree or portions thereof that are lying on the ground and that meet utilization standards listed in A2**

(b) Additional trees to be cut, if any, are designated for cutting if Marked with **white** paint.

(c) Cutting unit boundaries and trees that shall be left uncut are Marked with **N/A** paint.

C4.211 - DOWNPAYMENT *(06/2007)*

The downpayment amount shown in A18 may not be applied toward any other payment required under the provisions of this contract, except damages determined pursuant to B9.4, transferred to other timber sales, or refunded until (a) stumpage value representing 25 percent of the total bid value of the timber sale has been charged and paid for, or (b) the estimated value of the unscaled timber is equal to or less than the amount of the downpayment, or (c) if 36 CFR 223.49(e) is applicable, the estimated value of the unscaled timber is equal to or less than the amount of the downpayment.

If Forest Service makes a determination that this contract should not have been included under increased downpayment requirements (36 CFR 223.49(e)), the downpayment shall be revised and applied in accordance with 36 CFR 223.49(f).

C4.212 - TEMPORARY REDUCTION OF DOWNPAYMENT *(08/2009)*

Notwithstanding B4.211 or C4.211, upon the Purchaser's written request Forest Service may temporarily reduce the downpayment when Purchaser's scheduled operations are delayed or interrupted for 30 or more consecutive days, or the contract term is extended for 30 or more consecutive days for any of the following reasons:

(1) Forest Service requests or orders Purchaser to delay or interrupt operations for reasons other than breach;

(2) Purchaser interrupts or delays scheduled operations to work on a sale designated by the Forest Service as in urgent need of harvesting; or

(3) An adjustment of the contract term authorized upon a determination of substantial overriding public interest, including a market-related contract term addition, or an urgent removal contract term extension under 36 CFR 223.53.

When Purchaser is not cutting or removing timber under contract during a qualifying period of delay, interruption, or extension listed above the downpayment may be reduced to $1000 or 2 percent of the downpayment amount stated in the contract, whichever is greater. The Purchaser must restore the downpayment to the full amount stated in the contract within 15 days from receipt of the bill for collection and written notice from the Contracting Officer that the basis for temporarily reducing the downpayment no longer exists. Purchaser shall not cut or remove timber on a contract where the downpayment has been temporarily reduced until the downpayment amount stated in the contract is fully restored.

C4.4 - PAYMENTS NOT RECEIVED *(08/2012)*

(a) Payments are due and payable on the date of issue indicated on the bill for collection. When a payment for timber cut and other charges is not received at the location designated by Forest Service by the date specified in the bill for collection for, Contracting Officer will suspend all or any part of Purchaser's Operations until payment or acceptable payment guarantee is received. Other charges include, but are not limited to:

(i) Slash disposal, road maintenance, and contract Scaling deposits;

(ii) Cooperative work at rates established by specific agreement under B4.218;

(iii) Damages pursuant to B9.4;

(iv) Road use fees;

(v) Restoration of downpayment pursuant to B4.22;

(vi) Periodic payments pursuant to B4.213;

(vii) Extension Deposits pursuant to B4.217; and

(viii) Other mandatory deposits.

(b) Failure to pay amounts due by the date specified in the bill for collection shall be considered a breach under B9.3. The 30-day notice period prescribed therein shall begin to run as of the end of business on the date specified for receipt of payments. If the performance or payment is guaranteed by surety bond, the surety will receive a copy of the written notification of breach. Demand will be made on the surety or other institution providing the guarantee or bond instrument for immediate payment 10 days after issuance of written notification of the breach.

(c) Pursuant to the Debt Collection Improvement Act of 1996, as amended, if payment is not received by Forest Service within 15 days after the date of issue indicated on the bill for collection:

(i) Simple interest shall be assessed at the Current Value of Funds Rate as established by the Secretary of the Treasury. Interest will begin to accrue as of the date of issue indicated on the initial bill for collection.

(ii) Debtors will be assessed administrative charges, in addition to the delinquent amount due. Administrative charges are those additional costs incurred by the Government in processing, handling, and collecting delinquent debts.

(iii) A penalty charge of six (6) percent per annum will be assessed on any portion of a debt delinquent more than 90 days. This penalty charge is in addition to interest and administrative charges under paragraphs (c)(i) and (c)(ii). The penalty charge shall accrue from the date of issue indicated on the bill for collection and shall be assessed on all outstanding amounts, including interest and administrative costs assessed under paragraphs (c)(i) and (c)(ii).

(iv) Payments will be credited on the date received by the Federal Depository or Collection Officer designated on the bill for collection.

(d) Forest Service remedies for Purchaser's failure to make payment for timber cut and other charges when due, except for accrual of interest, suspension of all or any part of Purchaser's Operations, and administrative offset, shall be stayed for so long as:

(i) A bona fide dispute exists as to Purchaser's obligation to make such payment and

(ii) Purchaser files and prosecutes a timely Claim.

C5.125# - SHARE COST ROAD LIABILITY INSURANCE *(08/2006)*

Purchaser is authorized to use cooperative roads constructed under provisions of **Sierra Pacific Industries** , Cooperator, and Forest Service, and subsequent easements, supplements, and agreements thereto, available for inspection at the Forest Supervisor's Office, **Placerville** , California, and subject to the following liability insurance requirements.

Purchaser shall provide a satisfactory certificate of insurance covering Purchaser's and all subcontractor's operations on cost share roads referred to above.

Purchaser shall present the certificate of insurance to Forest Service prior to use of cost share roads.

Insurance shall be of the following form and limits:

Comprehensive Automobile Bodily Injury/Property Damage Liability Insurance covering all owned, leased, hired and non-owned automobiles.

Minimum limits:	**$1,000,000**	**per person bodily injury or death**
	$1,000,000	**per occurrence bodily injury or death**
and	**$1,000,000**	**per occurrence property damage or a**
combined single limit of	**$1,000,000**	

In addition to above, Purchaser and Purchaser's assigns shall carry the following limits of insurance for the purpose of covering fire suppression expense, property damage to timber land due to fire, and property damage to non-owned automobiles and equipment due to fire.

Comprehensive General Liability Bodily Injury/Property Damage Insurance for minimum limits of:

	$1,000,000	**per person bodily injury or death**
	$1,000,000	**per occurrence bodily injury or death**
and	**$1,000,000**	**per occurrence property damage or a**
combined single limit of	**$1,000,000**	

Such Comprehensive General Liability policy shall include an endorsement covering fire suppression expense, property damage to timber land due to fire, and property damage to non-owned automobiles and equipment due to fire. Said endorsement shall have minimum property damage limits of **$ 1,000,000** and be designated separately on the Certificate of Insurance.

The Certificate of Insurance shall require insurance carrier to notify Cooperator by mail ten (10) days prior to cancellation or expiration of above coverage. The Certificate of Insurance shall also name **Sierra Pacific Industries** as additionally insured solely as respects operations conducted by or on behalf of the Purchaser involving use of the cost shared roads referred to above.

C5.31# - ROAD MAINTENANCE REQUIREMENTS *(07/2001)*

Purchaser shall maintain roads in accordance with the following Contract Road Maintenance Requirements Summary:

See Contract Road Maintenance Requirements Summary Table.

Table A

C5.31# - Contract Road Maintenance Requirements Summary

Road	Termini		Miles	Applicable Prehaul Road Maintenance Specifications									
	From	To		810									
All Native Surface Roads				P									
All Chip Seal/Paved Surface Roads				P									

P = Purchaser Performance Item, D = Deposit to Forest Service, D3 = Deposit to Third Party
Maximum slide and slump repair is 50 CY

Road	Termini		Miles	Applicable During Haul Road Maintenance Specifications									
	From	To		811	812								
All Native Surface Roads				P	P								

P = Purchaser Performance Item, D = Deposit to Forest Service, D3 = Deposit to Third Party
Maximum slide and slump repair is 50 CY

Road	Termini		Miles	Applicable Post Haul Road Maintenance Specifications									
	From	To		809	810	811	812	831	834	837			
All Native Surface Roads				P	P	P	P	P	P	P			

P = Purchaser Performance Item D = Deposit to Forest Service D3 = Deposit to Third Party
Maximum slide and slump repair is 50 CY

C5.32# - ROAD MAINTENANCE DEPOSIT SCHEDULE *(07/2001)*

Other provisions herein notwithstanding, when Forest Service requests payment in lieu of Purchaser's performance of road maintenance, Purchaser shall make Required Deposits (16 USC 537) for current and/or deferred road maintenance. Such deposits are based on the estimated volume and distance hauled and Purchaser's commensurate use of each road listed in the Road Maintenance Plan in C5.31#.

Purchaser and Forest Service may agree in writing on adjustment of such rates. If Purchaser uses roads under jurisdiction of Forest Service other than those listed in the Road Maintenance Plan, Forest Service shall establish rates commensurate with Purchaser's use of such roads.

The Required Deposits for Forest Service work in lieu of Purchaser performance and for deferred maintenance is: **$2.40** per **MBF** .

The following table lists who Purchaser will make deposits for road maintenance to, and the rate per unit of measure of the deposit. The Road Maintenance Agreement is available for inspection at the Forest Supervisor's office.

Deposit Made To	Rate	Unit of Measure
N/A		

C5.35# - ROAD AND WATER SUPPLY USE *(05/2008)*

National Forest water supply locations, access, method of filling trucks, period of water availability and procedures designed to maintain water quality at each location shall be agreed in advance of use. Such use shall at no time reduce water supplies to the level that further use may be detrimental to aquatic resources or other established use. Waterholes and other improvements relating to said water supplies shall be put into condition, prior to expected seasonal periods of precipitation or runoff, to avoid resource damage.

Damage to resources at such locations caused by Purchaser's Operations, other than fire suppression activities, shall be repaired by Purchaser in a timely and agreed manner to the extent practicable to restore and prevent further resource damage.

Unless otherwise agreed, Purchaser's use of roads and other water supply requirements shall conform to the following table.

See Table A

Table A

SPECIFICATIONS PURSUANT TO C5.35# - REQUIREMENTS OF ROAD AND WATER SUPPLY USE

Load Limitations	Purchaser shall notify Forest Service in writing of the planned size and load distribution for equipment which exceeds the State of California Vehicle Code legal size and weight, and the National Forest System roads to be used. Such notice may be part of plan of operation under B6.311. Within I5 days after receipt of the written notice Forest Service shall notify Purchaser in writing of any regulations or restrictions that may be needed to protect National Forest Transportation Facilities. A written permit shall be required for moving any vehicle which is in excess of the established legal size and weight which is not listed in the above plan, except as may be authorized in prior written agreements.
Existing Non-National Forest System Roads	Roads not shown on Sale Area Map may be used as Temporary Roads if there is agreement before use is started.
Snow Removal	If Purchaser removes snow from roads, such work shall be done with Forest Service approval and in a manner that will protect roads and adjacent resources. Snow berms shall be removed or placed to avoid accumulation of melt water on the road and prevent water concentration on erosive slopes or soils. Snow must not be removed to the road surface. A minimum 6 inch snow depth must be left to protect the roadway. If the road surface is damaged, Purchaser shall replace lost surface material and repair structures damaged in blading operations prior to hauling, unless climatic conditions prevent necessary work from being accomplished or as otherwise agreed in writing. Single lane roads shall be plowed full width including turnouts. In event double lane roads are not plowed to full width, warning signs shall be required and plowing shall be no less than single lane (12 feet) with intervisible turnouts.
Water Supply Deposits	N/A

Surface Replacement Deposits	Purchaser shall make Required Deposits for deferred surface replacement (16 U.S.C. 537) for use of existing surfaced roads. If applicable, such deposits shall be based upon the volume and distance hauled on the roads and at the applicable rates listed in the table below titled Surface Replacement Deposit Schedule. If Purchaser uses surfaced roads under jurisdiction of Forest Service other than those listed, Forest Service may establish applicable rates for such surfaced roads.

SURFACE REPLACEMENT DEPOSIT SCHEDULE

Road No.	From	To	Miles	Rate
All Surfaced System Roads			45	$1.13/mbf/mile

Sale Area Average Rate: $5.59/MBF

C6.24# - SITE SPECIFIC PROTECTION MEASURES *(04/2004)*

Special protection measures needed to protect known areas identified on Sale Area Map or on the ground include:

Cultural Resource Protection Measures: **CA-1 on Sale Area Map - No operations are permitted within zones flagged in pink and/or pink and black checkered flagging, site boundaries posted with "Tractor Prohibited" signs or a combination thereof. Any trees in close proximity to said areas will be directionally felled away from site.**
Wildlife and Botanical Protection Measures: **CA-2 and CA-3 on Sale Area Map - Subject to C.315# no operations are permitted within areas flagged with pink and chartruese flagging (CA-2). No operations permitted within areas flagged with orange flagging and the words "Noxious Weed" printed on it (CA-3).**
Cave Resource Protection Measures: **N/A**

C6.315# - SALE OPERATIONS SCHEDULE *(08/2006)*

Unless otherwise agreed in writing, Purchaser's Operations shall be performed in accordance with the following schedule:

See Table A

Table A

C6.315# - SALE OPERATIONS SCHEDULE. (08/2006)

SCHEDULE PURSUANT TO C6.315# - SALE OPERATIONS SCHEDULE (8/2006)

Subdivision/ Area/Unit	Conditions of Operation	Purpose
All Subdivisions	Unless otherwise agreed, removal of specified blowdown areas identified on the Sale Area Map will be completed by October 1st., 2014	To harvest known concentrations of blowdown.
All Subdivisions	No equipment use or harvesting activities permitted during specified time in areas designated as LOP (Limited Operating Period) as shown on the Sale Area Map. Road maintenance is acceptable.	Protection of wildlife and recreational use.
All Subdivisions	No removal of blowdown or hazard trees in protected areas shown on Sale Area Map except blowdown timber along the following roads, 12N21, 12N05, 12NY06, 12NY06A, 12NY06B, 13N29A, 13N31A, 13N31AN, 13N43, 13N77 and 13N86 is included timber. Only trees located within the road prism (includes cut and fill slopes) may be removed. This includes the portion of those trees outside of the road prism. Trees that are completely outside of the road prism must be left in place. In addition, hazard trees may be felled for the purpose of safety in protected areas but must be left in place unless the tree falls into the road prism.	For wildlife and soils benefits
All Subdivisions	No equipment, removal of blowdown or hazard trees, or felling of small damaged trees as listed in C6.41#, C6.42 and C6.7# is permitted within buffers of streams or other protected areas as shown on Sale Area Map (i.e. meadows).	For water quality and aquatic habitat protection
All Subdivisions except in designated campgrounds, administrative sites, and all road prisms.	Notwithstanding Specifications in C6.7# all unmerchantable blow down logs and unmerchantable felled hazard trees (trees that do not meet merchantability standards) will be retained and left in place.	For wildlife and soils benefits
All water supply locations	Sites used to draft water shall be approved by Forest Service prior to use. A Forest Service approved screen covered drafting box or other device shall be used to create low entry velocity.	Minimize removal of aquatic species.

C6.32# - PROTECTION OF RESERVE TREES *(04/2004)*

Purchaser's damage or destruction of reserve trees described in C2.3# will cause serious and substantial silvicultural or other damage to the National Forest. It will be difficult if not impossible to determine the amount of such damage. Therefore, Purchaser shall pay as fixed, agreed, and liquidated damages $ **2927.29** for each **Sugar Pine** reserve tree and $ **N/A** for each **N/A** reserve tree damaged or destroyed by Purchaser's Operations, in addition to amounts payable under B3.45 and B3.46.

Damage, as used herein, includes any injury to the living crown, bole, or roots of reserve trees. If areas are marked on the ground around such reserve trees, operation of heavy equipment or skidding of products within the area shall be considered to be damage to the tree.

C6.331 - LOG TRUCKING *(08/2006)*

To promote safe operations on National Forest roads and on Specified Roads, loads shall be safely secured before trucks move from the landing or loading location.

C6.37 - SUBSTITUTE METHODS *(08/2006)*

Notwithstanding other provisions herein, for minor changes such as changes in logging systems for areas smaller than 5 acres, Purchaser and Forest Service may agree in writing that use of substitute methods or equipment will achieve Forest Service objectives under this contract and may be used in lieu of those specified for Purchaser's Operations.

C6.41# - FELLING, BUCKING, AND LIMBING *(08/2007)*

Unless otherwise agreed in writing, Purchaser's felling, bucking, and limbing operations shall be conducted as specified in the table below.

See Table A

C6.41# – FELLING, BUCKING, AND LIMBING. (8/2007)

SPECIFICATIONS AND TREATMENTS PURSUANT TO C6.41# - FELLING, BUCKING AND LIMBING

Table A

Treatment Method and Applicable Map Symbol	Felling, Bucking and Limbing Specifications
Limbing	Outside of construction clearings, Clearcutting Units and regeneration units, unless otherwise provided by B6.414, Purchaser shall, prior to skidding/yarding operations, cut exposed limbs from products which are to be skidded/yarded. Such limbing of stems shall be done to a top diameter of approximately 6 inches, at which point the top shall be cut from the remainder of the stem.
No Lop "No Lop"	N/A
Whole Tree Yarding "Whole"	NA
Directional Felling "DF"	Within areas designated DF on Sale Area Map, Included Timber shall be directionally felled away from roads, all campground improvements, streams, sensitive sites and property not owned by the federal government with the use of specialized equipment. Such directional felling shall not be required when in the faller's judgment it is unsafe to do so, and shall be left standing.
Treatment of Stumps "TS"	Within areas shown on Sale Area Map, Purchaser shall treat stumps of all live White Fir trees equal to or greater than 14 inches stump diameter, (measured inside bark) unless otherwise agreed in writing. Treatment shall be with a borate compound registered by EPA in the State of California for prevention of annosus root disease. Treatment shall consist of removal of sawdust and other loose debris from the cut surface of the stump and application of a thin layer of the borate compound uniformly over the entire cut surface, including exposed wood surfaces on the stump sides, at the rate specified on the product label. Any surface irregularities on the stump preventing application of a uniform layer of borate compound shall be cut level prior to treatment. Unless waived in writing, Purchaser shall also apply an approved colorant mixed with the borate compound to insure complete coverage. Treatment should be done as soon as possible but shall be completed no later than 4 hours after felling, otherwise stumps shall be re-cut and treated. Purchaser shall not apply borate compound during heavy rain fall or when such precipiation rate is predicted within 24 hours of application to cause borate compound to be flushed off the stump and become ineffective, in that case treatment shall be reapplied. Application shall be completed within 24 hours of the precipitation having ceased. Borate compound also shall not be applied to stumps located within stream buffer distances shown on sale area map of live streamcourses and meadows/wetlands shown on Sale Area Map and/or 50 feet of sensitive plant location boundaries as flagged on the ground. Purchaser shall provide the borate compound and colorant and apply it in compliance with the State of California laws and regulations pertaining to pesticides and pest control operations. Borate compound storage shall be located such that any spillage will not contaminate water. All spills shall be promptly cleaned up and spilled material disposed of according to the product label. All spills occuring in water or over 20 pounds shall be reported to Forest Service within 8 hours.

<table>
<tr><td></td><td>Purchaser shall submit at the end of each month a “Monthly Summary of Pesticide Use Reports” to the appropriate County Agricultural Commissioner with a copy to the District Ranger.</td></tr>
<tr><td>Maximum Log Length</td><td>Cut trees shall be bucked prior to skidding so that resulting logs shall not exceed the maximum log length including trim allowance shown in following table:
<table>
<tr><td>Unit Number</td><td>Maximum Log Length</td></tr>
<tr><td>Entire Sale Area</td><td>41 feet</td></tr>
</table></td></tr>
<tr><td>Minimum Stump Height</td><td>
<table>
<tr><td>Unit/Subdivision</td><td>Minimum Stump Height (inches)</td><td>Purpose or Reason</td></tr>
<tr><td>N/A</td><td></td><td></td></tr>
</table></td></tr>
</table>

C6.42# - GROUND BASED SKIDDING *(08/2006)*

Unless otherwise agreed in writing, the method of skidding Included Timber shall be as shown on the Sale Area Map, by areas, with symbols defined in the following table:

See Table A

Table A

C6.42# - Ground-Based Skidding (08/2006)

Map Symbol	Requirements
TRAC	Skid road pattern shall be agreed in advance of felling and main skid roads shall be flagged on the ground in advance of felling. Purchaser shall stage-log by felling and skidding Included Timber in two or more separate operations when necessary to prevent undue damage to the resources or residual stand. Needed tractor trails shall be constructed in advance of skidding. Products shall be end-lined as needed to protect resources or residual timber from unnecessary damage. The number of chokers shall be limited as necessary to avoid unnecessary damage to resources or residual timber. By agreement, tractors may be used to separate products to prevent stain.
SUSP	Products shall be skidded with leading end clear of ground.
SPACE	Skid roads will average 100 feet from center to center, except where converging.
ENDL	Endlining shall not be required for distances in excess of 60 feet uphill, and 120 feet downhill.
MAX	Tractors used for skidding outside Clearcutting Units, regeneration units or other authorized clearings, shall be of the type (rubber-tired or track-laying) shown on the Sale Area Map and shall not exceed the overall width designated on Sale Area Map.
MH	Purchaser shall cut Included Timber and move it to designated skid trails using equipment with a boom having an operating radius of at least _N/A_ feet for bunching trees, capable of severing, lowering and placing trees up to _ N/A _ inches diameter at stump height on the ground prior to skidding. Such equipment must be capable of operating on slopes up to N/A %. Notwithstanding above, hand felling using chainsaws may be required in or adjacent to sensitive areas to protect resources from unnecessary damage. Trees which exceed capability of specified equipment may be felled, bucked and skidded in a manner consistent with the requirements of B6.41 - Felling and Bucking, C6.41# - Felling, Bucking, and Limbing Requirements and the above "TRAC", "SUSP", "SPACE", "ENDL", and "MAX" requirements.
CTL	Included Timber shall be felled, limbed and bucked by a self-propelled mechanical harvester capable of producing finished sawlogs or chippable boles. Limbs of Included Timber shall be placed evenly in the machinery skid trail prior to product removal. The harvester shall be an all-wheel drive machine with at least 3 axles and a processing head mounted on a boom having a minimum-operating radius of 20 feet. Notwithstanding above, hand felling using chainsaws may be required in or adjacent to sensitive areas to protect resources or residual timber from unnecessary damage. All Products shall be removed by an all-wheel drive forwarder with at least 3 axles capable of self-loading and unloading. The forwarder shall carry all products free of the ground during removal. The loading crane shall have a minimum-operating radius of 15 feet. Log landings and transfer points shall be agreed in advance of harvesting. Included Timber exceeding the harvester's capability may be felled by conventional chainsaw methods, forwarded to nearest skid trail and processed into a finished Product with harvester or chainsaw, consistent with the requirements B6.61 - Meadow Protection, B6.41 - Felling and Bucking, C6.41# - Felling, Bucking, and Limbing and the above "TRAC", "SUSP", "SPACE", "ENDL", and "MAX" requirements.
PB	Purchaser shall cut Included Timber and move trees to pre-approved skyline corridors to facilitate skyline yarding using equipment with a boom having an operating radius of at least _N/A_ feet for bunching trees, capable of severing, lowering and placing trees up to _ N/A _ inches diameter at stump height on the ground prior to yarding. Such equipment must be capable of operating on slopes up to N/A %. Bundles shall not exceed yarder capablity or cause unnecessary damage to residual stand.

	Notwithstanding above, hand felling using chainsaws may be required in or adjacent to sensitive areas to protect resources from unnecessary damage. Such trees shall be felled away from the corridor in a manner that minimizes residual stand damage during yarding. Included Timber exceeding the feller's capability may be felled by conventional chainsaw methods
HCTL	Included Timber shall be felled, limbed and bucked by a self-propelled mechanical harvester capable of producing finished sawlogs or chippable boles. Such equipment must be capable of operating on slopes up to N/A %. The harvester shall be an all-wheel drive machine with at least 3 axles, or track mounted, and a processing head mounted on a boom having a minimum-operating radius of 20 feet. Notwithstanding above, hand felling using chainsaws may be required in or adjacent to sensitive areas to protect resources or residual timber from unnecessary damage. Included Timber exceeding the harvester's capability may be felled by conventional chainsaw methods

C6.5 - STREAMCOURSE PROTECTION *(08/2006)*

Unless otherwise agreed in writing, wheel or track laying equipment shall not operate within "Buffer Strips" except as necessary for fire suppression activities. "Buffer Strips" are areas marked on the ground or are within the distances identified on the Sale Area Map measured from the apparent high water mark of streamcourses. Boundaries of Buffer Strips may be modified by agreement in writing to meet unforeseen operating conditions.

Culverts, bridges, or other suitable structures shall be required on skid roads and trails only at points where it is necessary to protect Stream courses. The type of crossing structures, method of installation and removal shall be determined by agreement. Purchaser in accordance with C6.6 - Erosion Prevention and Control, shall remove such structures and associated fills.

Damage to Stream course or Buffer Strips caused by unauthorized Purchaser's Operations shall be repaired by Purchaser in a timely and agreed manner to the extent practical as determined by Forest Service to restore and prevent further damage to Stream courses.

C6.6# - EROSION PREVENTION AND CONTROL *(05/2008)*

Erosion prevention and control work, including Streamcourse protection, required by C6.5 and B6.6 shall be completed within 15 calendar days after skidding operations related to each landing are substantially completed or after Forest Service designation on the ground of work where such designation is required hereunder. Said time limit shall be exclusive of full days lost in Purchaser's Operations due to causes beyond Purchaser's control. Such on the ground designation shall be done as promptly as feasible unless it is agreed that the location of such work can be established without marking on the ground. After September 15 and as long thereafter as operations continue the work shall be done as promptly as practicable. Damage resulting from Purchaser's Operations due to failure to perform required work shall be repaired by Purchaser.

Notwithstanding other provisions in this contract and unless otherwise agreed in writing, any hay, straw, or mulch used in this contract shall be State of California certified weed free.

Additional erosion control requirements of this contract are listed in the following table.

See Table A

Table A

SPECIFICATIONS PURSUANT TO C6.6# - EROSION PREVENTION AND CONTROL.

Vegetative Soil Stabilization N/A

Special Erosion Prevention Measures Purchaser shall give adequate treatment by spreading slash or wood chips or by agreement giving other treatment to portion of tractor roads, skid trails, landings, cable yarding corridors, tractor-end lined corridors and Temporary Road fills where necessary to supplement other erosion prevention measures required elsewhere in this contract. In no event shall Purchaser be required to treat more acres than that shown in the legend of Sale Area Map. The specific locations to be treated shall be designated on the ground by Forest Service. These special erosion prevention measures are to be done within the same date and time periods as stated above.

Soil Scarification. N/A

Backblading Within recreation development sites and public use areas designated on Sale Area Map, Purchaser shall, at Forest Service request, backblade skid trails in lieu of cross ditching.

Tillage: N/A

C6.7# - SLASH TREATMENT *(08/2006)*

Purchaser shall pile, scatter, yard, construct firelines or otherwise treat slash defined in specifications below, within designated areas. Work required of Purchaser shall be in accordance with the following slash plan and specifications, and the Sale Area Map.

All vegetative debris associated with construction of Specified Roads such as unutilized timber, brush and grubbed stumps is Construction Slash. Measures to be taken by Purchaser for treatment of Construction Slash are set forth in the attached road construction specifications and in the attached slash treatment specifications.

Vegetative debris larger than 1 inch in diameter outside bark and 3 feet long resulting from Purchaser's Operations, other than Construction Slash, is Logging Slash. Measures to be taken by Purchaser for treatment of Logging Slash are set forth below unless otherwise agreed in writing.

Forest Service and Purchaser shall jointly develop a schedule for completion of slash treatment on the various portions of Sale Area prior to Purchaser's Operations.

Removing may be substituted for treatment of any other specified method.

By agreement in writing, certain slash may be left for fuelwood. When the specified treatment is by a combination of methods, Logging Slash not treated by one of the methods shall be treated by the other(s).

See the slash treatment specification table below.

See Table A.

Table A

SPECIFICATIONS PURSUANT TO C6.7# - SLASH TREATMENT *(8/2006)*

Specified slash treatment methods shall be shown on Sale Area Map or listed in the following tables by the following symbols:

Slash Treatment Methods

Symbol	Method	Definition
Buck-L	"Bucking Large Logging Slash"	Tops and limbs over 4 inches diameter outside bark (d.o.b.), not to be otherwise treated, shall be bucked into lengths not to exceed 6 feet, unless agreed otherwise.
Buck-P	"Bucking and Piling"	Logging Slash smaller than N/A inches and larger than 4 inches in large end d.o.b. shall be bucked into lengths not to exceed N/A feet and left in place. Logging Slash 4 inches and smaller in large end d.o.b. shall be hand Piled within Required Disposal Strip for Forest Service disposal.
Bury	"Burying"	Logging Slash shall be buried where agreed in borrow areas, pits, trenches, or other locations reasonably near the area of origin. Logging Slash shall be matted down in layers and shall be covered with at least 2 feet of rock and soil so that the final surface is sloped to drain and relatively smooth.
Chip	"Chipping"	Chippable Logging Slash up to 4 inches in d.o.b. shall be processed through a chipping machine. Chips shall be scattered to a loose depth not exceeding 6 inches.
Deck	"Decking" large material	Logging Slash 10 inches or larger in large end d.o.b. and 10 feet or more in length shall be Decked for disposal by Forest Service by piling pieces parallel to each other.
Mach	"Machine Piling"	Concentrations of Logging Slash, excluding scattered individual pieces, shall be Machine Piled by tractor equipped with brush rake for disposal by Forest Service.
Pile	"Piling" small material	Logging Slash smaller than 10 inches in large end d.o.b. and 10 feet long shall be hand Piled for disposal by Forest Service.
Remove	"Removing"	Logging Slash shall be moved or hauled to locations shown on Sale Area Map and designated on the ground where it shall be piled for disposal by Forest Service.
Scat 18" Scat 30"	"Scattering"	Logging Slash shall be scattered to reduce slash concentrations with slash being generally left within 18 or 30 inches of the ground as shown on Sale Area Map. Logging Slash shall be scattered into openings away from and without unnecessary damage to residual trees. All scattered logs shall be limbed, placed away from trees and positioned so they will not roll. When Scattering is specified, another method may be used by agreement.
Stack	"Stacking" small material	Logging Slash N/A inches or smaller in large end d.o.b. and N/A feet or more in length shall be stacked for disposal by Forest Service by piling pieces parallel to each other.

View "Visible Slash Treatment"

Designated on Sale Area Map with boundaries posted on the ground are <> with distance limitations for visible slash treatment. Within such units and the area of visible Logging Slash adjacent thereto, Logging Slash shall be treated by Purchaser. Primary treatment shall be by Removing, Burying, Chipping, Piling, Machine Piling, or a combination of these means unless a method is specified or prohibited on Sale Area Map. Logging Slash not readily treated by the selected or specified method shall be removed to designated areas or treated as agreed.

YUMD "Yarding Unutilized Material-Decking"

All unutilized material developed by Purchaser's Operations shall be treated by the d.o.b. and length specifications as shown in the unit specification table. All unutilized material shall be Yarded to landings and Decked. Where this is impractical, or other reasons, other locations shall be agreed upon.

Unit	Large End d.o.b. (in)	Length (feet)

YUME "Yarding Unutilized Material-Exterior Boundary"

All unutilized material developed by Purchaser's Operations shall be treated by the d.o.b. and length specifications as shown in the unit specification table. All unutilized material shall be yarded to locations a minimum of 50 feet slope distance within the exterior boundaries of such units and positioned so the yarded material will not roll.

Unit	Large End d.o.b. (in)	Length (feet)

YUML "Yarding Unutilized Material-Landing"

All unutilized material developed by Purchaser's Operations shall be treated by the d.o.b. and length specifications as shown in the unit specification table. All unutilized shall be yarded to locations within 100 feet slope distance of landing. Where this is impractical, or other reasons, other locations shall be agreed upon.

Unit	Large End d.o.b. (in)	Length (feet)

YUMR "Yarding Unutilized Material-Removal"

All unutilized material developed by Purchaser's Operations shall be treated by the d.o.b. and length specifications as shown in the unit specification table. All unutilized shall be removed to locations shown on Sale Area Map and designated on the ground, or other agreed locations, and Decked.

Unit	Large End d.o.b. (in)	Length (feet)

Cover "Covering Piles"

All piles shall be covered with a durable waterproof covering as approved by Forest Service. The material shall be at least six feet in width. Piles shall not be less than fifty percent covered, with the covering extending not less than half way down all sides. Pieces of burnable material shall be placed on top of the durable waterproof covering to keep the covering from blowing off the pile.

Fell	"Damaged Small Tress"	Unless treated under other provisions, all trees smaller than the minimum d.b.h. in A2, over 5 feet in height, and damaged beyond recovery by Purchaser's Operations shall be felled. Such trees shall be limbed to a stem diameter outside bark of approximately 3 inches, at which point the top shall be cut from the remainder of the stem, and shall be bucked into lengths not exceeding 20 feet.
Fire-L	"Firelines"	Shown on Sale Area Map and to be flagged on ground after logging by Forest Service are firelines to be constructed by Purchaser unless otherwise agreed in writing. Purchaser shall construct not more than <> chains of fireline by hand and not more than <> chains of fireline by tractor. Firelines constructed by hand shall be cleared of all vegetative debris larger than one inch in d.o.b. and three feet long. The width of firelines shall be at least <> feet, except across the top of cutting units where the width shall be at least <> feet. At least <> feet shall be scraped to mineral soil. In areas where there is potential for burning material to roll, the fireline shall be constructed in a trenched manner on the downhill side. Tractor lines shall be cleared of all vegetative debris, larger than one inch in diameter and three feet long, to a width of at least <> feet, with at least <> feet to mineral soil. No slash, brush, or other vegetative debris shall be buried in or under berms created in the construction of firelines. All limbs overhanging into the fireline, shall be removed to a minimum height of 8 feet. Firelines shall be completed on each unit in accordance with B6.311 unless otherwise agreed in writing. In subdivisions <> and shown on Sale Area Map, Logging Slash shall be scattered within <> feet slope distance of the inside edge of firelines.
Fuel-B	"Fuelbreaks"	Shown on Sale Area Map, with boundaries designated on the ground, are "Fuelbreaks" of varying width. Within such Fuelbreaks all Logging slash and Construction slash shall be treated by Purchaser. Primary treatment shall be by Removing, Burying, Chipping, Piling, Machine Piling, or a combination of these methods unless a method is specified or prohibited on Sale Area Map. Slash larger than treatment size requirements of selected or specified methods shall be scattered outside Fuelbreak, or treated as agreed.

PILING SPECIFICATIONS. All piles shall be reasonably compact and free of soil to facilitate burning and shall be constructed of such size and at such distance from trees so that burning shall not result in unnecessary damage to residual timber. Such Logging Slash shall be bucked into lengths not exceeding ten feet prior to piling. Maximum width of tractor, with brush rake attached, shall not exceed N/A inches. Machine Piling is not required on areas where use of tractors would cause undue damage to residual timber or where slopes exceed N/A percent. Piles shall be located a distance of at least twice their height in feet from the outer edge of tree crowns or snags. Piles shall be no less than four feet in height or greater than N/A feet in height. Material extending three feet or more outside the edge of a pile shall be trimmed. An eight foot fuelbreak shall be cleared of all but fine material around each Machine Pile and an 18 inch wide fireline shall be cleared to mineral soil around the outer ring of the fuelbreak. For hand piles, Purchaser shall construct a fireline cleared to mineral soil and at least 3 feet wide around each pile. In areas where there is a potential for burning material to roll, firelines, including those for Machine Piles, shall be trenched on the downhill side of each pile to adequately prevent material from crossing firelines. Trenches shall be constructed by hand unless otherwise agreed.

UNIT AND SUBDIVISION.SLASH TREATMENT SPECIFICATIONS.

	SLASH TREATMENT	
Subdivision or Unit No	***Specified Method***	***Prohibited Method***
Campgrounds and Administrative Sites	**Pile** within designated site and up to 50' outside of site boundaries and improvements	
Campgrounds and Administrative Sites	**Remove** slash not meeting Pile specification within designated site and up to 50' outside of site boundaries and improvements	
All subdivisions except in areas noted in C6.315#	**Fell** within all subdivisions except as noted in C6.315# where equipment and skidding is prohibited (Protected stream buffers, aquatic features or other areas shown on Sale Area Map)	
Areas outside of 50' **Pile** zone along system roads but not in Campgrounds, Administrative Sites or other Protected Areas	**Scat 18"**	

LANDINGS AND DISPOSAL SITES. Unutilized logs accumulated at landings and disposal sites shall be Decked by Purchaser for disposal by Forest Service. The maximum height of decks is shown in the following table. Other slash accumulated at landings and disposal sites shall be kept separate from unutilized logs and treated by the method shown in the following table.

		SLASH TREATMENT	
	Subdivision or Unit No.	***Specified Method***	***Maximum Height of Decks***
Landings	***Entire Sale Area*** ***Entire Sale Area***	***Deck*** ***Mach***	***10 feet*** ***10 feet***
Disposal Sites			

TREATMENT ALONG PERMANENT ROADS Permanent roads that require roadside slash treatment are listed in the attached table and shown on Sale Area Map. All Logging and Construction Slash within Required Disposal Strips shall be treated by Purchaser. "Required Disposal Strips" are those areas adjacent to permanent roads where slash treatment is required for resource objectives. The width of Required Disposal Strips is shown in the attached table and is measured in slope distance from Roadbed edges of permanent roads. By agreement, in Clearcutting Units and regeneration units slash from Required Disposal Strips may be treated with other Logging Slash. By agreement the location of Required Disposal Strips may be adjusted from side to side without materially changing the total work required.

Slash treatment in Required Disposal Strips shall be accomplished without affecting the proper functioning of channels leading to and from drainage structures.

Logging Slash larger than treatment size requirements of the specified method shall either be Scattered outside Required Disposal Strip, within Required Disposal Strip or Decked at agreed locations as shown in the attached table.

			SLASH TREATMENT	
Road No.	***Subdivision and/ or Unit No. or Road Juncitons (From To)***	***Width of Required Disposal Strip***	***Specified Method***	***Slash Larger Than Treatment Size Requirements of Specified Method***
All system roads within Sale Area	***All Subdivisions***	***50 feet***	***Pile unless otherwise noted in C6.315#***	***N/A***

TREATMENT ALONG TEMPORARY ROADS. Outside of Clearcutting Units or regeneration units, all trees felled or pushed over and trees damaged beyond recovery by Temporary Road construction shall be felled, limbed to a stem d.o.b. of approximately 3 inches, at which point the top shall be cut from the remainder of the stem, and stem shall be bucked into lengths not exceeding N/A feet. Such slash shall be Scattered free of soil to reduce concentrations unless treatment is required by another specified method.

ADDITIONAL SLASH TREATMENT REQUIREMENTS. Within areas shown on Sale Area Map, Purchaser shall perform work according to the specifications in the attached Table, unless otherwise agreed in writing.

Subdivision, Payment Units, Roads and or Road Segments	Additional Slash Treatment Requirements
All Subdivisions	Broken ends of merchantable logs shall not be bucked off in the units. Slash and Substandard Material accumulated at the landings shall be Decked or Machine Piled, in accordance with specifications above. Material accumulated at landings shall be considered as Timber Subject to Agreement under C2.11#, described as Substandard Material and may be removed and paid for at Purchaser's option.

C6.815 - THIRD PARTY SCALING SERVICES *(04/2004)*

Notwithstanding the requirement for Forest Service or parties under contract to Forest Service to provide Scaling services under B6.81, Scaling designated in A10 shall be conducted by a third party Scaling organization approved by Forest Service. Scaling shall be done in accordance with A9 and Purchaser shall bear costs for Scaling service.

In the event third party Scaling service is suspended for causes such as strikes, termination of third party's approval to Scale National Forest logs by Forest Service, or Purchaser's failure to pay third party Scaling costs, hauling operations shall be suspended until agreed alternate Scaling services are provided or service by third party is resumed.

When an approved alternate Scaling location pursuant to B6.811 does not have an approved third party scaling organization as a commonly used Scaling services provider, Forest Service or parties under contract to Forest Service shall provide Scaling services at the approved alternate location. In such an event, the cost of waived third party Scaling listed in A10 shall be charged to Timber Sale Account.

If Forest Service and Purchaser agree in writing that another party under contract to Forest Service will perform Scaling, the contract will be modified to include C6.816 and Timber Sale Account will be charged for such Scaling.

C7.2# - SPECIFIED FIRE PRECAUTIONS *(06/2012)*

Purchaser or a designated Purchaser's Representative shall certify compliance with specific Timber Sale Contract and California Public Resources Code (CPRC) fire precautionary measures in B7.1 Plans, C7.2# and C7.22#. Certification shall be provided prior to starting operations during Fire Precautionary Period and shall be updated as needed.
Listing of specific fire precautionary measures in the following subsections is not intended to relieve Purchaser in any way from compliance with State fire laws covering fire prevention and suppression equipment applicable to Purchaser's Operations.
Upon request of Forest Service, Purchaser shall permit and assist in periodic testing and inspection of required fire equipment.
The following definitions shall apply to C7.2# and C7.22#:

Active Landing: A location Purchaser is skidding logs into, or performing other operations such as delimbing, log manufacturing, and chipping logs. Except for EV and E days, loading logs or stockpiled chips only on a cleared landing does not constitute an Active Landing.

Hot Saw: A harvesting system that employs a high-speed (>1100 rpm) rotating felling head (i.e., full rotation lateral tilt head).

Mechanical Operations: The process of felling, skidding, chipping, shredding, piling, log processing and/or yarding which requires the use of motorized power which includes, chainsaws, chippers, motorized carriages, masticators, stroke delimbers, skidders etc.

Specific equipment requirements and fire precautionary measures are shown in the following table and in C7.22#:

Table A

Table A – C7.2# - Specified Fire Precautions (06/2012)

A. Fire Tools and Equipment

Purchaser shall meet applicable parts of Section 4428 of the CPRC.

Unless agreed otherwise, Fire tools kept at each Active Landing shall be sufficient to equip all employees in the felling, yarding, loading, chipping, and material processing operations associated with each landing. Fire equipment shall include two tractor headlights for each tractor dozer used in Purchaser's Operations. Tractor headlights shall be attachable to each tractor and served by an adequate power source. Fire tools shall be kept in a sealed fire tool box adjacent to the Active Landing and readily accessible in event of fire.

Where cable yarding is used, Purchaser shall provide a size 0 or larger shovel with an overall length of not less than 46 inches and a serviceable 5 gallon backpack pump filled with water or a fire extinguisher bearing a label showing at least a 4-A rating must be within 25 feet of each tail and corner block.

Trucks, tractors/skidders, pickups and other similar mobile equipment shall be equipped with and carry at all times a size 0 or larger shovel with an overall length of not less than 46 inches and a 2-1/2 pound axe or larger with an overall length of not less than 28 inches.

All required fire tools shall be maintained in suitable and serviceable condition for fire fighting purposes.

B. Fire Extinguishers

Purchaser shall equip each internal combustion yarder, fuel truck, and loader with a (4-A:60-B:C) fire extinguisher for oil and grease fires.

Skidders and tractors shall be equipped with a minimum 5-BC fire extinguisher.

Fire extinguishers shall be mounted, readily accessible, properly maintained and fully charged.

Purchaser shall equip all mechanized harvesting machines and log processors with hydraulic systems, powered by an internal combustion engine (e.g. masticator, chipper, feller/buncher, harvester, forwarder, Hot Saw, stroke delimber, etc), with at least two 4-A:60-B:C fire extinguishers or an acceptable CAFS substitute identified in Section K.

C. Spark Arresters and Mufflers

Except for tractors and other equipment with exhaust-operated turbochargers, Purchaser shall equip each operating tractor and any other internal combustion engine with an approved spark arrester. There shall be no exhaust bypass on any system.

Spark Arresters shall be a model tested and approved under Forest Service Standard 5100-1a as shown in the National Wildfire Coordinating Group Spark Arrester Guide, Volumes 1 and 2, and shall be properly mounted and maintained according to manufacturer's specifications.

Every motor vehicle subject to registration shall at all times be equipped with an adequate exhaust system meeting the requirements of the California Vehicle Code.

D. Power Saws

Each power saw shall be equipped with a spark arrester approved and maintained in effective working order as identified in the Spark Arrestor Guide in Section C. above and according to applicable parts of CPRC Section 4442 or 4443. An Underwriters Labortories (UL) approved fire extinguisher containing a minimum 14 ounces of fire retardant shall be kept with each operating saw.

A size 0 or larger shovel with an overall length of not less than 38 inches shall be kept with each gas can, but not more than 300 feet from each power saw when used off cleared landing areas.

E. Fire Supervisor & Fire Patrolperson

Purchaser shall designate in the fire plan required by B7.1 and furnish on Sale Area during operating hours a fire supervisor, named in writing and authorized to act on behalf of Purchaser in fire prevention and suppression matters.

Unless agreed otherwise, Purchaser shall furnish and designate in writing, a Fire Patrolperson each operating day when Project Activity Level C or higher is in effect. When on duty, the Fire Patrolperson is required to patrol the operation for the prevention and detection of fires, to take suppression action where necessary and to notify Forest Service as required under Sections I. Reporting Fires and L. Communications. This Fire Patrol is required on foot, unless otherwise agreed.

By written agreement, one Fire Patrolperson may provide patrol on this and adjacent projects or sales. No Fire Patrolperson shall be required on Specified Road construction jobs except during clearing operations unless otherwise specified.

F. Seasonal Permits

Purchaser shall obtain written permits from Forest Service before allowing welding, warming fires or burning, subject to C7.22# – Emergency Precautions.

G. Clearing of Fuels

Purchaser shall clear away, and keep clear, fuels and logging debris as follows:

Welding equipment and stationary log loaders, yarders and other equipment listed in California State Law:	10 feet slope radius
Tail or corner haulback blocks:	All running blocks on a cable yarding operation shall be located in the center of an area that is cleared to mineral soil at least 15 feet in diameter.
Lines near, between or above blocks:	Sufficient clearing to prevent line from rubbing on snags, down logs and other dead woody material.

H. Smoking

All smoking shall be confined within a car, truck, crew rig or other enclosed cab after 1:00 PM on Ev days and all hours on E days (C7.22#). At other times, any smoking shall be done while sitting in an area at least 3 feet in diameter, cleared of flammable materials. Burning tobacco and matches shall be extinguished before they are properly disposed.

I. Reporting Fires

As soon as feasible, but no later than **15 minutes** after discovery, Purchaser shall notify Forest Service of any fires on Sale Area or along roads used by Purchaser.

J. Tank Truck

Purchaser shall provide a water tank truck or trailer on or in proximity to Sale Area during Purchaser's Operations hereunder during Fire Precautionary Period unless otherwise agreed.

Tank truck or trailer shall contain at least 300 gallons of water and comply with the following requirements:

(1) Pump, which at sea level, can deliver 23 gallons per minute at 175 pounds per square inch measured at the pump outlet. Pumps shall be tested on Sale Area by Forest Service using a 5/16 inch orifice with a one inch in line test kit and shall meet or exceed the pressure values identified in the following table for nearest temperature and elevation:

Temp	Sea Level		1000 Feet		2000 Feet		3000 Feet		4000 Feet		5000 Feet		6000 Feet		7000 Feet		8000 Feet		9000 Feet		10000 Feet	
55	179	23	174	23	169	23	165	22	161	22	157	22	153	22	150	21	146	21	142	21	139	21
70	175	23	171	23	166	22	162	22	158	22	154	22	150	21	147	21	143	21	139	21	136	20
85	171	23	168	23	163	22	159	22	155	22	151	21	147	21	144	21	140	21	136	20	133	20
100	168	23	164	23	159	22	155	22	152	22	148	21	144	21	141	21	137	20	133	20	131	20
	PSI	GPM	PSI	GPM	PSI	GPM	PSI	GPM	PSI	GPM	PSI	GPM	PSI	GPM	PSI	GPM	PSI	GPM	PSI	GPM	PSI	GPM

The pump outlet shall be equipped with 1-1/2 inch National Standard Fire Hose thread. A bypass or pressure relief valve shall be provided for other than centrifugal pumps.

(2) 300 feet of 3/4-inch inside diameter rubber-covered high-pressure hose mounted on live reel attached to pump with no segments longer than 50 feet, when measured to the extreme ends of the couplings. Hose shall have reusable compression wedge type 1-inch brass or lightweight couplings (aluminum or plastic). One end of hose shall be equipped with a coupling female section and the other end with a coupling male section. The hose shall, with the nozzle closed, be capable of withstanding 200 PSI pump pressure without leaking, distortions, slipping of couplings, or other failures.

(3) A shut-off combination nozzle that meets the following minimum performance standards when measured at 100 P.S.I. at the nozzle:

	G.P.M.	Horizontal Range
Straight Stream	10	38 feet
Fog Spray	6 - 20	N/A

(4) Sufficient fuel to run pump at least 2 hours and necessary service accessories to facilitate efficient operation of the pump.

(5) When Purchaser is using Hot Saws or Masticators an additional 250 feet of light weight hose, approved by Forest Service, shall be immediately available for use and be capable of connecting to the 300 feet of hose and appurturances in (2) and (3) above.

(6) This equipment and accessories shall be deliverable to a fire in the area of operations and is subject to the requirements for each specific activity level identified in C7.22#.

K. Compressed Air Foam System (CAFS)

A fire suppression system where compressed air is added to water and a foaming agent. By agreement, Purchaser may substitute a CAFS or functional equivalent in lieu of the tank truck, trailer or fire extinguishers, provided it meets or exceeds the following specifications and requirements:

1. Variable foam expansion ratio – 10:1 to 20:1.
2. Units shall be kept fully charged with air; water and foam concentrate as recommended by the manufacturer and have the appropriate tools to service the system.
3. The unit shall contain enough energy to empty tank and clear hose prior to exhausting propellent.
4. The unit shall be capable of being completely recharged within 10 minutes.
5. When used on cable yarding landings, the unit shall be outfitted for immediate attachment to carriage and transported without damage to the unit.

Fire extinguishers required for Hot Saws, Masticators and similar equipment identified in Section B. above may be substituted with a 3 gallon CAFS.

Tank truck, trailer or equivalent may be substituted with a 30 Gallon CAFS with at least 550 feet of one inch hose and an adjustable nozzle with enough water, air and foam concentrate for at least one recharge.

This equipment and accessories shall also be deliverable to a fire in the area of operations and subject to the requirements for each specific activity level identified in C7.22#.

L. Communications

Purchaser shall furnish a serviceable communications system such as a telephone, radio-telephone, radio system or satellite phone connecting each operating side within the Sale Area with Purchaser's headquarters, and capable of notifying Forest Service within **15 minutes** of discovery of any fires on the Sale Area or along Purchaser's haul route. When such headquarters is at a location which makes communication to it clearly impractical, Forest Service may agree to a reasonable alternative notification method.

A Citizen's Band (CB)radio is not acceptable communications.

M. Cable Yarding Tank Unit

When all or part of Included Timber will be harvested by a long span (over 1,500 feet)cable yarding operation, Purchaser shall provide at each active cable yarding landing a tank truck, trailer or acceptable CAFS substitute which can be lifted and transported by the carriage.

The unit shall meet the same requirements as specified for the tank truck, trailer or approved CAFS substitute.

N. Helicopter Yarding Fire Precautions

Purchaser shall provide and maintain fire equipment as follows:

1. The fire tool box required under this provision shall be equipped for attachment to the helicopter long line so that it may be hauled to needed locations. Such attachment device shall not interfere with access to fire tools. Unless agreed otherwise, the fire tool box shall be located at the Active Landing ready for immediate dispatch.
2. An external helibucket readily attachable to the helicopter, with a capacity of at least 500 gallons, and having a remote control door mechanism adequate for rapid dropping of water. The helibucket shall be located at the helicopter service landing and shall be filled with water ready for immediate dispatch unless otherwise agreed.
3. All aircraft used in conjunction with Purchaser's Operations shall be equipped with an operable radio system capable of meeting Region Five avionics requirements.
4. For protection of fuel servicing operations, fire extinguishers which have the following ratings based on the open hose discharge capacity, i.e., "broken hose," of the aircraft fueling system shall be readily available:
   a. Where said capacity does not exceed 200 gallons per minute, at least one approved extinguisher having a minimum rating of 20-B;
   b. Where said capacity is in excess of 200 gallons per minute, but not over 350 gallons per minute, one approved extinguisher having a minimum rating of 80-B;
   c. Where said capacity is in excess of 350 gallons per minute, two approved extinguishers, each having a minimum rating of 80-B.
5. By agreement, a suitable CAFS may also be used in lieu of the above extinguishers.
6. Extinguishers of over 50 pounds gross weight shall be of wheeled type or be mounted on carts to provide mobility and ease of handling.

C7.22# - EMERGENCY PRECAUTIONS *(06/2012)*

Purchaser's Operations shall conform to the limitations or requirements in the Project Activity Level (PAL) table below. Unless otherwise agreed in writing, Project Activity Levels applicable to this project shall be the predicted levels for the Fire Danger Rating Area(s), or fire weather station(s) stated in the Sale Area Map legend.
Forest Service, in its sole discretion, may change the predicted activity level if the current fire suppression situation, weather and vegetation conditions warrant an adjustment. If practicable, Forest Service will determine the following day's activity level by 6:00 PM. Purchaser shall obtain the predicted Project Activity Level from the appropriate Ranger District Office before starting work each day.
Forest Service may change the Project Activity Level Table to other values upon revision of the National Fire Danger Rating System. When Purchaser is notified, the revised Project Activity Levels will supersede the levels in the Project Activity Level Table below.

PROJECT ACTIVITY LEVEL (PAL) - C7.22# - EMERGENCY PRECAUTIONS

PROJECT ACTIVITY LEVEL (PAL) – C7.22# - EMERGENCY PRECAUTIONS

PROJECT ACTIVITY LEVEL TABLE

Level	*Project Activity Minimum Requirements and Restrictions. Restrictions at each level are cumulative.*
A	Minimum required by C7.2#.
B	1. Tank truck, trailer, or approved CAFS substitute shall be on or adjacent to the Active Landing.
C	1. When Hot Saws or Masticators are operating, a tank truck, trailer or approved CAFS substitute shall be within ¼ mile of these operations. Effective communications shall exist between the operator and the Active Landing. 2. Immediately after Mechanical Operations cease, Fire Patrol is required for two hours.
D	1. Immediately after Hot Saw or Masticator operations cease, Fire patrol is required for three hours. 2. No Dead Tree felling after 1:00 PM, except recently dead. 3. No Welding or cutting of metal after 1:00 PM, except by special permit.
Ev	1. The following activities may operate all day: a) Loading and hauling logs decked at approved landings. b) Loading and hauling chips stockpiled at approved landings. c) Servicing equipment at approved sites. d) Dust abatement, road maintenance (Chainsaw use prohibited), culvert installation within cleared area, chip sealing, paving, earth moving or rock aggregate stock pile loading and installation (does not include pit or quarry development). e) Chainsaw and log processing operations associated with loading logs or other forest products at approved landings. 2. Hot Saws or Masticators may operate until 1:00 PM; provided that: a) A tractor or other equipment with a blade capable of constructing fireline is on or adjacent to the active landing or within ¼ mile of the operating equipment. This piece of equipment shall have effective communication with the Hot Saw or Masticator. b) Any additional restrictions specified by the Forest. 3. All other conventional Mechanical Operations are permitted until 1:00 PM. **4. Some operations may be permitted after 1:00 PM, on a case-by-case basis, under the terms of a PAL Ev Variance Agreement. Activities for which a Variance may be issued are:** • **Rubber Tire Skidding** • **Chipping on Landings** • **Helicopter Yarding** • **Fire Salvage** When approved by a Line Officer, a Variance Agreement can be implemented when the criteria specified in the agreement are met and mitigation measures are in place. This approval is good for ten (10) days unless cancelled sooner or extended by the Contracting Officer for an additional ten (10) days. Variance approval can be withdrawn at the sole discretion of Forest Service. Variance approval is contingent on the 7-day fire weather forecast, fuel conditions, site characteristics, current fire situation, state of Purchaser's equipment for prevention and suppression readiness, type of operation and social and community considerations etc. (See attached Project Activity Level Variance Agreement).

E	The following activities may operate all day: 1. Loading and hauling logs decked at approved landings. 2. Loading and hauling chips stockpiled at approved landings. 3. Servicing Equipment at approved sites. 4. Dust abatement, road maintenance (chainsaw use prohibited) or loading stock piles and rock aggregate installation (does not include pit or quarry development). 5. Chainsaw operation associated with loading at approved landings. All other activities are prohibited.

C8.66# (Option 1) - USE OF TIMBER *(04/2004)*

(a) This contract is subject to the Forest Resources Conservation and Shortage Relief Act of 1990, as amended (16 USC 620, et seq.).

(b) Except for **None** determined pursuant to public hearing to be surplus, unprocessed Included Timber shall not be exported from the United States nor used in direct or indirect substitution for unprocessed timber exported from private lands by Purchaser or any person as defined in the Act (16 USC 620e).

(c) Timber in the following form will be considered unprocessed:

(i) Trees or portions of trees or other roundwood not processed to standards and specifications suitable for end product use;

(ii) Lumber, construction timbers, or cants intended for remanufacturing not meeting standards defined in the Act (16 USC 620e); and

(iii) Aspen or other pulpwood bolts exceeding 100 inches in length.

(d) Unless otherwise agreed in writing, unprocessed Included Timber shall be delivered to a domestic processing facility and shall not be mixed with logs intended for export.

(e) Prior to award, during the life of this contract, and for a period of 3 years from Termination Date, Purchaser shall furnish to Forest Service, upon request, records showing the volume and geographic origin of unprocessed timber from private lands exported or sold for export by Purchaser or affiliates.

(f) Prior to delivering unprocessed Included Timber to another party, Purchaser shall require each buyer, exchangee, or recipient to execute an acceptable agreement that will:

(i) Identify the Federal origin of the timber;

(ii) Specify domestic processing for the timber involved;

(iii) Require the execution of such agreements between the parties to any subsequent transactions involving the timber;

(iv) Require that all hammer brands and/or yellow paint must remain on logs until they are either legally exported or domestically processed, whichever is applicable; and

(v) Otherwise comply with the requirements of the Act (16 USC 620d).

(g) No later than 10 days following the execution of any such agreement between Purchaser and another party, Purchaser shall furnish to Forest Service a copy of each such agreement. Purchaser shall retain, for 3 years from Termination Date, the records of all sales, exchanges, or dispositions of all Included Timber.

(h) Upon request, all records dealing with origin and disposition of Included Timber shall be made available to Contracting Officer.

(i) For breach of this Section, Forest Service may terminate this contract and take such other ac-tion as may be provided by statute or regulation, including the imposition of penalties. When terminated by Forest Service under this Section, Forest Service will not be liable for any Claim submitted by Purchaser relating to the termination.

C8.74 - SSTS PROCESSING REQUIREMENTS AND RECORDS *(04/2004)*

To meet the requirements of the Special Salvage Timber Sale (SSTS) Program, established in conjunction with the Small Business Administration, and as found in 13 CFR 121.508, Purchaser agrees:

(a) If any part of Included Timber is to be resold, that, as an eligible logger, it will accomplish a significant portion of the logging operation, exclusive of hauling, with its own employees. "Significant portion" means that Purchaser uses its own employees to accomplish two or more of the following logging elements: (i) felling and bucking, (ii) skidding/yarding, and (iii) loading. Purchaser further agrees to subcon-tract such SSTS logging elements not accomplished with it own employees only to concerns eligible for preferential award of an SSTS.

(b) If Included Timber is not to be resold for manufacture into lumber and timbers, Purchaser will manufacture a significant portion of the logs with its own employees. "Manufacture of logs" means, at a minimum, a breakdown of a log into the rough cut of the finished product. Purchaser further agrees to accomplish the logging of SSTS timber, exclusive of hauling, with its own employees or to subcontract such logging only to concerns eligible for preferential award of an SSTS.

(c) Upon request of Contracting Officer or an officer of the Small Business Administration, Purchaser shall furnish all records sufficient to verify eligibility and compliance with the requirements of this program. Such records may include employee payroll records, subcontracting records, disposition of Included Timber records, and other documents as necessary.

Failure to provide records upon request, filing false information, or making false statements relating to SBA size status or failing to comply with the disposition and manufacturing requirements of Included Timber shall be considered a breach of this Subsection and may result in termination of this contract pursuant to B9.3.