

USDA FOREST SERVICE, R-4

SECTION 311000 – FENCE-LINE CLEARING AND GRUBBING

PART 1 - GENERAL

1.1 SUMMARY

- A. This work shall consist of clearing, grubbing, trimming, removing, and disposing of Brush and trees in the fence-line right of way. This work shall also include preservation of vegetation and objects designated to remain from injury or defacement.

1.2 RELATED SECTIONS

- A. Section 024100 “Waste Material Disposal.”

1.3 DEFINITIONS

- A. Areas to be Cleared and Grubbed - The limits of clearing and grubbing will be established by this specification, by other specification items, or on contract Drawings. The clearing and grubbing limits will normally coincide with the designated working limits; however, the Contracting Officer may also designate individual trees and snags outside the clearing limits for selective removal and disposal, or he may designate areas within the working limits where clearing and grubbing is not required or allowed within the provisions of this specification.
 - 1. Grading Limits – N/A.
 - 2. Working Limits - Area consisting of room for sawyers and equipment to maneuver to perform the necessary clearing and grubbing. These limits, to be held to a minimum.
 - 3. Clearing Limits – 10 foot wide right of way may be cleared plus any additional overhead trimming needed to operate a boom or other equipment.

1.4 MEASUREMENT AND PAYMENT

- A. There will be no separate measurement or payment for work in this Section. Clearing and Grubbing is considered incidental to other items of work shown in the Schedule of Items.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 CLEARING AND GRUBBING

- A. All trees, brush, shrubs, stumps, roots, and other vegetative material and debris within the designated clearing limits, may be cleared, and scattered away from fence-line. No

soil will be removed from fence-line right of way only above ground disturbance is allowed.

END OF SECTION 311000

July 2014