

WORK LIST

STATION Sta./Ft.	DESCRIPTION OF WORK / PRE-HAUL MAINTENANCE
0+00	Begin Surface Blading (Motor Grader) at intersection of NFSR 583 & 583D. Place 15 tons of aggregate road base.
3+00	Place 15 tons of aggregate road base 30 ft each way.
6+00	Place 15 tons of aggregate road base 30 ft each way.
9+00	Place 15 tons of aggregate road base 30 ft each way.
12+00	Place 15 tons of aggregate road base 30 ft each way.
16+00	End of Roadwork.
<ul style="list-style-type: none">• 1030 Surface Blading (Motor Grader) – 0.30 miles @ \$1000.00 per mile = \$300.00• 1040 Spot Surface Repair – 75 tons of Aggregate @ \$ 35.00 per ton = \$2,625.00 <p>Total Estimated Pre-haul Maintenance Cost = \$2,925.00</p>	