C2.11# - TIMBER SUBJECT TO AGREEMENT *(02/1971)*

In addition, there is within Sale Area an unestimated quantity of:

Species	Product
Douglas-fir	Grn Bio Cv

that shall be Included Timber upon written agreement.

C2.3# - RESERVE TREES *(04/2004)*

Notwithstanding the designations for cutting under B2.31, B2.32, B2.33, or B2.34, live or dead **Resource** reserve trees or groups of reserve trees within such cutting units or clearings shall be left uncut. Reserve trees are identified by **Red and white polka dot flagging** and shall be protected in accordance with C6.32#. Units with reserve trees are shown on Sale Area Map.

C2.35# (OPTION 1) - INDIVIDUAL TREE DESIGNATION *(06/2008)*

All **trees not marked with orange paint, in Leave Tree Marked Subdivisions 6, 8, and 9, and all trees in Designation by Description Subdivisions meeting the attached Designate by Description** which meet the minimum tree diameter stated in A2 are designated for cutting. Additional timber to be cut, if any, will be designated for cutting in accordance with B2.37.

Leave trees, Marked with **orange paint**, or identified by **the description in the attached table** are not to be cut, unless designated by the Forest Service.

C3.47# - ABNORMAL DELAY *(09/2004)*

Unless otherwise agreed, felled timber meeting Utilization Standards shall be removed by Purchaser pursuant to B2.2 and shall be presented for Scaling within the time period indicated in the following removal schedule. The number of days shown are consecutive calendar days.

Failure to remove and present such timber for Scaling within the required time limits will be considered abnormal delay, subject to B3.47.

See attached removal schedule.

DESCRIPTION PURSUANT TO C2.35# (OPTION 1) - INDIVIDUAL TREE DESIGNATION
(06/2008)

1. **Leave Tree Marked Subdivisions** 6, 8, and 9 (LTM).

   All trees without orange paint above and below stump height are designated for cutting.

2. **Designate by Description Subdivisions** 1, 2, 3, 4, 5, 7, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20

Definitions and Requirements:

D x D: Designate by Description

D x D Stump Height: Measure at 4.0 inches above the ground on the uphill side of the tree. Minimum stump height left for inspection will be 4 inches.

D x D Diameter: Measure at the D x D specified stump height, outside the existing bark as is, with a diameter tape that is perpendicular to the bole of the tree. Trees with stumps missing all or part of their bark will be measured as presented. Measure to the nearest tenth of an inch.

D x D Spacing: Measured slope distance at 4.0 inches above the ground from the closest point between trees. This does not need to be measured on the uphill side of the tree.

Down Trees: a) A partial or entire tree lying on the ground with an attached root wad; b) a root sprung tree with broken and exposed roots showing above the ground (root sprung trees must remain identifiable as root sprung after logging).

All skyline corridors, tractor skid roads, temporary roads, and landing clearing limits shall be identified and approved per C6.42#, before this provision is implemented.

All Douglas-fir, Western hemlock, Incense cedar, Western red cedar, and True fir leave trees with a D x D diameter 8.0 inches or greater, all other coniferous species leave trees, and all hardwoods trees shall remain standing after logging is complete, except those removed for operational purposes, i.e.: danger, guyline, and corridor trees.

Standing or down trees outside the Subdivision boundaries shall not be used to determine cut trees within the Subdivision.

All Designate by Description Subdivisions

Standing, live Douglas-fir, Western hemlock, Incense cedar, Western red cedar, and True firs must have a D x D diameter of 8.0 inches or greater to qualify as a leave tree to cut other Douglas-fir, Incense cedar, Western red cedar, Western hemlock and True fir trees.

DESCRIPTION PURSUANT TO C2.35# (OPTION 1) - INDIVIDUAL TREE DESIGNATION
(06/2008)
(Continued)

All Designate by Description Subdivisions:

Priority 1. Douglas-fir, Western hemlock, Cedars and True fir trees shall be cut if they are within the DxD spacing distance, from the following table, of a **live** blue "Boundary Cutting Unit" carded, orange painted conifer or hardwood boundary tree that is 8.0 inches stump diameter or larger.

Priority 2. All coniferous trees, except Pines and Pacific Yew, not marked with orange paint above and below stump height, shall be cut if they are within 60.0 feet, at stump height, of a conifer or hardwood (DTR) tree painted with two complete bands of orange paint above stump height and at least one stump mark below stump height.

Priority 3. Douglas-fir, Western hemlock, Cedars, and True fir trees shall be cut if they are within the DxD spacing distance, from the following table, of a **live** conifer tree painted with orange paint above and below stump height.

After the first three priorities have been implemented, Priority 4 will be used to determine the remaining trees in the subdivision to be cut.

Priority 4. Douglas-fir, Western hemlock, Cedars, and True fir trees shall be cut if they are within the DxD spacing distance of a **live** Douglas-fir, **live** Western hemlock, **live** True fir, **live** Incense cedar, or **live** Western red cedar with a larger stump diameter that is inside the unit boundary. Trees outside of the boundary shall not be used to cut trees inside the boundary.

No Pine, Pacific Yew or hardwoods are designated for removal except as needed for normal harvest operations, i.e. yarding corridors, landings, roads, etc.

D x D Designated Spacing Distances:

Subdivision	DxD Spacing Distance
17, 18, 19,and 20	20.0 feet
1, 2, 3, 4, 5, 7, 10, 13, 14, 15, 16, 16A, 16B	19.0 feet

REMOVAL SCHEDULE PURSUANT TO C3.47# - ABNORMAL DELAY (09/2004)

Included Timber	Time Limits
All Subdivisions	60 days after felling is started
All timber decked during construction clearing.	60 days after felling on each Specified Road constructed by Purchaser is initiated.
Timber decked during road construction/reconstruction.	60 days after Forest Service authorizes Purchaser to use roads pursuant to B5.2.

C4.21# (OPTION 1) - TRANSFER OF PURCHASER CREDIT *(07/2001)*

The amount of Purchaser Credit earned on National Forest lands which may be transferred to this contract is limited to_____and from other revested lands within the Forest boundary_____. This limit may be adjusted pursuant to B8.3. Any such adjustment shall be calculated in a manner consistent with the limit computation at time of sale.

Purchaser credit transferred to this contract from other contracts may be used to meet charges for timber subject to B4.2. Transfer of purchaser credit to or from Timber Sale Account shall be made monthly, or at longer intervals, as requested by Purchaser.

C4.211 - DOWNPAYMENT *(06/2007)*

The downpayment amount shown in A18 may not be applied toward any other payment required under the provisions of this contract, except damages determined pursuant to B9.4, transferred to other timber sales, or refunded until (a) stumpage value representing 25 percent of the total bid value of the timber sale has been charged and paid for, or (b) the estimated value of the unscaled timber is equal to or less than the amount of the downpayment, or (c) if 36 CFR 223.49(e) is applicable, the estimated value of the unscaled timber is equal to or less than the amount of the downpayment.

If Forest Service makes a determination that this contract should not have been included under increased downpayment requirements (36 CFR 223.49(e)), the downpayment shall be revised and applied in accordance with 36 CFR 223.49(f).

C4.212 - TEMPORARY REDUCTION OF DOWNPAYMENT *(08/2009)*

Notwithstanding B4.211 or C4.211, upon the Purchaser's written request Forest Service may temporarily reduce the downpayment when Purchaser's scheduled operations are delayed or interrupted for 30 or more consecutive days, or the contract term is extended for 30 or more consecutive days for any of the following reasons:

(1) Forest Service requests or orders Purchaser to delay or interrupt operations for reasons other than breach;

(2) Purchaser interrupts or delays scheduled operations to work on a sale designated by the Forest Service as in urgent need of harvesting; or

(3) An adjustment of the contract term authorized upon a determination of substantial overriding public interest, including a market-related contract term addition, or an urgent removal contract term extension under 36 CFR 223.53.

When Purchaser is not cutting or removing timber under contract during a qualifying period of delay, interruption, or extension listed above the downpayment may be reduced to $1000 or 2 percent of the downpayment amount stated in the contract, whichever is greater. The Purchaser must restore the downpayment to the full amount stated in the contract within 15 days from receipt of the bill for collection and written notice from the Contracting Officer that the basis for temporarily reducing the downpayment no longer exists. Purchaser shall not cut or remove timber on a contract where the downpayment has been temporarily reduced until the downpayment amount stated in the contract is fully restored.

C4.4 - PAYMENTS NOT RECEIVED *(08/2012)*

(a) Payments are due and payable on the date of issue indicated on the bill for collection. When a payment for timber cut and other charges is not received at the location designated by Forest Service by the date specified in the bill for collection for, Contracting Officer will suspend all or any part of Purchaser's Operations until payment or acceptable payment guarantee is received. Other charges include, but are not limited to:

(i) Slash disposal, road maintenance, and contract Scaling deposits;

(ii) Cooperative work at rates established by specific agreement under B4.218;

(iii) Damages pursuant to B9.4;

(iv) Road use fees;

(v) Restoration of downpayment pursuant to B4.22;

(vi) Periodic payments pursuant to B4.213;

(vii) Extension Deposits pursuant to B4.217; and

(viii) Other mandatory deposits.

(b) Failure to pay amounts due by the date specified in the bill for collection shall be considered a breach under B9.3. The 30-day notice period prescribed therein shall begin to run as of the end of business on the date specified for receipt of payments. If the performance or payment is guaranteed by surety bond, the surety will receive a copy of the written notification of breach. Demand will be made on the surety or other institution providing the guarantee or bond instrument for immediate payment 10 days after issuance of written notification of the breach.

(c) Pursuant to the Debt Collection Improvement Act of 1996, as amended, if payment is not received by Forest Service within 15 days after the date of issue indicated on the bill for collection:

(i) Simple interest shall be assessed at the Current Value of Funds Rate as established by the Secretary of the Treasury. Interest will begin to accrue as of the date of issue indicated on the initial bill for collection.

(ii) Debtors will be assessed administrative charges, in addition to the delinquent amount due. Administrative charges are those additional costs incurred by the Government in processing, handling, and collecting delinquent debts.

(iii) A penalty charge of six (6) percent per annum will be assessed on any portion of a debt delinquent more than 90 days. This penalty charge is in addition to interest and administrative charges under paragraphs (c)(i) and (c)(ii). The penalty charge shall accrue from the date of issue indicated on the bill for collection and shall be assessed on all outstanding amounts, including interest and administrative costs assessed under paragraphs (c)(i) and (c)(ii).

(iv) Payments will be credited on the date received by the Federal Depository or Collection Officer designated on the bill for collection.

(d) Forest Service remedies for Purchaser's failure to make payment for timber cut and other charges when due, except for accrual of interest, suspension of all or any part of Purchaser's Operations, and administrative offset, shall be stayed for so long as:

(i) A bona fide dispute exists as to Purchaser's obligation to make such payment and

(ii) Purchaser files and prosecutes a timely Claim.

C5.1# (OPTION 1) - TEMPORARY ROAD AND LANDING CONSTRUCTION *(06/2008)*

In addition to the requirements of B5.1 and B6.63, Purchaser and Forest Service will agree to the design, construction, maintenance, closure, and obliteration of all Temporary Roads.

Construction of Temporary Roads in areas shown on Sale Area Map shall be in accordance with the attached plans or criteria.

Unless otherwise agreed, if Purchaser's Operations require more than 0 cubic **N/A** of rock for Temporary Roads, landings, or other temporary uses, such rock shall be obtained from commercial sources.

PLANS AND/OR CRITERIA PURSUANT TO C5.1# (OPTION 1) - TEMPORARY ROAD AND LANDING CONSTRUCTION (06/2008) **See table**

C5.12# - USE OF ROADS BY PURCHASER *(06/1999)*

Purchaser's use of existing roads identified on Sale Area Map by the following codes is prohibited or subject to restrictive limitations, unless agreed otherwise:

Code	Use Limitations
X	Hauling prohibited
R	Hauling restricted
U	Unsuitable for hauling prior to completion of agreed reconstruction
P	Use prohibited
A	Public use restriction
W	Regulation waiver

Roads coded A will be signed by the Forest Service to inform the public of use restrictions. Purchaser's use of roads coded R, A, or W shall be in accordance with the following restrictions:

See Restricted Road List Table.

C5.1# (OPTION 1) - TEMPORARY ROAD AND LANDING CONSTRUCTION *(06/2008)*

In addition to the requirements of B5.1 and B6.63, Purchaser and Forest Service will agree to the design, construction, maintenance, closure, and obliteration of all Temporary Roads.

Construction of Temporary Roads in areas shown on Sale Area Map shall be in accordance with the attached plans or criteria.

Unless otherwise agreed, if Purchaser's Operations require more than 0 cubic N/A of rock for Temporary Roads, landings, or other temporary uses, such rock shall be obtained from commercial sources.

PLANS AND/OR CRITERIA PURSUANT TO C5.1# (OPTION 1) - TEMPORARY ROAD AND LANDING CONSTRUCTION (06/2008) **See table**

C5.12# - USE OF ROADS BY PURCHASER *(06/1999)*

Purchaser's use of existing roads identified on Sale Area Map by the following codes is prohibited or subject to restrictive limitations, unless agreed otherwise:

Code	Use Limitations
X	Hauling prohibited
R	Hauling restricted
U	Unsuitable for hauling prior to completion of agreed reconstruction
P	Use prohibited
A	Public use restriction
W	Regulation waiver

Roads coded A will be signed by the Forest Service to inform the public of use restrictions. Purchaser's use of roads coded R, A, or W shall be in accordance with the following restrictions:

See Restricted Road List Table.

PLANS AND Criteria PURSUANT TO C5.1# (OPTION1)-
TEMPORARY ROAD AND LANDING CONSTRUCTION (0/2008)
(Continued)

1. The Forest Service and Purchaser shall agree to temporary road locations and clearing limits prior to construction.

2. Temporary roads shall be constructed to a minimum width to accommodate logging equipment and shall be located to minimize the number of trees cut, and minimize the extent of ground impacted by construction.

3. All trees to be cut by the purchaser shall be identified, and designated for cutting by the Forest Service, prior to cutting.

4. On native running surfaces, hauling shall be restricted to when dry conditions exist, approximately May 31 to November 1. If temporary roads are to be used when wet conditions exist, enough rock surfacing shall be placed on the road to prevent sedimentation.

5. Weed free straw bales and/or other agreed upon erosion control devices shall be placed along the road, as needed, to prevent sediment from entering stream courses.

6. Clearing and grubbing debris shall be scattered in areas designated on the ground by the Forest Service.

7. At the end of each season, or if the road is not being used for an extended period of wet weather, purchaser shall install drivable drain dips and water bars, or other erosion control measures as agreed to by the Forest Service, to stabilize the road and prevent erosion (on slopes over 8%, this may require a structure approximately every 100 feet).

8. Culverts shall be placed in all stream courses where they are crossed by temporary roads, and ditchlines adjacent to existing roads, and shall be installed to return the water into the same stream course or ditchline. Culverts shall be strong enough to withstand the weight of logging equipment. Culverts shall not be less than 18" in diameter, but shall be large enough to transport all water running down the stream course or ditchline, unless otherwise agreed to in writing.

9. Culvert installation in live streams shall take place between **July 1 and August 31**. During culvert installation in live streams, the stream shall be temporarily diverted around the site and biodegradable geotextile cloth will be placed downstream from the site to minimize transport of sediment, unless other methods are agreed to in writing with the Forest Service.

10. At the end of temporary road use, culverts will be pulled and removed off of Forest Service land, the roadbed scarified to below the compacted layer, the roadbed recontoured to facilitate stream flow, water bars will be installed, and erosion control methods will be used to stabilize the road and prevent erosion.

11. Landings shall be designed in accordance with B6.422, shall be as small as operationally feasible, and shall be agreed to in writing with the Forest Service.

12. Areas to be covered with fill material shall be cleared of logs and cull woody material over 4 inches in diameter and/or 8 feet long.

13. Where side slopes exceed 45 percent, waste material shall be utilized in other areas of the road, or end-hauled to locations authorized in writing by the Forest Service.

14. Placement of rock ballast shall not take place unless mutually agreed to in writing by the Forest Service.

15. Rock ballast shall not exceed 4 inches in depth, unless mutually agreed to in writing by the Forest Service. Landing cut and fill slopes shall be left at no steeper than 1 ½ to one upon completion of sale operations.

TABLE A PURSUANT TO C5.12# - USE OF ROADS BY PURCHASER (06/1999)

Restricted Road List

Road Number	Road Name	Termini		Map Legend	Description of Restrictions
		From	To		
1912272	N/A	MP 0.00	MP 0.35	R	*
1912672	N/A	MP 1.20	MP 1.70	R	*
1912291	N/A	MP 0.00	MP 0.17	R	*
1912000	N/A	MP 0.00	MP 8.10	R	*
1920671	N/A	MP 0.00	MP 0.33	R	*
1920664	N/A	MP 0.00	MP 0.39	R	*
1920661	N/A	MP 0.00	MP 0.42	R	*
1920660	N/A	MP 0.00	MP 4.96	R	*
1920055	N/A	MP 0.00	MP 0.10	R	*
1920052	N/A	MP 0.00	MP 0.25	R	*
1920000	N/A	MP 0.00	MP 1.24	R	*
1900703 (Whiterock pit)	N/A	MP 0.00	EOR	R	*

*Limited structural strength, will not support commercial haul during wet weather conditions.

Title and Date of Governing Road Rules Document:

Road Rules for Commercial Haul Willamette National Forest	**January 1999**
Commercial Road Rules	**Effective Date**

Sale Name: CPH Thin

C5.13# - ROAD COMPLETION DATE *(04/2004)*

Construction of Specified Roads shall be completed no later than 10/31/2015 ; except for earlier construction completion dates for roads listed below:

Road Number	Road Name	Station From	Station To	Completion Date

Completion date is binding on the party that constructs road, whether Purchaser or Forest Service. Contracting Officer shall modify the completion date in writing to conform to the approved Plan of Operations under B6.311 at the request of Purchaser.

When Purchaser elects Forest Service construction of Specified Roads shown in sale advertisement, Forest Service may adjust construction completion date when road construction is delayed or interrupted for causes that qualify for an adjustment of the completion date of Forest Service's road construction contract. When qualifying delays or interruptions of road construction occur, Forest Service shall evaluate such occurrences and document any findings. The current status of any adjustment shall be available to Purchaser on request. Promptly after the end of Normal Operating Season in which qualifying days occur, Forest Service shall give Purchaser written notice of (a) number of qualifying days claimed, and (b) new construction completion dates. After all road construction is complete, Forest Service shall grant Contract Term Adjustment. Such adjustment shall be limited to road completion date delays that occurred during Normal Operating Season.

If Forest Service is responsible for road construction and the actual date of road completion is 1 year or more after the completion date stated above, Purchaser may request a rate redetermination under B3.3 for remaining volume. Such request must be made within 30 days of notification that road construction has been completed. Upon receipt of such request, Forest Service shall redetermine rates using standard methods in effect on the completion date of road construction. Rates to be established shall apply to all timber removed from Sale Area after the effective date of the rate redetermination.

Forest Service shall in no way be responsible for any delay or damage caused by road contractor in performing the road construction, except such delay as may be the fault or negligence of Forest Service.

When Purchaser constructs Specified Roads and requests Contract Term Adjustment, completion dates shall be adjusted by number of days that qualify for such adjustment, provided such qualifying days occur before specified construction completion date. When Purchaser desires to construct an alternate facility under B5.26, Forest Service and Purchaser shall agree, in writing, on a construction completion date for alternate facility. Contract Term Adjustment as noted above will apply. Completion date shall be adjusted where a Design Change or physical changes necessitate a modification of Specified Road construction work that increases the scope or magnitude of the required work.

If Purchaser fails to complete construction of any or all Specified Roads by applicable completion date, as adjusted, Contract Term Extension shall not be granted.

As used in this Subsection, construction of a road is completed when:

(a) Purchaser constructs Specified Roads and Forest Service furnishes Purchaser with written notice of acceptance under B6.36 or

(b) Forest Service constructs road and furnishes Purchaser with written notice authorizing use of road.

Notwithstanding B5.1, Purchaser shall not use a road that Purchaser has elected for Forest Service to construct, until construction is completed and Forest Service furnishes Purchaser with written notice authorizing use of road.

C5.213# - DEPOSIT FOR RECONSTRUCTION ENGINEERING SERVICES *(04/2004)*

Purchaser shall make a cash deposit for engineering services (preconstruction and construction) provided by Forest Service for reconstruction of National Forest system roads necessary to accommodate Purchaser's use under this contract, pursuant to 16 USC 537.

The total amount to be deposited by Purchaser for reconstruction related engineering services to be completed by Forest Service personnel or by public works contract is $ $22,656.00 . Purchaser shall make this deposit at the end of the first full Normal Operating Season or 12 months from contract award, whichever occurs first. In the event a different deposit schedule is agreed to, such deposit shall be due within 15 days after the date of issue indicated on the initial bill for collection, pursuant to B4.4.

The amount of the required deposit will be shown as an associated charge on Purchaser's Timber Sale Account. Forest Service shall retain any unexpended deposit for reconstruction related engineering services.

The deposit for reconstruction related engineering services shall be commensurate with project need and Purchaser's road use. Forest Service shall complete reconstruction related engineering services on the following schedule unless a different completion schedule is agreed in writing:

Road or Facility No.	Termini From	Termini To	Engineering Services Completion Date
Road-1912	0	8.1	10/31/2015
Road-1912672	0	.1	10/31/2015
Road-1920660	0	4.96	10/31/2015
Road-1920661	0	.52	10/31/2015

Reconstruction related engineering services may consist of some or all of the engineering work and expense of: preparing, setting out, controlling, inspecting, and measuring the reconstruction of a National Forest system road.

C5.221# - MATERIAL SOURCES *(04/2004)*

Sources of local materials are designated on Drawings and Sale Area Map. Forest Service assumes responsibility for the quality and quantity of material in designated sources. Purchaser shall determine the equipment and work required to produce the specified product, including the selection of acceptable material that is reasonably available in the source that meets specifications. The designation of source includes the rights of Purchaser to use certain area(s) for plant site, stockpiles, and haul roads.

Should the designated source, due to causes beyond the control of Purchaser, contain insufficient acceptable material, Forest Service will provide another source with adjustment in accordance with B5.253.

When Purchaser elects not to use designated sources, Purchaser shall furnish the specified product with no adjustment in unit rates. Quality testing shall be the responsibility of Purchaser. Test results shall be furnished to Forest Service.

When Purchaser elects not to use designated sources and the Schedule of Items lists pit development separately, cost allowance will be reduced under B5.253 when Forest Service determines the work will not be required.

When materials are subject to a weight measurement, the specific gravity or weight/volume relationship used as a basis for determination of estimated quantities shall be:

Source I **N/A** , Source II **N/A** , and Source III **N/A** .

Purchaser may, when agreed in writing, use on the project such suitable stone, gravel, and sand, or other material found in the excavation, and will earn a cost allowance for the excavation of such materials at the corresponding contract unit price and for the pay items for which the excavated material is used. Purchaser shall replace, without additional cost allowance, sufficient suitable materials to complete the portion of the work that was originally contemplated to be constructed with such material. Purchaser shall not excavate or remove any material, except that which is within the excavation limits, without written authori-zation from Forest Service.

When material is appraised from non-National Forest designated sources, owner charges for the material in terms of unit cost for royalties, purchase of raw materials, or finished products shall be as follows until **N/A** :

See Material Source Table.

Should quantity vary from that estimated, payment to owners shall be for units actually obtained. Purchaser shall make arrangements with owner(s) for measurement and payment for royalties, purchase of raw materials, or finished products, as shown above.

Materials produced or processed from National Forest lands in excess of the quantities required for performance of this contract are the property of Forest Service, unless prior written agreement has been obtained to use excess material on other National Forest sales. Forest Service is not obligated to reimburse Purchaser for the cost of their production.

Materials shall be stored to assure the preservation of their quality and fitness for the work. Stored materials shall be located to facilitate their prompt inspection. Sites on Forest Service administered land, approved by Forest Service, may be used for storage purposes and for the placing of Purchaser's plant equipment. All storage sites provided by Forest Service shall be restored at Purchaser's expense. Purchaser

shall be responsible for making arrangements for storage on other than Forest Service administered lands.

When the construction of the portion of the project for which Temporary Roads used for hauling materials is completed, all such Temporary Roads shall be restored as nearly as practicable to their original ground profile, unless otherwise agreed in writing.

MATERIAL SOURCE TABLE PURSUANT TO C5.221# - MATERIAL SOURCES (04/2004)

Material	Type of Purchase	Owner(s)	Unit of Measure	Unit Price	Estimated Quantity	Total
N/A						

C5.31# - ROAD MAINTENANCE REQUIREMENTS *(07/2001)*

Purchaser shall maintain roads in accordance with the following Contract Road Maintenance Requirements Summary:

See Contract Road Maintenance Requirements Summary Table.

CONTRACT ROAD MAINTENANCE REQUIREMENTS SUMMARY TABLE PURSUANT TO C5.31# - ROAD MAINTENANCE REQUIREMENTS (07/2001)

Contract Road Maintenance Requirements Summary

Road	Termini		Miles	Applicable Prehaul Road Maintenance Specifications									
	From	To		T-803	T-811	T-813	T-831	T-832	T-834	T-838	T-842	T-851	T-854
1912272	Jct. 1912672	Unit 6	0.35	P			P	P	P	P			P
1912372	Jct. 1912	Jct. 1912291	0.50	P			P	P	P	P			P
1912291	Jct. 1912672	Unit 4	0.17	P			P	P	P	P			P
1912	Jct. 19	Unit 5	8.10	P	P		P	P	P		P	P	P
1920671	Jct. 1920660	Unit 18	0.33	P			P	P	P	P			P
1920664	Jct. 1920660	Unit 19	0.39	P			P	P	P	P			P
1920661	Jct. 1920660	Unit 16	0.42	P			P	P	P	P			P
1920660	Jct. 1920	Unit. 7	4.96	P	P		P	P	P	P	P	P	P
1920055	Jct. 1920660	Unit 15	0.10	P			P	P	P	P			P
1920052	Jct. 1920660	EOR	0.25	P			P	P	P	P			P
1920	Jct. 19	Jct. 1920660	1.24	P	P		P	P	P		P	P	P
19	County Maint	Jct 1920	9.32	P			D		D				

P = Purchaser Performance Item, D = Deposit to Forest Service, D3 = Deposit to Third Party

Road	Termini		Miles	Applicable During Haul Road Maintenance Specifications									
	From	To		T-803	T-811	T-813	T-831	T-832	T-834	T-838	T-842	T-851	T-854
1912272	Jct. 1912672	Unit 6	0.35	P			P	P	P	P			P
1912672	Jct. 1912	Jct. 1912291	0.50	P			P	P	P	P			P
1912291	Jct. 1912672	Unit 4	0.17	P			P	P	P	P			P
1912	Jct. 19	Unit 5	8.10	P	P		P	P	P		P	P	P
1920671	Jct. 1920660	Unit 18	0.33	P			P	P	P	P			P
1920664	Jct. 1920660	Unit 19	0.39	P			P	P	P	P			P
1920661	Jct. 1920660	Unit 16	0.42	P			P	P	P	P			P
1920660	Jct. 1920	Unit 7	4.96	P	P		P	P	P		P	P	P
1920055	Jct. 1920660	Unit 15	0.10	P			P	P	P	P			P
1920052	Jct. 1920660	EOR	0.25	P			P	P	P	P			P
1920	Jct. 19	Jct. 1920660	1.24	P	P	P	P	P	P		P	P	P
19	County Maint	Jct. 1920	9.32	P			D		D				

P = Purchaser Performance Item, D = Deposit to Forest Service, D3 = Deposit to Third Party

Road	Termini		Miles	Applicable Post Haul Road Maintenance Specifications									
	From	To		T-803	T-811	T-813	T-831	T-832	T-834	T-838	T-842	T-851	T-854
1912272	Jct. 1912672	Unit 6	0.35				P	P	P	P			
1912672	Jct. 1912	Jct. 1912291	0.50				P	P	P	P			
1912291	Jct. 1912672	Unit 4	0.17				P	P	P	P			
1912	Jct. 19	Unit 5	8.10		P		P	P	P		P		
1920671	Jct. 1920660	Unit 18	0.33				P	P	P	P			
1920664	Jct. 1920660	Unit 19	0.39				P	P	P	P			
1920661	Jct. 1920660	Unit 16	0.42				P	P	P	P			
1920660	Jct. 1920	Unit 7	4.96		P		P	P	P		P		
1920055	Jct. 1920660	Unit 15	0.10				P	P	P	P			
1920052	Jct. 1920660	EOR	0.25				P	P	P	P			
1920	Jct. 19	Jct. 1920660	1.24		P		P	P	P		P		
19	County Maint	Jct. 1920	9.32				D		D				

P = Purchaser Performance Item, D = Deposit to Forest Service, D3 = Deposit to Third Party

Description of work required by the above listed T-specs is shown in the following ROAD MAINTENANCE REQUIREMENTS SPECIFICATION table, and included in the timber sale contract.

ROAD MAINTENANCE REQUIREMENTS SPECIFICATION TABLE PURSUANT TO
C5.31# - ROAD MAINTENANCE REQUIREMENTS (07/2001)
(Continued)

1	2	3			4	5	6			7	8	9	
Road No. and Termini	Special Project Specification	Travel Way			Brush And Log Out	Surfacing	Dust Abatement			Seasonal Maintenance	Snow Removal	Post Haul	
		Width	X Slope	Comp			Product	Applicat. Rate	Width			Block	Treat
1912272		EX	AI		OPT						TS		PR
Jct. 1912672 Unit 6													
1912672		EX	AI		OPT						TS		PR
Jct. 1912 Jct. 1912291													
1912291		EX	AI		OPT						TS		PR
Jct. 1912672 Unit 4													
1912		EX	AI	B	5L;5R*						JU		PR
Jct. 19 Unit 5													
1920671		EX	AI		OPT						TS		PR
Jct. 1920660 Unit 18													
1920664		EX	AI		OPT						TS		PR
Jct. 1920660 Unit 19													
1920661		EX	AI		OPT						TS		PR
Jct. 1920660 Unit 16													
1920660		EX	AI		OPT						TS		PR
Jct. 1920 Unit 7													
1920055		EX	AI		OPT						TS		PR
Jct. 1920660 Unit 15													
1920052		EX	AI		OPT						TS		PR
Jct. 1920660 EOR													
1920		EX	AI	B	5L;5R*	50 CY*					TS		PR
Jct. 19 Jct. 1920660													
19											JU		
County Maint Jct. 1920													

*Distance is measured from bottom of ditchline and roadside shoulder. *Forest Service Grading A

ROAD MAINTENANCE REQUIREMENTS SPECIFICATION CODES TABLE PURSUANT TO C5.31# - ROAD MAINTENANCE REQUIREMENTS (7/01)
(Continued)

Column No.	Heading	Entry	Explanation
	Any	Blank	Except as otherwise described, no entry indicates Purchaser is not authorized or required to perform the work item(s).
	Any	RC	This work requirement applies only when haul of sale related construction materials occurs.
2	Special Project Specification	Number	Entry indicates Special Project Specification which applies.
3	Travel Way	EX	Purchaser shall maintain the traveled way to the width existing upon entry, or at the completion of Specified Road work.
		Numbers	Purchaser shall maintain the traveled way to the standard width indicated by the entry, plus curve widening, in accordance with Section T-811. If required, the road template shall be shaped to this width and to the designated cross slope before haul and during recurring maintenance.
		IS, C, OS, F, or AI	Cross slopes are designated as: IS (Inslope), C (Crown), OS (Outslope), F (Flat), AI (As Is).
		A or B	If compaction is required.
4	Brush and Log Out	Numeric & R and or L	Purchaser shall remove brush for specified width on either or both the right (R) side or left (L) side of road.
		As Staked	Limits of brushing are as staked or marked in the field.
		OPT	Purchaser may use hand or mechanical means of brushing.
		H	Only hand brushing may be used.

ROAD MAINTENANCE REQUIREMENTS SPECIFICATION CODES TABLE PURSUANT TO C5.31# - ROAD MAINTENANCE REQUIREMENTS (7/01)
(Continued)

Column No.	Headings	Entry	Explanation
5	Surfacing	Aggregate Grading	Purchaser shall place surfacing on roads listed according to the grading indicated.
		D	Contractor is to make deposits for listed road maintenance, including surface rock replacement.
6	Dust Abatement	Opt	Product selection is Purchaser's choice from those listed in Section T-812.
		Product Abbr.	Unless otherwise agreed, Purchaser is restricted to product listed corresponding to the abbreviation shown in Section T-812; (i.e., LigS = Lignon Sulfonate) Application rates are estimated amounts.
		EX	Purchaser shall abate dust on the existing width
		Numbers	Purchaser shall abate dust to the width indicated by entry.
7	Seasonal Maintenance	W	Waterbars and/or crossditching shall be required prior to expected seasonal precipitation.
		B	Entrance barriers shall be installed by Purchaser prior to nonuse periods.
8	Snow Removal	TS	Snowplowing authorized for Purchaser's Operations without recreation access being provided per Section T-803 requirements.
		JU	Snowplowing authorized, but must provide for recreation joint use per Section T-803 requirements.
		Blank	Snowplowing is not authorized. Forest Service may authorize plowing by permit when not in conflict with other uses.
9	Post Haul	PR	PR denotes that work is Purchaser's Responsibility to perform.

C5.32# - ROAD MAINTENANCE DEPOSIT SCHEDULE *(07/2001)*

Other provisions herein notwithstanding, when Forest Service requests payment in lieu of Purchaser's performance of road maintenance, Purchaser shall make Required Deposits (16 USC 537) for current and/or deferred road maintenance. Such deposits are based on the estimated volume and distance hauled and Purchaser's commensurate use of each road listed in the Road Maintenance Plan in C5.31#.

Purchaser and Forest Service may agree in writing on adjustment of such rates. If Purchaser uses roads under jurisdiction of Forest Service other than those listed in the Road Maintenance Plan, Forest Service shall establish rates commensurate with Purchaser's use of such roads.

The Required Deposits for Forest Service work in lieu of Purchaser performance and for deferred maintenance is: **$2.45** per **Ton** .

The following table lists who Purchaser will make deposits for road maintenance to, and the rate per unit of measure of the deposit. The Road Maintenance Agreement is available for inspection at the Forest Supervisor's office.

Deposit Made To	Rate	Unit of Measure
N/A		

C6.24# - SITE SPECIFIC PROTECTION MEASURES *(04/2004)*

Special protection measures needed to protect known areas identified on Sale Area Map or on the ground include:

Cultural Resource Protection Measures: **N/A**
Wildlife and Botanical Protection Measures: **All logging and road building activities in Subdivisions 1, 4, 5, 6, 8, 9, and 10 are restricted between March 1 - July 15.**
Cave Resource Protection Measures: **N/A**

C6.29# - PROTECTION OF HABITAT OF NESTING NON-THREATENED, ENDANGERED AND SENSITIVE RAPTORS *(09/2004)*

Location of areas needing special measures for protection of nesting non-TE&S raptors, colony nesting birds, and species with designated protection outlined in the ROD for Amendments to Forest Service and Bureau of Land Management Planning Documents Within the Range of the Northern Spotted Owl (1994), are shown on the Sale Area Map and identified on the ground. Measures needed to protect such areas have been included elsewhere in this contract or as follows: **N/A**
If protection measures prove inadequate or if other such areas are discovered, Forest Service may either terminate the sale under B8.34 or unilaterally modify this contract to provide additional protection regardless of when such facts become known. Discovery of such areas by either party shall be promptly reported to the other party.

In the events of contract modification under this Subsection, Purchaser shall be reimbursed for any additional protection required by the modification, provided that any work or extra protection required shall be subject to prior approval by Forest Service. Amount of reimbursement shall be determined by Forest Service using standard Forest Service rate redetermination methods in effect at time of agreed change and shall be in the form of a reduction in Current Contract Rates unless agreed otherwise in writing. However, in no event may Current Contract Rates be reduced below Base Rates.

C6.315# - SALE OPERATION SCHEDULE *(06/1994)*

Unless otherwise agreed to between Purchaser and Forest Service, Purchaser's Operations shall be performed in accordance with the following schedule.

See attached schedule.

SCHEDULE PURSUANT TO C6.315# - SALE OPERATION SCHEDULE *(06/1994)*

Subdivision	Operating Conditions	Purpose
All	Permanent and temporary road reopening and construction/reconstruction is restricted during the wet season (approximately between November 1 and May 31).	Avoid potential surface erosion of exposed soil.
All permanent and temporary roads	No live instream culvert work from September 1 to June 30.	Minimize input of sediment into streams.
All permanent and temporary native surfaced roads	Native surfaced road use is restricted during the wet season (approximately between November 1 and May 31) unless rocked.	Minimize input of sediment into streams.
All Ground-Based yarding and felling areas	Ground based yarding/felling operations are restricted during the wet season (approximately between November 1 and April 30).	Minimize reduction of soil productivity (minimize additional soil compaction and puddling).

C6.32# - PROTECTION OF RESERVE TREES *(04/2004)*

Purchaser's damage or destruction of reserve trees described in C2.3# will cause serious and substantial silvicultural or other damage to the National Forest. It will be difficult if not impossible to determine the amount of such damage. Therefore, Purchaser shall pay as fixed, agreed, and liquidated damages $ **1,000** for each **Resource** reserve tree and $ **N/A** for each **N/A** reserve tree damaged or destroyed by Purchaser's Operations, in addition to amounts payable under B3.45 and B3.46.

Damage, as used herein, includes any injury to the living crown, bole, or roots of reserve trees. If areas are marked on the ground around such reserve trees, operation of heavy equipment or skidding of products within the area shall be considered to be damage to the tree.

C6.405 - ALTERNATE REMOVAL OF INCLUDED TIMBER *(05/2005)*

Purchaser and Forest Service may agree to alternate removal requirements of Included Timber contained in A2. Alternate removal requirements are to be set forth in an agreement signed by both Purchaser and Contracting Officer. The terms of the agreement binds both parties and becomes part of the timber sale contract.

The development and execution of the agreement is based upon the determination by the Contracting Officer that removal of Included Timber is economically impractical if Purchaser has no ready market for such logs in the tributary area. A tributary area is defined as the area in which the Purchaser and competitors regularly deliver saw logs, or 200 miles from the Sale Area, whichever distance is greater.

The agreement for alternate removal requirements shall be executed prior to removing any timber from the Subdivisions included in the agreement. Alternate removal requirements shall apply only to whole units and not to portions of units. All material meeting alternate removal specifications shall be cut and removed to locations designed in the agreement.

Volumes of material with alternate removal requirements will be determined from the National Cruise report for the sale. Purchaser will be charged for the following:

a) stumpage value at current contract rates of the alternatively removed timber;
b) plus the cost of other work required by the Forest Service to dispose of alternatively removed material;
c) plus the difference between the appraised transportation cost of the Sawtimber and/or Nonsawtimber material involved and the appraised transportation cost of the alternative.
d) Minus any work required to be completed by the Purchaser associated with alternate removal requirements.

Charges will be debited to the Purchaser's timber sale account.

Upon acceptance of the alternate removal requirements, the Subdivision will be removed from the Sale Area under B6.36.

Title to material included in the alternate removal agreement shall remain with the Forest Service.

C6.41# - SPECIFIC REQUIREMENTS *(01/2000)*

Notwithstanding B6.41, B6.411, B6.5 and B6.61, felling objectives shall be accomplished by the type of felling methods and equipment listed herein. Methods or equipment other than those specified may be approved. For Subdivisions shown in the following table, Purchaser shall submit a cutting plan for Forest Service acceptance, prior to the start of felling operations.

See attached table.

TABLE PURSUANT TO C6.41# - SPECIFIC REQUIREMENTS (01/2000)

FELLING METHODS	SUBDIVISIONS
Trees shall be felled away from designated Streamcourses, wet areas, and the Area to Protect (ATP) as shown on Sale Area Map. Direction of felled trees shall also be to the lead, which shall facilitate the yarding operation so damage to residual trees is kept to a minimum. Exceptions to these objectives apply only where safety, or protecting improvements, terrain features, or felling within Subdivision boundaries preclude felling to lead.	All
Trees shall be felled away from the trail as shown on the Sale Area Map. Flaggers shall be required during felling operations.	5
Trees shall be felled away from the section corner and bearing trees in Subdivision 14.	14
Trees shall be felled away from ATP in Subdivisions 5,18, & 19 as shown on the Sale Area Map.	5, 18, 19
FELLING EQUIPMENT	SUBDIVISIONS
Wedges	All

C6.42# - YARDING/SKIDDING REQUIREMENTS *(04/2003)*

Purchaser shall submit for Forest Service approval a Yarding/Skidding Plan prior to the start of felling operations. Requirements other than those specified in the following table may be approved. When appropriate, such approval shall include adjustments in Current Contract Rates and revision of the Sale Area Map. In no such case shall the adjustments result in Current Contract Rates less than Base Rates.

Location of all skid roads and trails, tractor roads, skyline corridors, mechanized harvester trails, forwarder roads, and other log skidding facilities, shall be approved prior to their use or construction.

See attached table for requirements.

TABLE PURSUANT TO C6.42# - YARDING/SKIDDING REQUIREMENTS (04/2003)

	YARDING/SKIDDING REQUIREMENTS	SUBDIVISION
1.	Location of all skyline roads shall be agreed upon prior to felling.	Skyline portions of 1,2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
2.	Except during lateral yarding, the yarding system must keep one end of the log suspended above ground during in haul.	Skyline portions of 1,2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
3.	The carriage shall be positioned such that during lateral yarding, logs are yarded away from stream courses.	Skyline portions of 1,2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
4.	Ground-lead yarding is permitted within 100 feet of subdivision unit boundaries, 100 feet of tail trees, and 100 feet of tower position.	Skyline portions of 1,2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
5.	Skyline roads will be spaced no further apart than 150 feet at back end of road when radial roads are used, and 150 feet center to center where parallel roads are used.	Skyline portions of 1,2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
6.	When skyline, haulback, or other cables pass through areas of residual trees or reproduction more than 18 inches in height, lines shall be pulled out of the residual trees or reproduction area prior to restringing the next skyline road.	Skyline portions of 1,2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
7.	Skyline corridors shall initially be made as narrow as practicable, with corridors being only wide enough to allow free passage of the carriage and turn of logs. The corridors shall normally not exceed 12 feet in width after yarding has been completed.	Skyline portions of 1,2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
8.	The haulback line that is attached to the carriage shall be positioned, so that it remains within the skyline corridor. The objective is to reduce lateral movement in the skyline.	Skyline portions of 1,2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20

TABLE PURSUANT TO C6.42# - YARDING/SKIDDING REQUIREMENTS (04/2003)
(Continued)

	YARDING/SKIDDING REQUIREMENTS	SUBDIVISION
9.	Tail trees and intermediate supports may be necessary to achieve suspension requirements.	Skyline portions of 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
10.	All yarding across stream courses and within 50 feet slope distance of streams is to be done with the logs suspended free of the ground.	Skyline portions of 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
11.	All yarding across wet areas must be done with the Logs suspended free of the ground.	All
12.	Yard away from the Area to Protect (ATP)	5, 18, 19
13.	A slackpulling motorized carriage able to maintain a fixed position on the skyline during lateral yarding and able to pass over intermediate supports is required. The carriage must be capable of lateral yarding up to 75 feet from skyline.	Skyline portions of 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
14.	A yarder with a maximum block height of 50 feet to keep the lines under the canopy is required. Lines may need to be hung across some creeks to get suspension in which case the lines may be above the canopy.	Skyline portions of 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, 16, 16A, 16B, 17, 18, 19, and 20
15.	Ground based yarding equipment will be restricted to designated skid trails at all times and permitted on slopes 30% or less, as approved by the Forest Service.	Tractor portions of 19
16.	Logs shall be tractor skidded with the leading and free of the ground.	Tractor portions of 19
17.	Equipment backing off of designated trails is prohibited unless otherwise agreed to in writing.	Tractor portions of 19
18.	Tractor skid roads shall not exceed 12 feet in width over 90% of the length of the trail when skidding operations are completed.	Tractor portions of 19
19.	Trees adjacent to skid trails will be left as rub trees until surrounding timber removal is complete.	Tractor portions of 19

TABLE PURSUANT TO C6.42# - YARDING/SKIDDING REQUIREMENTS (04/2003)
(Continued)

YARDING/SKIDDING REQUIREMENTS		SUBDIVISION
20.	The maximum overall width of the tractor shall be 10 feet or less.	Tractor portions of 19
21.	Location of all skidtrails/skidroads shall be agreed upon prior to felling.	Tractor portions of 19
22.	On slopes less than 45% and outside of riparian area and no cut-buffers identified on the Sale Area Map, the purchaser may use a track mounted harvester or other similar equipment for the purpose of "pre-bunching" logs. Pre-bunching logs will be restricted according to the requirements as stated in C6.315#. Pre-bunching is defined as the mechanical falling, bucking and bunching of trees. All locations being considered for pre-bunching shall be agreed to by the Forest Service prior to felling. To reach trees identified for removal, the equipment is to have a boom capable of reaching trees at least 25 feet from the approved skid trail. Equipment is required to stay on approved trails working on a slash mat where ever possible. Approved trails/travel ways are to be no less than 50 feet apart. Limit passage on designated travel ways to 2-3 trips (not counting get back roads.) Harvesters will not be allowed to travel closer than 60 feet from any perennial stream channel.	All
23.	Trees shall be felled away from the trail as shown on the Sale Area Map. Flaggers shall be required during felling operations.	5

C6.6# - EROSION CONTROL AND SOIL TREATMENT BY PURCHASER *(04/2014)*

Erosion prevention and control work required by B6.6, shall be completed within 15 calendar days after yarding/skidding operations related to each landing are substantially completed or after Forest Service designation on the ground of work where such designation is required hereunder. Said time limit shall be exclusive of full days lost in Purchaser's Operations due to causes beyond Purchaser's control. Such on the ground designation shall be done as promptly as feasible unless it is agreed that the location of such work can be established without marking on the ground. After September 15, and as long thereafter as operations continue, the work shall be done as promptly as practicable. Damage resulting from Purchaser's Operations due to failure to perform required work shall be repaired by Purchaser.

On slopes greater than **20** percent, erosion control measures will be done with methods other than mechanized equipment, unless otherwise agreed.

Where soil has been disturbed or displaced on Sale Area by Purchaser's Operations and where measures described in B6.6 will not result in satisfactory erosion control or where subsoiling is shown on Sale Area Map, the following shall be performed. If applicable, timing of the work shall be coordinated with required scarification or subsoiling.

(a) Where staked or otherwise marked on the ground by Forest Service, seed, fertilizer, and mulch will be applied as indicated below in the seeding, fertilizing, and mulching schedule. All applications shall be current and done during the period from **March 15 - April 15** to **August 25 - October 1** , unless otherwise agreed to. Applications shall be done only during favorable conditions. If Purchaser and Forest Service agree, seed can be applied and covered within 10 days of ground disturbance, and may be done outside the required periods.

(b) Where shown on Sale Area Map, landings, Temporary Roads and/or skidtrails/roads shall be scarified to a depth of 20 inches to provide a seedbed for grass seed, fertilizer, and mulch. Seed, fertilizer, and mulch shall be spread evenly at the rates shown in the table. When the seed, fertilizer, and mulch are applied in separate operations, the second or third operations shall be within 10 days of the first or second.

(c) Where shown on Sale Area Map, landings, Temporary Roads, and skid trails/roads used by Purchaser shall be subsoiled to a minimum depth of 20 inches, except that Forest Service may agree to lesser depths. Each subsoiler shank shall be equipped with a shoe and wings which has a total width of at least 18 inches. The design of the shank and wings will be such that the treated, compacted soil is slightly lifted and well-fractured rather than plowed, mixed, or displaced. The distance between subsoiler shank passes shall not exceed 36 inches. Treated areas shall span the total width of compaction. Subsoiling shall be kept reasonably current and shall be done during Normal Operating Season unless otherwise agreed.

(d) When agreed to, Purchaser may use alternate methods of erosion control.

Seed shall meet current Forest Service requirements, with the additional requirement that no seed containing any noxious weed seed in excess of established state limitations as listed in the current "State Noxious Weed Requirements Recognized in the Administration of the Federal Seed Act" publication will be used (commonly referred to as the "all states" noxious weed seed list). Seed shall be furnished separately or in mixture in standard containers clearly marked with: (1) seed name; (2) lot number; (3) net weight; (4) percentages of purity and of germination (in case of legumes, percentage of germination to include hard seed); (5) percentage of weed seed content; and (6) certification that no noxious weed seeds in excess of established state standards are present. The contractor shall furnish the Government duplicate signed copies of a certificate, signed by a Registered Seed Technologist or Seed Analyst (certified through either the Association of Official Seed Analysis or the Society of Commercial Seed Technologists), certifying that each lot of seed has been tested in accordance with the Association of Official Seed Analysts Standards within 12 months prior to date of application. This certificate shall include (1) name and address of laboratory, (2) date of test, (3) lot number for each kind of seed, (4) name of seed, (5) percentage of

germination, (6) percentage of purity, (7) percentage of weed seed content, and (8) certification that no noxious weed seeds in excess of established state limitations are present in any kind of seed.

Legume seed shall be inoculated with approved cultures in accordance with the instructions of the manufacturer.

No seed may be applied without prior written approval by the government.

(e) Purchaser may be required to seed areas disturbed by harvest activites to prevent the spread of noxious weeds, or the establishment of new areas.

See attached application schedule.

APPLICATION SCHEDULE PURSUANT TO C6.6# - EROSION CONTROL AND SOIL TREATMENT BY PURCHASER *(04/2014)*

	AREAS	***SEED***		***FERTILIZER***		***MULCH***	
SUBDIVISION OR UNIT NUMBER	***A) SKID TRAILS B) FIRELINES C) TEMP. ROADS D) LANDINGS E) OTHER***	***APPLICATION***		***APPLICATION***		***APPLICATION***	
		SPECIES 1/ MIXTURE	***LBS/AC***	***TYPE 2/***	***LBS/AC***	***TYPE 3/***	***LBS/AC***
ALL	C) TEMP. ROADS D) LANDINGS	FS PROVIDED	20			7/	1500
ALL	E) SYSTEM ROAD CUT AND FILL SLOPES	FS PROVIDED	20			7/	1500

The Purchaser will be required to pay a co-op deposit of $.02/Ton, for the cultivation and harvest of replacement seed of native species for use on future contracts.

1/ For sales in Oregon, the seed shall meet the State certification specifications. Seed must be packaged in containers carrying official certification labels sewn in, glued to, or printed upon the container, with the following information:

1. Variety (if certified as to variety) and kind.
2. Quantity of seed (pounds or bushels).
3. Class of certified seed (blue tags for certified seed).
4. Inspection or lot number traceable to the certifying agency's records.

For sales in Washington, the seed shall be labeled as "Prohibited and Restricted Noxious Weed Free for the State of Washington." The purchaser shall furnish a copy of the seed analysis.

For state of California lands in Region 6, seed must be certified by the state of California, or by an independent agency or company that is approved by the state of California for "prohibited and restricted noxious weed free for the state of California."

For mixtures of seed, each ingredient in excess of 5 percent must be listed with its percentage by weight and its germination percentage.

Legumes must be innoculated with nitrogen fixing bacteria before planting. The label must show the expiration date of the innoculant.

All seed treated with a fungicide or pesticide must be labeled that it is "treated" giving the name of the chemical used, and an appropriate warning or a caution statement.

2/ Fertilizer shall be a standard commercial fertilizer with guaranteed analysis of contents clearly marked on containers.

3/ Mulch shall meet the appropriate State's certification specifications, with evidence of its certification traceable to the certifying agency's records.

7/ Wood Fiber Mulch OR Straw (Organic-Weedfree)

C6.7 - SLASH DISPOSAL *(06/2008)*

As used in the following Subsections, the term "slash" is vegetative debris including, but not limited to, cull logs, blasted or pushed-out stumps, chunks, broken tops, limbs, branches, rotten wood, damaged brush, damaged or destroyed reproduction, saplings or poles, resulting from Purchaser's Operations.

Any burning of slash or refuse by Purchaser is subject to C7.201.

Forest Service may agree to substitute methods of slash disposal if such substitute methods will give equally satisfactory results.

Forest Service may waive specific slash treatment requirements. Purchaser's Timber Sale Account will be charged for any slash treatment requirements waived or for work taken over by Forest Service. The amount of such charges will be determined by Forest Service if Purchaser has not begun felling operations. If felling operations have begun, charges will be determined by mutual agreement.

Forest Service may enter into a written agreement with the Purchaser for the Purchaser to complete slash disposal work originally scheduled to be done by the Forest Service. The agreement will describe the work to be completed by the Purchaser, and the value of such work. Value of the work to be done will be based upon the slash disposal plan in which the cooperative deposits were calculated, and will include Forest Service overhead. Any deposits paid by the Purchaser for this work will be credited to the Purchaser's timber sale account. This work is in addition to that required by C6.74#.

Forest Service may also enter into a written agreement with Purchaser for the Purchaser to remove slash from landings, subject to B3.41. Brush disposal deposits paid by the Purchaser for the Forest Service to burn landing piles will be credited to the Purchaser's timber sale account in the amount shown in the brush disposal plan, less the amount needed by the Forest Service for final cleanup of the landings following removal of the landing slash piles by the Purchaser. The credit will be made following the final removal by the Purchaser of all Included Timber, and slash piles, from the Sale Area.

C6.74# - SLASH TREATMENT REQUIREMENTS *(02/2002)*

Purchaser shall pile, burn, yard, construct firelines or otherwise treat slash defined in C6.7, within designated areas. Work required of Purchaser shall be in accordance with the attached slash plan, specifications, and Sale Area Map.

Unless otherwise agreed, or shown in the attached slash plan or specifications, when Included Timber is removed during Normal Operating Season, required slash work shall be completed within 30 days of removal of approximately three-quarters of the volume in the unit. When Included Timber is removed outside Normal Operating Season, required work will be completed within 30 days of the beginning of the next Normal Operating Season.

See attached specifications.

SPECIFICATIONS PURSUANT TO C6.74# - SLASH TREATMENT REQUIREMENTS (02/2002)

In accordance with Contract Provision C6.74#, SLASH TREATMENT REQUIREMENTS, the following is the detailed Slash Disposal Plan:

I. Yarding Tops and Limbs Left Attached to Logs

During the skyline and tractor yarding of timber in all Subdivisions, tops and limbs will be left attached to all logs and will be yarded to the landings. For safe and efficient operations at the landings, to keep landing size small and to keep piles from burning too long and hot, the larger unutilized material (over 2 inches in diameter outside bark on the small end and at least 6 feet long), shall be limbed, severed, and stacked in a parallel position in a separate pile, unless otherwise agreed to in writing by the Forest Service. On temporary roads, if the landing area is large enough, this requirement may be waived. The location of piles and method of piling shall be in accordance with the specifications listed below in section II (Machine Piling of Landing and Roadside Clean-up Slash).

II. Machine Piling of Landing and Roadside Clean-up Slash

A. Slash to be piled

The purchaser is responsible for machine piling all unutilized material resulting from logging operations at all landings, and within 25 feet from the edge of roads 1912, 1912672, 1912291, 1912272, 1920660, 1920664, 1920671, and 1920055 inside the adjacent Subdivisions. This will include piling within 25 feet from both sides of the roads where the Subdivision is on both sides of the road. The machine used to grapple pile the slash shall stay on the road surface. Material to be piled will include all material at least 1 inch in diameter on the small end, and at least 3 feet in length. This may include chunks, broken tops, and limbs, branches, rotten wood, and brush, damaged or destroyed reproduction, and saplings or poles created by any type of vegetative cutting or clearing.

For safe and efficient operations at landings, to keep landing size small and keep piles from burning too long and hot, besides the top material, any additional larger unutilized material (over 6 inches diameter outside bark on the small end, and at least 2 feet in length) shall be stacked in a parallel position in or beside the same pile as the larger top material, unless otherwise agreed to in writing by the Forest Service.

B. Location of piles

Piles will be located so as to minimize damage to standing green trees during burning. Unless otherwise approved by Forest Service, piles will be constructed to be equal distance between the boles of standing green trees, or at least 20 feet from a standing green tree where the trees are farther apart. Piles will not be placed where they will interfere with functioning of drainage structures, ditches, or stream channels.

C. Construction and size of piles

Piles shall be constructed using a 'lift and stack' method using equipment with a hydraulic attachment mechanism capable of constructing piles that are compact and free of dirt and rocks. Completed piles shall be approximately equal in height and width, and shall not exceed 10 feet in height. In piles where the tops are permitted to be piled in the same pile as the other slash, piles may be up to 15 feet in height.

C6.815 - THIRD PARTY SCALING SERVICES *(04/2004)*

Notwithstanding the requirement for Forest Service or parties under contract to Forest Service to provide Scaling services under B6.81, Scaling designated in A10 shall be conducted by a third party Scaling organization approved by Forest Service. Scaling shall be done in accordance with A9 and Purchaser shall bear costs for Scaling service.

In the event third party Scaling service is suspended for causes such as strikes, termination of third party's approval to Scale National Forest logs by Forest Service, or Purchaser's failure to pay third party Scaling costs, hauling operations shall be suspended until agreed alternate Scaling services are provided or service by third party is resumed.

When an approved alternate Scaling location pursuant to B6.811 does not have an approved third party scaling organization as a commonly used Scaling services provider, Forest Service or parties under contract to Forest Service shall provide Scaling services at the approved alternate location. In such an event, the cost of waived third party Scaling listed in A10 shall be charged to Timber Sale Account.

If Forest Service and Purchaser agree in writing that another party under contract to Forest Service will perform Scaling, the contract will be modified to include C6.816 and Timber Sale Account will be charged for such Scaling.

C6.84 (OPTION 1) - USE OF PAINT BY PURCHASER *(05/2005)*

Notwithstanding B6.842, use of paint by the Purchaser within the Sale Area in the color(s) used by the Forest Service in the preparation of the sale and administration of the contract will be by written approval of the Forest Service.

C6.840 - ACCOUNTABILITY *(04/2014)*

Notwithstanding B6.84, when Weight scaled contracts offer products at different rates in A4, each product must be completely removed from a landing or decking area before another product can be removed, unless otherwise agreed to in writing by the Contracting Officer.

C6.851 - WEIGHT OF LOST LOADS *(04/2014)*

Purchaser shall present all loads for weighing and shall furnish a weight ticket for each load pursuant to a weighing services agreement. Any load for which a weight ticket is not provided, or the weight ticket is incomplete or unreadable, or does not include the Forest Sevice load receipt number, shall be considered a lost sample load with a net weight equal to the load with the heaviest net weight presented during the billing period, as established by the Forest Service.

C7.1 - PLANS *(09/2004)*

The plan shall state how Purchaser's representative or alternates will be contacted in a fire emergency, both during periods of operation and at other times such as evenings or weekends. Purchaser shall certify compliance with specific fire precautionary measures included as Subsections under C7.2 - Specific Fire Precautions, before beginning operations during Fire Precautionary Period (closed season) and shall update such certification when operations change.

If helicopter yarding is required, the plan shall include a schedule of rates mutually agreed to for computing Purchaser costs incurred toward meeting Purchaser's obligations under A14, or for paying for helicopters controlled by Purchaser and used under Forest Service direction for suppressing Operations Fires or other fires on Sale Area, excluding Negligent Fires.

C7.11 - ADDITIONAL AREA OF FIRE RESPONSIBILITY *(03/1989)*

The area within 200 feet slope distance of the center line of any road constructed or reconstructed under this contract on National Forest lands outside of Sale Area shall be considered as a part of Sale Area in connection with responsibilities under B7.3 and B7.4 until the road has been accepted in writing by Forest Service.

C7.2 - SPECIFIC FIRE PRECAUTIONS *(09/2002)*

When the industrial fire precautions level is I or higher, unless waiver is granted under C7.22, specific required fire precautionary measures are as follows:

A. Fire Security.

Purchaser will designate in writing a person or persons who shall perform fire security services listed below on Sale Area and vicinity. The designated person will be capable of operating Purchaser's communications and fire fighting equipment specified in the contract, excluding helicopters, and of directing the activities of Purchaser's personnel on Forest fires. Such person must report any fire detected to Forest Service within 15 minutes of detection. In lieu of having the designated person perform the required supervisory duties, Purchaser may provide another person meeting the qualifications stated above to direct the activities of Purchaser's personnel and equipment during all fire fighting activities.

Services described shall be for at least 1 hour from the time Purchaser's Operations are shut down. For the purposes of this provision, personnel servicing equipment, and their vehicles, who are not engaged in cutting or welding metal are excluded.

Fire security services shall consist of moving throughout the operation area or areas constantly looking, reporting, and taking suppression action on any fires detected. Where possible, the designated person shall observe inaccessible portions of helicopter operating areas from vantage points within or adjacent to Sale Area.

Purchaser shall furnish fire security services based on the predicted industrial precaution level, obtained by Purchaser from the appropriate Ranger District Headquarters. If predictions made after 6:00 p.m. local time, are significantly different than originally estimated, Forest Service will inform Purchaser when changes in fire security services are indicated.

B. Fire Extinguisher and Equipment (on Trucks, Tractors, Power Saws, etc.).

(a) Each yarder or loader equipped with an internal combustion engine or other spark emitting source shall be equipped with a readily accessible fire extinguisher, with an Underwriter's Laboratory (UL) Rating of at least 5 B,C.

(b) All power-driven equipment operated by Purchaser on National Forest land, except portable fire pumps, shall be equipped with one fire extinguisher having a UL rating of at least 5 B,C and one "D" handled or long handled round point shovel, size O or larger. In addition, each motor patrol, truck and passenger-carrying vehicle shall be equipped with a double-bit axe or Pulaski, 3-1/2 pounds or larger.

(c) Equipment required in (a) and (b) shall be kept in a serviceable condition and shall be readily available.

(d) Each gasoline power saw operator shall be equipped with a pressurized chemical fire extinguisher of not less than 8-ounce capacity by weight, and one long handled round point shovel, size O or larger, except at a landing where a suitable fire extinguisher and shovel are immediately available. The extinguisher will be kept in possession of the saw operator at all times. The shovel shall be accessible to the operator within 1 minute.

(e) Each helicopter shall be equipped with one fire extinguisher having a UL rating of at least 5 B,C mounted inside the aircraft within reach of the pilot's operating position.

(f) One refill for each type or one extra extinguisher sufficient to replace each size extinguisher required on equipment shall be safely stored in the fire tool box or other agreed upon place on Sale Area that is protected and readily available.

(g) At each area where helicopters are being serviced or supplied, a carbon dioxide fire extinguisher with a UL rating of at least 20 B,C will be provided on the site and placed where it is available for immediate use.

C. Spark Arrestors and Mufflers.

Each internal combustion engine shall be equipped with a spark arrester qualified and rated under USDA Forest Service Standard 5100-1a as shown in the National Wildfire Coordination Group Spark Arrester Guide, unless it is:

(a) Equipped with a turbine-driven exhaust supercharger such as the turbocharger. There shall be no exhaust bypass.

(b) A multi-position engine, such as on power saws which must meet the performance levels set forth in the Society of Automotive Engineers (SAE) "multi-positioned small engine exhaust fire ignition standard, SAE recommended practice J335B" as now or hereafter amended.

(c) A passenger carrying vehicle or light truck, or medium truck up to 40,000 GVW, used on roads and equipped with a factory designed muffler complete with baffles and an exhaust system in good working condition.

(d) A heavy duty truck, such as a dump or log truck, or other vehicle used for commercial hauling, used only on roads and equipped with a factory designed muffler and with a vertical stack exhaust system extending above the cab.

Exhaust equipment described in this Subsection, including spark arresters and mufflers, shall be properly installed and constantly maintained in serviceable condition.

D. Fire Tools.

Purchaser shall furnish serviceable fire fighting tools in a readily accessible fire tool box or compartment of sound construction with a hinged lid and hasp so arranged that the box can be secured or sealed. The box shall be red and marked "Fire Tools" in letters at least 1 inch high. It shall contain a minimum of:

(a) Two axes or Pulaskis with a 32 inch handle.

(b) Three adze eye hoes. One Pulaski may be substituted for one adze eye hoe.

(c) Three long handled, round point shovels, size 0 or larger.

E. Tank Truck.

Purchaser shall provide a tank truck or trailer, containing not less than 300 gallons of water, during yarding, skidding, loading, land clearing, right-of-way clearing, mechanical falling, and mechanical treatment of slash. Such tank truck or trailer shall be maintained in a serviceable condition and located within 10 minutes, round trip, from each operating side during Fire Precautionary Period (closed season), except as provided under B7.21.

The tank truck or trailer shall be equipped with a pump capable of discharging 20 gallons of water per minute, using a 1/4 inch nozzle tip, through a 50 foot length of poly or rubber lined hose. In addition, 500 feet of serviceable hard rubber poly or rubber lined or FJRL hose of not less than 1 inch outside diameter, fitted with a nozzle capable of discharging a straight stream of 1/4 inch diameter and a spray pattern shall be immediately available for use. The tank, pump, nozzle and at least 250 feet, of the total 500 feet of hose, shall be connected and ready for use at all times. Synthetic hose may be used by

agreement.

If a trailer is used, it shall be equipped with a hitch to facilitate prompt movement. A serviceable tow vehicle shall be immediately available for attachment to the trailer and must meet the time requirements stated above. Such truck or trailer shall be equipped to operate for a minimum of 8 hours.

Where designated on Sale Area Map, Purchaser shall provide a tank trailer or water source and pumping equipment, including accessories, which can be lifted and transported by the yarding system. The component parts shall meet all specifications above. The tank trailer or water supply and pumping accessories shall be deliverable to a fire, in area of operations, within 15 minutes of detection.

In lieu of the above tank trailer or water supply for helicopter operations, Purchaser may provide a suitable helicopter water bucket with a 300 gallon capacity. When Purchaser provides a water bucket, a water source shall be provided within 5 minutes round trip flight time from operating side.

F. Communications.

During Purchaser's Operations, excluding powersaw falling and bucking, Purchaser shall provide adequate two-way communication facilities to report a fire to Forest Service within 15 minutes of detection. Citizen Band radios (CB's) are not considered adequate two-way communications because FCC Regulations prohibit commercial use.

G. Smoking and Open Fire Restrictions.

Smoking and fires shall be permitted only at the option of Purchaser. Purchaser shall not permit open fires on Sale Area without advance permission in writing from Forest Service.

H. Blasting.

Blasting shall be permitted only for road construction purposes unless advance permission is obtained from Forest Service.

Whenever the Industrial Fire Precaution Level is II or greater, a fire security person equipped with a long handled round point No. 0 or larger shovel and a 5 gallon backpack pump can filled with water, will stay at location of blast for 1 hour after blasting is done. Blasting may be suspended by Forest Service, in areas of high rate of spread and resistance to control.

Fuses shall not be used for blasting. Explosive cords shall not be used without permission of Forest Service, which may specify conditions under which such explosives may be used and precautions to be taken.

I. Compliance with State Fire Laws.

Listing of specific fire precautionary measures in the foregoing Subsections is not intended to relieve Purchaser in any way from compliance with State fire laws covering fire prevention and suppression equipment, applicable to Purchaser's Operations.

J. Aircraft Communications.

Every aircraft used in conjunction with Purchaser's Operations shall be equipped with an operable radio system. The radio system shall be capable of transmitting and receiving on VHF frequency 122.85 Megahertz (MHz) with a minimum output of 5 watts at the transmitter. The system shall be located and installed so that the pilot can operate it while flying. A shielded all-weather broad-band antenna shall be part of the system. Radio and antenna shall be properly installed and maintained.

Upon discovery or notification of a fire on Sale Area, all aircraft pilots controlled by Purchaser shall

monitor VHF frequency 122.85 MHz when within 5 miles of a fire and broadcast their intentions.

K. Logging Block Equipment.

Purchaser shall provide a serviceable 5 gallon backpack pump full of water, one axe, and one long handled round point shovel, size 0 or larger, at each haulback block through which a running line passes.

The area below such blocks must be kept clear of all flammable debris under 4 inches in diameter for a distance of 6 feet in all directions. Material larger than 4 inches that poses a fire risk, such as punky logs, must also be removed.

Purchaser shall avoid line-rub on rocks or woody material which may result in sparks or sufficient heat to cause ignition of fire.

C7.201 - BURNING BY PURCHASER *(01/1993)*

Notwithstanding the Fire Precautionary Period limitation of B7.2, Purchaser is required to obtain written permission from Forest Service prior to any burning on the National Forest Lands.

C7.22 - EMERGENCY FIRE PRECAUTIONS *(09/2004)*

Purchaser shall restrict operations in accordance with the Industrial Fire Precaution Levels attached. Forest Service may change the Industrial Fire Precaution Levels to other values upon revision of the National Fire Danger Rating System and may change the specific Industrial Fire Precaution Levels when such changes are necessary for the protection of the National Forest. When sent to Purchaser, the revised Industrial Fire Precaution Levels will supersede the attached levels.

INDUSTRIAL FIRE PRECAUTIONS SCHEDULE

LEVEL INDUSTRIAL FIRE PRECAUTION

I. Closed Season - Fire precaution requirements are in effect. A Fire Watch/Fire Security is required at this and all higher levels unless otherwise waived.

II. Partial Hootowl - The following may operate only between The hours of 8 p.m. and 1 p.m. local time:

power saws, except at loading sites;
cable yarding;
blasting;
welding or cutting of metal.

III. Partial shutdown - The following are prohibited:

cable yarding - except that gravity operated logging systems employing non-motorized carriages may be operated between the hours of 8 p.m. and 1 p.m. local time when all blocks and moving lines are 10 feet or more above the ground, excluding the line between the carriage and the choker.

power saws - except at loading sites and on tractor/skidder operations between the hours of 8 p.m. and 1 p.m. local time.

In addition, the following are permitted between the hours of 8 p.m. and 1 p.m. local time:

tractor, skidder, feller-buncher, forwarder, or shovel logging operations where tractors, skidders or other equipment with a blade capable of constructing fireline are immediately available to quickly reach and effectively attack a fire start;
mechanized loading and hauling;
blasting;
welding or cutting of metal;
any other spark-emitting operation not specifically mentioned.

IV. General shutdown - All operations are prohibited.

The following definitions shall apply to these Industrial Fire Precaution Levels:

Cable yarding systems: A yarding system employing cables and winches in a fixed position.

Closed Season (Fire Precautionary Period): That time period each year when a fire hazard exists as

described in A12.

Hauling: Where hauling involves transit through more than one shutdown zone/regulated use area, the precaution level at the woods site shall govern the level of haul restrictions, unless prohibited by other than the Industrial Fire Precaution Level system.

Loading sites/woods site: A place where any product or material (including but not limited to logs, firewood, slash, soil, rock, poles, posts, etc.) is placed in or upon a truck or other vehicle.

Advance written waiver of the above precautions may be issued by the Contracting Officer or Forest Service Representative.

Such waiver, or substitute precautions under B7.21, shall prescribe measures to be taken by Purchaser to reduce the risk of ignition, and/or the spread of fire. The Contracting Officer or Forest Service Representative shall consider site specific weather factors, fuel conditions, and specific operations that result in less risk of fire ignition and/or spread than contemplated when precaution level was predicted. Consideration shall also be given to measures that reduce the precaution levels above. Purchaser shall assure that all conditions of such waivers or substitute precautions are met.

Purchaser shall obtain the predicted Industrial Fire Precaution Level from the appropriate Ranger District headquarters. If predictions made after 6:00 p.m., local time, are significantly different than originally estimated, Forest Service will inform Purchaser when changes in restrictions or industrial precautions are indicated.

C8.13 - DISCLAIMER OF EXPRESSED OR IMPLIED WARRANTY *(09/2004)*

Purchaser and Forest Service hereby agree, acknowledge, and accept that there is no expressed or implied warranty provided by the Forest Service that guarantees the Purchaser will be allowed to complete the removal of products sold under the terms of the contract. Upon execution of the contract, Purchaser hereby acknowledges the acceptance of the risk that this contract is subject to interruption or termination as a result of litigation associated with the environmental analysis process used by the Forest Service in the planning of this timber sale. If such interruption or termination occurs due to litigation, Purchaser agrees to accept as full compensation for such interruption remedies pursuant to B8.33, or for termination remedies pursuant to B8.34.

C8.212 - MARKET-RELATED CONTRACT TERM ADDITION *(11/2008)*

The term of this contract may be adjusted when a drastic reduction in wood product prices has occurred in accordance with 36 CFR 223.52. The Producer Price Index used to determine when a drastic reduction in price has occurred is stated in A20. Purchaser will be notified whenever the Chief determines that a drastic reduction in wood product prices has occurred. If the drastic reduction criteria specified in 36 CFR 223.52 are met for 2 consecutive calendar quarters, after contract award date, Contracting Officer will add 1 year to the contract term, upon Purchaser's written request. For each additional consecutive quarter such a drastic reduction occurs, Contracting Officer will, upon written request, add an additional 3 months to the term during Normal Operating Season, except that no single 3-month addition shall extend the term of the contract by more than one year. Contracting Officer must receive Purchaser's written request for a market-related contract term addition before the expiration of this contract.

No more than 3 years shall be added to a contract's term by market-related contract term addition unless the following conditions are met:

(i) The sale was awarded after December 31, 2006; and

(ii) A drastic reduction in wood product prices occurred in at least ten of twelve consecutive quarters during the contract term, but not including the quarter in which the contract was awarded.

For each qualifying quarter meeting the criteria in paragraphs (i) and (ii) of this provision, the Forest Service will, upon the Purchaser's written request, add an additional 3 months during the normal operating season to the contract, except no single 3-month addition shall extend the term of a contract by more than 1 year.

In no event shall a revised contract term exceed 10 years as a result of market-related contract term addition.

Additional contract time may not be granted for those portions of the contract that have a required completion date or for those portions of the contract where Contracting Officer determines that the timber is in need of urgent removal or that timber deterioration or resource damage may result from delay.

C8.3# (OPTION 1) - CONTRACT CHANGES *(06/2004)*

Contract changes involving volumes and/or values will use a weightratio of **2.8090** to convert net CCF cruise volumes to TONS.

C8.4 - PERFORMANCE BY OTHER THAN PURCHASER *(04/2004)*

This Section adds subparagraph (b)(iii) to B8.4 as follows:

(iii) Specifically assumes in writing the obligations of Purchaser as listed in Small Business Certification executed by Purchaser and attached to and made a part of this contract.

C8.66# (Option 1) - USE OF TIMBER *(04/2004)*

(a) This contract is subject to the Forest Resources Conservation and Shortage Relief Act of 1990, as amended (16 USC 620, et seq.).

(b) Except for **Alaska yellow-cedar** determined pursuant to public hearing to be surplus, unprocessed Included Timber shall not be exported from the United States nor used in direct or indirect substitution for unprocessed timber exported from private lands by Purchaser or any person as defined in the Act (16 USC 620e).

(c) Timber in the following form will be considered unprocessed:

(i) Trees or portions of trees or other roundwood not processed to standards and specifications suitable for end product use;

(ii) Lumber, construction timbers, or cants intended for remanufacturing not meeting standards defined in the Act (16 USC 620e); and

(iii) Aspen or other pulpwood bolts exceeding 100 inches in length.

(d) Unless otherwise agreed in writing, unprocessed Included Timber shall be delivered to a domestic processing facility and shall not be mixed with logs intended for export.

(e) Prior to award, during the life of this contract, and for a period of 3 years from Termination Date, Purchaser shall furnish to Forest Service, upon request, records showing the volume and geographic origin of unprocessed timber from private lands exported or sold for export by Purchaser or affiliates.

(f) Prior to delivering unprocessed Included Timber to another party, Purchaser shall require each buyer, exchangee, or recipient to execute an acceptable agreement that will:

(i) Identify the Federal origin of the timber;

(ii) Specify domestic processing for the timber involved;

(iii) Require the execution of such agreements between the parties to any subsequent transactions involving the timber;

(iv) Require that all hammer brands and/or yellow paint must remain on logs until they are either legally exported or domestically processed, whichever is applicable; and

(v) Otherwise comply with the requirements of the Act (16 USC 620d).

(g) No later than 10 days following the execution of any such agreement between Purchaser and another party, Purchaser shall furnish to Forest Service a copy of each such agreement. Purchaser shall retain, for 3 years from Termination Date, the records of all sales, exchanges, or dispositions of all Included Timber.

(h) Upon request, all records dealing with origin and disposition of Included Timber shall be made available to Contracting Officer.

(i) For breach of this Section, Forest Service may terminate this contract and take such other ac-tion as may be provided by statute or regulation, including the imposition of penalties. When terminated by Forest Service under this Section, Forest Service will not be liable for any Claim submitted by Purchaser relating to the termination.

C8.71 - TRIPARTITE LAND EXCHANGE *(04/1999)*

Purchaser agrees that timber values for which cash payment is required under B4.0 may be applied to any land exchange transaction authorized by law under which the owner of offered lands agrees to accept the money value of timber sold for the value of land granted to the United States.

C8.73 - REQUIREMENT FOR SMALL BUSINESS PROCESSING *(04/2004)*

To meet the requirements of the small business timber sale set-aside program, Purchaser shall not sell, trade, exchange, or otherwise convey for processing more than 30 percent (50 percent in Alaska) of the advertised sawtimber volume of this sale to a concern that is not a small business within the meaning of the small business size regulations found in 13 CFR 121.507.

Purchaser shall, at the time of execution of this contract, complete the "Small Business Certification" (SBA form 723) and submit it to Contracting Officer. The completed certification together with its provisions pertaining to the disposition, manufacturing, and record keeping requirements of Included Timber by Purchaser and other small business concerns is hereby made a part of this contract.

Upon request of Contracting Officer or an officer of the Small Business Administration, Purchaser shall furnish all records sufficient to verify eligibility and compliance with the requirements of this program. Such records may include employee payroll records, disposition of Included Timber records, and other documents as necessary.

Failure to provide records upon request, filing false information, or making false statements relating to SBA size status or failing to comply with the disposition and manufacturing requirements of Included Timber shall be considered a breach of this Subsection and may result in termination of this contract pursuant to B9.31.

TRAFFIC CONTROL PLAN AND SPECIFICATIONS PURSUANT TO B6.33 SAFETY

Unless otherwise agreed, the following measures are required to provide adequate warning of hazards for users of roads and trails adjacent to Purchaser's Operations.

Part I. Signing and Other Warning Methods:

(a) Signs. The following signs are required when Purchaser's Operations are in progress adjacent to or on Forest Service controlled roads and trails:

	MINIMUM LETTER SIZE AND LEGEND	MINIMUM SIZE AND SHAPE	WHEN AND WHERE REQUIRED
1.	LOGGING OPERATIONS NEXT <> MILES (4" letters)	24" (rectangle) 36"	Min. 100ft. outside of any continuous work areas, on roads listed in C5.31# and trails listed in Part II.
2.	LOGGING OPERATIONS (3" letters)	24" (diamond) 24"	To be used in conjunction with "Logging Operations Next <> Miles" and where work area is not continuous.
3.	FOR LOGGING USE ONLY (3" letters)	24" (diamond) 24"	Required where roads listed in C5.31# and temporary roads intersect with C5.31# roads. Install a cross ditch to discourage use when sign is covered or removed for extended periods.
4.	TRUCKS (4" letters)	24" (diamond) 24"	At critical intersections on roads listed in C5.31# when traffic is heavy or otherwise exceeds volumes stated in Part II below. Remove or cover when the sign is not applicable.
5.	END LOGGING OPERATIONS (4" letters)	24" (rectangle) 24"	Use in conjunction with "Logging Operations Next <> Miles" and "Logging Operations".
6.	TREE FELLING AHEAD (3" letters)	24" (diamond) 24"	Required 200 feet in advance of danger area where timber is being felled adjacent to all roads, including temporary roads, and trails.
7.	ROAD MACHINERY AHEAD (3" letters)	24" (diamond) 24"	Required at least 200 feet in advance of Purchaser road maintenance operations on roads listed in Schedule C5.31#.

TRAFFIC CONTROL PLAN AND SPECIFICATIONS - B6.33 SAFETY (continued)

All signs shall meet requirements as specified in Parts I and VI of the Manual of Uniform Traffic Control Devices (MUTCD).

Sign borders and lettering shall be black. Borders are ½ inch wide, inset ½ inch from outside edge of sign. All sign backgrounds shall be orange, except signs #1 and 5 which shall be reflectorized orange.

Signs shall be installed on posts, with a 5 foot minimum ground clearance, or on temporary supports complying with MUTCD standards.

All signs are to be removed or covered when operations are interrupted for seasonal nonuse or other extended periods.

Purchaser shall furnish personnel and advance warning signs when cable or helicopter logging above roads or trails, felling adjacent to roads or trails, where logs being bucked may roll into roads or trails, and in areas where fallout from blasting may occur. On roads listed in C5.31# and temporary roads, Purchaser may temporarily block the road in lieu of furnishing flag personnel.

(b) Barricades. On roads listed in C5.31#, if Purchaser's Operations cause the traveled way or road shoulders to be constricted overnight, or longer, by such obstructions as decked logs, parked equipment, or piled slash, Purchaser shall place barricades on both sides of the encroaching obstruction to safely channel traffic around such obstructions. Barricades shall remain in place until the obstruction is removed.

Barricades shall be Type II and meet specifications in MUTCD, Part VI. Barricades must be at least 3 feet high. Rails must be at least 2 feet long. Striping shall be alternating orange and white, sloping at a 45 degree angle, and reflectorized. For rails 2 fee to 3 feet long, striping shall be 4 inches wide. For rails longer than 3 feet, striping shall be 6 inches wide. Two rails, 8-12 inches in width, must face each direction.

Barricades shall be equipped with warning lights which shall be Type A low intensity flashing and shall be maintained so as to be capable of being visible on a clear night from a distance of 3,000 feet.

(c) Other Traffic Control Methods. The posting of CB channel signs may be authorized.

On roads listed in C5.31#, Purchaser may be authorized to install temporary gates, barricades (except cables), or natural barriers. The devices must be installed with the necessary hazard markers, be reasonably passable by Forest Service, and be removed prior to acceptance of the Subdivision being served by the road.

TRAFFIC CONTROL PLAN AND SPECIFICATIONS - B6.33 SAFETY (continued)

Part II. Specified Requirements:

None

Purchaser and Forest Service agree to the above stated requirements of the Traffic Control Plan:

Name	Name
Title	Title
Date	Date