

**KT-GT.9# - STEWARDSHIP PROJECTS**

**Project Number 001:** The C55 & 57 Patroon Stewardship project will include the delivery of **625** tons of **Limestone road base** to be spread on **NFSR 121** in locations as flagged on the ground by the Forest Service.

Another **625** tons of **Limestone road base** will be spread on **NFSR 125** in locations as flagged on the ground by Forest Service.

**TECHNICAL SPECIFICATIONS**

**Equipment Specifications:** Contractor shall furnish equipment of sufficient size and quantity to perform hauling within the allowed time. The equipment shall be able to tail gate spread or belly dump the aggregate. Material will be spread with a motor grader.

**Equipment Inspection:** The government reserves the right to inspect the Contractor's equipment prior to award of the contract and to reject equipment which becomes defective during the course of the work.

**Material:** The mineral aggregate shall be a flexible base, Type A, Grade 2 as per Texas State Department of Transportation specifications.