JOHNSON LAKE TIMBER SALE

TEMPORARY ROAD PLAN-APPRAISAL ALLOWANCE

DATE: 12/23/2014

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
Back-In to P.U. 10		**FR 5350**	**D**				
	0.00-0.03	Construct Back-In Landing off of FR 5350 to PU 10		Each	1	250	$ 250.00
	0.00	Haul and place 20 cy (26 cy loose) 22-A crushed gravel for approach/radii. Place 22-A 4" deep.		CY	20	25	$ 500.00
		Total for P.U. 10					**$ 750.00**
Back-in to P.U. 14		**FR 5350**	**D**				
	0.00-0.03	Construct Back-In Landing off of FR 5350 to PU 14		Each	1	250	$ 250.00
	0.00	Haul and place 20 cy (26 cy loose) 22-A crushed gravel for approach/radii. Place 22-A 4" deep.		CY	20	25	$ 500.00
		Total for P.U. 14					**$ 750.00**
Back-in to P.U. 11 & 14		**FR 5350-H**	**D**				
	0.00-0.03	Use Existing Road for Back-In Landing		Each	1	$100	$ 100.00
	0.00	Haul and place 30cy (39cy loose) pit run gravel for surfacing of radii.		CY	30	11	$ 330.00
		Total for PU 11 & 14					**$ 430.00**
Back-in to P.U. 2		**FR 5357**	**D**				
	0.00-0.03	Construct Back-In Landing off of FR 5357 to PU 2		LS	1	$250	$ 250.00
		Total for PU 2					**$ 250.00**
Back-in to P.U. 3 & 9		**FR 5357**	**D**				
	0.00-0.03	Use Existing Decommissioned Road Bed for Back-In Landing to PU 3 & 9		LS	1	$250	$ 250.00
		Total for PU 3 & 9					**$ 250.00**

Prepared By Eric Cromell
Civil Engineering Technician

JOHNSON LAKE TIMBER SALE

TEMPORARY ROAD PLAN-APPRAISAL ALLOWANCE

DATE: 12/23/2014

Road Number	Mile Post	Item Description	Season of Use	Unit	Quantity	Unit Allowance	Appraisal Allowance
Temp Road to P.U. 12		**Temp Road off of FR 5357**	**D**				
	0.00-0.11	Construct Temporary Road. Clear, grub and shape to crown or outslope as per typical details. As directed by the Forest Service.		Mile	0.11	$6,000	$ 660.00
		Total for Temp Road					**$ 660.00**
		TOTAL TEMP ROAD WORK					**$ 3,090.00**

Prepared By Eric Cromell
Civil Engineering Technician