

Sale Name: *Compartment 52 GCTC RCW Habitat Improvement Project*

Sam Houston N.F.		
NFSR 233A WORK LIST		
STATION MP	DESCRIPTION OF WORK	
0.0	B.O.P. - Intersection of FS 233 and FS 233A	
	Begin blading (Motor Grader).Place 50 tons of Agg.(Limestone) to road surface 4” depth.	
0.165	Begin placing 50 tons of Agg.(Limestone) to road surface 4” depth.	
0.308	Begin placing 25 tons of Agg.(Limestone) to road surface 4” depth.	
0.365	Begin placing 50 tons of Agg.(Limestone) to road surface 4” depth.	
0.600	Begin placing 100 tons of Agg.(Limestone) to road surface 4” depth	
0.770	End blading (Motor Grader).	
	E.O.P. @ FS 233A.	
	1040- Spot Surface Course Placement 275 tons@ \$29.50 (Limestone road base)	\$ 8,112.50
	<u>1020- Blading (Grader) 0.770@ \$ 1,000.00 mile</u>	<u>\$ 770.00</u>
	Total Prehaul Maintenance Cost for NFSR 233A:	\$ 8,882.50
Sam Houston N.F. NFSR 233A		C-52 GCTC Sheet 1 of 1