

Sam Houston N.F.		
NFSR 233D WORK LIST		
STATION MP	DESCRIPTION OF WORK	
0.0	B.O.P. - Intersection of NFSR 233 and NFSR 233D. Begin blading.( Dozer) Begin placing 75 tons Agg.( Limestone) road surface to 4" depth.	
0.036	Clean dip drain lead off ditch right 60' with "J" hook (Dozer)	
0.061	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.141	Clean dip drain lead off ditch right 60' with "J" hook (Dozer). Begin placing 50 tons oversize 1"X3" Agg.(Limestone)	
0.238	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.256	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.301	Clean dip drain lead off ditch left 60' with "J" hook (Dozer).	
0.325	Clean dip drain lead off ditch left 60' with "J" hook (Dozer).	
0.367	Clean dip drain lead off ditch right 60' with "J" hook (Dozer). Begin placing 150 tons oversize 1"X 3" Agg.(Limestone)	
0.385	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.405	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.420	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.480	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.510	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.525	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.550	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.570	Clean dip drain lead off ditch right 60' with "J" hook (Dozer).	
0.660	E.O.P. End blading (Dozer)	
	1020-Blading ( Dozer) .660@ \$1,000.00	\$ 660.00
	1040- Spot Surface Course Placement 75 tons@ \$29.50 (Limestone road base)	\$ 2,212.50
	1040- Spot Surface Course Placement 200 tons@ \$38.00 (Limestone 1"X3" road base)	\$ 7,600.00
	3010- Drainage Structure clean dip drain and construct "J" hooks 16 hrs @ \$65.00 hr.	\$ 1,040.00
	<u>4050- Seeding and Fertilizing 0.75 acres @ \$470.00 acre</u>	<u>\$ 352.50</u>
	<b>Total Prehaul Maintenance Cost for NFSR 233D:</b>	<b>\$ 11,865.00</b>
Sam Houston N.F. NFSR 233D		C-52 GCTC Sheet 1 of 1