

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT REQUIREMENTS

SLASH PLAN AND SPECIFICATIONS
(Umatilla National Forest 6/9/08)

1. MACHINE SLASH PILING SPECIFICATIONS—LANDINGS

Purchaser shall machine pile slash within the designated cutting area as indicated on the Sale Area Map.

Piles shall be constructed using any machine with the ability to construct piles that will meet CT6.74# specification as described below. All material shall be concentrated in one area to the side of the forwarder or skid trail or in any available clearing that is in close proximity to the area where the machine or fellers are harvesting.

1. If using a dozer or skidder, Landing slash shall be piled with a brush blade. Brush blades must be no wider than 10 feet and have teeth that are a minumum of 12 inches apart and 10 inches long.
2. Piles will be located at least 25 feet from the drip line of live trees. Piles shall not be located on road surfaces or ditchlines unless approved by Forest Service.
3. Piles shall not be less than 6 feet wide by 6 feet high and not to exceed more than 15 feet high and 20 feet wide.
4. The Purchaser shall pile all slash located within the used landing area that is greater than 1 inch in diameter and 3 feet long. Any material protruding more than 6 feet from the perimeter of the pile will be cut off and placed in the pile.
5. As is practical, all piles shall be free of dirt and the duff layer will not be disturbed during piling operations.
6. All visual areas (A4 Forest Planning Areas) will have all activity generated debris piled.
7. The Forest Service may approve substitution if deemed necessary by timber sale administrator through consultation with Ranger District fuels person.

2. WHOLE TREE YARDING (WTY)

In Cutting Units No. all the Purchaser shall leave all limbs attached to logs and also leave the top attached to the top log. Limbs and tops shall be removed at the landing.

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT REQUIREMENTS (02/2002)

DESIGNATED PURCHASER WORK
RANKIN SALVAGE TIMBER SALE
SLASH PLAN AND SPECIFICATIONS
Umatilla National Forest Revision 08/09

Spec Cross Ref Nos.	Work Item Identification	Map Symbol	ESTIMATED Amount of Work/Areas to be treated.
1	Machine Slash Piling of decks and landings	MP	<u>32</u> acres within designated areas
2	Whole Tree Yard	WTY	<u>32</u> acres within designated areas