

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT REQUIREMENTS

SLASH PLAN AND SPECIFICATIONS
(Umatilla National Forest 6/9/08)

1. MACHINE SLASH PILING SPECIFICATIONS—LANDINGS AND DECKS

Purchaser shall machine pile slash within the designated landing areas. All slash larger than 1 inch and 2 feet in length shall be piled.

OR

Piles shall be constructed using any machine with the ability to construct piles that will meet CT6.74# specification as described below. All material shall be concentrated in one area to the side of the forwarder or skid trail or in any available clearing that is in close proximity to the area where the machine or fellers are harvesting.

1.) Piles will be located at least 25 feet from the drip line of live trees. Piles shall not be located on road surfaces or ditchlines unless approved by Forest Service.

2.) Piles shall not be less than 6 feet wide by 6 feet high.

3.) The Forest Service may approve substitution if deemed necessary by timber sale administrator through consultation with Ranger District fuels person

4.) Any area where 10 sale and or operational trees per acre are cut will have all slash piled to the specifications above. All visual areas (A4 Forest Planning Areas) will have all activity generated debris piled.

2. WHOLE TREE YARDING (WTY)

In Cutting Units No. 2,3,4,& 5 the Purchaser shall leave all limbs attached to logs and also leave the top attached to the top log. Limbs and tops shall be removed at the landing.

SPECIFICATIONS PURSUANT TO CT6.74# - SLASH TREATMENT
REQUIREMENTS (02/2002)

DESIGNATED PURCHASER WORK
TOMBSTONE COMMERCIAL THINNING TIMBER SALE
SLASH PLAN AND SPECIFICATIONS
Umatilla National Forest Revision 08/09

Spec Cross Ref Nos.	Work Item Identification	Map Symbol	ESTIMATED Amount of Work/Areas to be treated.
1	Landing Piling OR Machine Piling of Slash		<u>54</u> acres within designated areas
2	Whole Tree Yard	WTY	<u>54</u> acres within designated areas