

K-G.3.1.5# - PROJECT OPERATION SCHEDULE. (5/05) Unless otherwise agreed to between Contractor and Forest Service, Contractor's Operations shall be performed in accordance with the following schedule.

See attached schedule.

SCHEDULE PURSUANT TO K-G.3.1.5# - PROJECT OPERATION SCHEDULE (05/2005)

<u>Subdivision</u>	<u>Operation Conditions</u>	<u>Purpose</u>
West half of 36, south half of 201	Prohibit logging related activities, between March 1 to September 30 within ½ mile of an active nest, as verified by wildlife biologist.	Prevent harassment or disturbance to nesting goshawk.
1a, 2a, 4a	Conifers must be commercially removed over winter conditions. Suitable conditions are defined as either frozen ground conditions(frozen to a minimum of four inches), or one foot of packed snow	to avoid detrimental disturbance to soil, cultural and water resources.
<u>All</u>	Restrict haul 1630-197 road from 3-1 to 9-30 for all units.	
197	1540-22 road can only be used during winter conditions, which is defined as soil being frozen to a depth of 4 inches or one foot of packed snow.	to avoid detrimental disturbance to soil and water resources.