

SECTION 01110

SUMMARY OF WORK

PART 1 GENERAL

1.1 DESCRIPTION

- A. The work of this contract consists of installing rubber rolled flooring on the ground floor only of the Gordon Reese Cabin.
- B. All work will be performed under a single contract.

1.2 LOCATION

- A. The Gordon Reese Cabin is located at Chief Joseph Pass off of Montana Hwy #43, 27 miles west of Wisdom.

1.3 CONTRACTOR'S USE OF PREMISES

- A. The Gordon Reese Cabin will be closed to the public during the project.

1.4 SPECIAL CONSTRUCTION REQUIREMENTS

- A. Weekend and Holiday Work Restrictions: No on-site work shall be performed on weekends or federal holidays unless otherwise authorized by the Contracting Officer.

1.5 FIELD VERIFICATION

- A. Contractor is responsible for verifying all dimensions affecting the work of this contract.

1.6 TEMPORARY SERVICES

- A. There is no electrical service, water, or telephone service at the project site.

1.7 TEMPORARY CONTROLS

A. HOUSEKEEPING:

- 1. Keep project neat, orderly, and in a safe condition at all times. All construction debris and shall be cleaned up at the end of each working day and placed in suitable containers.

B. DISPOSAL:

- 1. Dispose of construction debris in a legal manner off of Forest Service property

1.8 CONSTRUCTION MATERIALS

- A. All materials shall be Contractor-furnished.

1.9 PRECONSTRUCTION CONFERENCE

- A. Before the start of construction, the Contracting Officer will arrange pre-construction meeting with the Contractor.

PART 2 PRODUCTS

2.1 RUBBER ROLLED FLOORING

- A. 8mm thick x 4 ft wide roll with 95% color as manufactured by Allied Products, LLC or approved equal. Color shall be #622.

2.2 ADHESIVE

- A. As recommended by flooring manufacturer.

2.3 SEAM SEALER

- A. Sikaflex 227 manufactured by Allied Products, LLC, or approved equal.

2.4 SEALANT

- A. Cleanbreak Rubber Flooring and Mat Sealant manufactured by Allied Products, LLC, or approved equal.

PART 3 EXECUTION

3.1 RUBBER FLOORING

- A. Install rubber roll flooring, seam sealer, and sealant in accordance with the manufacturer's written instructions. Roll flooring shall be laid in continuous lengths across the room; butt joints will not be permitted. Lay flooring tightly to walls, posts, and built-in benches and cabinets, etc. for a finished look. Flooring shall be extended under open counters and range/oven. Contractor is responsible for moving furniture.

PART 4 MEASUREMENT AND PAYMENT

- 4.1 Payment will be made at the contract lump sum price.

END OF SECTION