

Pre-Haul Work list
C-62 Black Forest Stewardship
Angelina National Forest

Roland RD:

MP 2+30

Begin placing 27 tons crushed limestone as flagged on the ground

MP 5+00

Place 54 tons crushed limestone as flagged on the ground

MP 9+00

Place 54 tons crushed limestone as flagged on the ground

McGilberry Rd:

MP 7+50

Begin placing 54 tons crushed limestone as flagged on the ground

MP 27+75

Place 27 tons crushed limestone as flagged on the ground

Note: All aggregate material is limestone road base

Forest Service Cost Estimate: 216 tons @ \$40.00 ton = \$8,640