

Sale Area Map
 Sale Name: Salt Multi Product
 National Forest: Shasta Trinity
 Ranger District: Hayfork
 South Fork Management Unit
 T30N R12W Sections 25, 26, 35, 36
 T30N R11W Sections 31, 32
 T29N R12W Sections 1, 2, 12
 T29N R11W Sections 5, 6, 7, 8
 M.D.M.

Legend

- Sale Area Boundary, B1.1
- Cutting Unit Boundary, C2.35#
- Site Specific, Botanical Protection Measures, B6.24, C6.24#
- Site Specific, Wildlife Protection Measures, B6.24, C6.24#
- Meadow Protection, B6.61
- Site Specific Wetlands Protection Measures, B6.62
- Site Specific, Noxious Weed Exclusion Area, B6.35
- Protect Known Survey Monuments, B6.23
- Road And Water Supply Use, C5.35#
- Forest Service System Roads, B5.12#
- State Highways
- Specified Road Reconstruction, B5.2, A9
- Hauling Restricted, C5.12#
- Hauling Prohibited, C5.12#
- Protection of Improvements, Gas Pipeline, B6.221
- Protection of Improvements, Power/Telephone Line, B6.221
- Streamcourse Protection, B6.5, C6.5
- ITM Designation of Timber, Individual Tree Markings, C2.35#
- LTM Designation of Timber, Leave Tree Markings, C2.35#
- DXSPP Designation By Species And Diameter, C2.352#
- RT Reserve Trees, C2.3#
- DF Directional Felling, C6.41#
- TRAC Ground Based Skidding, B6.42, C6.42#
- ENDL Ground Based Skidding, B6.42, C6.42#
- SPACE Ground Based Skidding, B6.42, C6.42#
- FELL Fell Damaged Small Trees, C6.7#
- WHOLE Whole Tree Yarding, C6.41#
- MACH Machine Pile Logging Slash, C6.7#
- COVER Covering Piles, C6.7#
- SCAT18 Scatter Logging Slash, C6.7#
- VIEW Visible Slash Treatment, C6.7#
- VSS Vegetative Soil Stabilization, C6.6
- SEPM Special Erosion Prevention Measures, C6.6#
- TILL Tillage, C6.6
- WARN Safety, B6.33
- KO Keep Roads Open, B6.22
- WASH Equipment Cleaning, B6.35
- EP Emergency Precautions, C7.22#

Contract Requirments:	Unit, Road, or Subdivision
DF, FELL, WHOLE, SPACE	Units All
ITM	Units 1, 2A, 2B, 2B1, 2CN, 2C1, 2C2, 3, 4, 5, 7, 9, 9A, 9B, 10, 11, 12, 13, 14, 20, 21, 22, 25A, 25B, 25C, 25E, 26, 30A, 30B, 33A, 33B, 33C, 36
LTM, MACH, RT, COVER	Units 17, 18, 40
TRAC, ENDL	Units 1, 2A, 2B, 2B1, 2CN, 2C1, 2C2, 3, 4, 5, 7, 9, 9A, 9B, 10, 11, 12, 13, 14, 17, 18, 20, 21, 22, 25A, 25B, 25C, 25E, 26, 30A, 30B, 33A, 33B, 33C, 36, 40
DXSPP, SCAT 18	Units 1, 2A, 2B, 2B1, 2CN, 2C1, 2C2, 3, 4, 5, 7, 9, 9A, 9B, 10, 11, 12, 13, 14, 20, 21, 22, 25A, 25B, 25C, 25E, 26, 30A, 30B, 33A, 33B, 33C, 36
VIEW	Units 1, 2A, 2B, 2CN, 2C1, 2C2, 26 Specified method: Removal
VSS	All temporary roads, landings, and primary skid roads, not to exceed 36.0 acres.
SEPM	Last 50 feet of skid roads at landings, not to exceed 2.0 acres.
WARN, KO	All roads controlled by Forest Service Sale Area
WASH	Project Activity Level, Area 4
EP	Landlines are approximate.

