Golden Timber Sale

SCHEDULE OF ITEMS					
ROAD 2600705 Reconstruction					
PROJECT LENGTH		1.49 miles			
ITEM NO.	DESCRIPTION	PAY UNIT	QTY.	UNIT COST	TOTAL
15101	Mobilization	Lump Sum	1	$10,942.93	$10,942.93
20358	Removal of corrugated metal pipe, disposal method (a)	Each	1	$358.96	$358.96
20419	Drainage excavation, type leadoff ditch	Foot	30	$6.53	$195.90
30359	Roadway reconditioning, compaction method E	Mile	1.49	$2,481.53	$3,697.48
32211	Aggregate surface course, grading T, compaction method B	Cubic Yard*	1140	$35.68	$40,675.20
40401	Minor hot asphalt concrete	Ton	110.00	$247.95	$27,274.50
60276A	18-inch corrugated aluminized steel pipe, 0.064 thickness, method B	Foot	38	$40.59	$1,542.42
				total	$84,687.39
	*Denotes contract quantity				

Golden Timber Sale

SCHEDULE OF ITEMS					
ROAD 2633700 Reconstruction					
PROJECT LENGTH		1.72 miles			
ITEM NO.	DESCRIPTION	PAY UNIT	QTY.	UNIT COST	TOTAL
15755	Erosion control & pollution prevention	Each	1	$810.58	$810.58
20103	Clearing and grubbing, disposal of tops & limbs (f), logs (f), stumps (f)	Mile	1.72	$698.54	$1,201.49
20358	Removal of corrugated metal pipe, disposal method (a)	Each	1	$384.38	$384.38
20419	Drainage excavation, type leadoff ditch	Foot	120	$5.72	$686.40
25101	Placed riprap, class 4	Cubic Yard*	35	$51.42	$1,799.70
25110	Hand placed riprap	Cubic Yard*	5	$66.03	$330.15
30359	Roadway reconditioning, compaction method B	Mile	1.72	$2,268.28	$3,901.44
32203	Aggregate base, grading Q, compaction method B	Cubic Yard*	20	$39.95	$799.00
32211	Aggregate surface course, grading T, compaction method B	Cubic Yard*	520	$35.68	$18,553.60
60276B	24-inch corrugated aluminized steel pipe, 0.064 thickness, method B	Foot	30	$50.98	$1,529.40
60277	28-inch span x 20-inch rise corrugated steel pipe arch, 0.064-inch thickness, method B	Foot	30	$58.75	$1,762.50
62509	Mulching, dry method	Lump Sum	All	$256.92	$256.92
				Total	$32,015.56
	*Denotes contract quantity				