

Butte Stewardship
Road Work

Decommissioning for Stewardship Projects-

4211539 Rd.- 2.5 miles of Rd., w/ existing waterbars approximately spaced every 100' - 200'. Waterbars will need reconditioning work (re-blading them to specified dimensions) to improve their functioning and construct leadouts where missing. 13 culverts (5 are 18" dia.; 7 are 24" dia.; 1 is 36" dia.) to be removed. Fill quantity over pipes varies- 4 or 5 have substantial fill (estimated to be greater than 500 CY)

4211541 Rd.- 1.7 miles of Rd., w/ existing waterbars approximately spaced every 100' - 200'. Waterbars will need reconditioning work (re-blading them to specified dimensions) to improve their functioning and construct leadouts where missing. 8 culverts (4 are 18" dia.; 1 is 24" dia.; 3 are 30" dia.) to be removed. Fill quantity varies, although only 1 pipe estimated to have substantial fill, in the vicinity of approx. 500 CY.

Rd. Reconstruction, as part of the Timber Sale (road sections to be hauled over)-

93 Rd. – Perform road surface work at mp 2.9, 3.1, 3.85 and 4.3. The work may consist of asphalt removal and replacement w/ aggregate or removal of damaged asphalt and repaving.