

Saddle Timber Sale

SCHEDULE OF ITEMS					
ROAD 1993 Reconstruction					
PROJECT LENGTH		3.35 miles			
ITEM NO.	DESCRIPTION	PAY UNIT	QTY.	UNIT COST	TOTAL
15101	Mobilization	Lump Sum	All	\$11,009.58	\$11,009.58
15755	Erosion control & pollution prevention	Each	1	\$517.59	\$517.59
20103A	Clearing and grubbing, disposal of tops and limbs (f), logs (f), stumps (f)	mile	3.35	\$1,038.92	\$3,480.38
20253	Removal of individual trees, miscellaneous, disposal of tops and limbs (f), logs (f)	each	7	\$208.05	\$1,456.35
20304	Removal of old asphalt	Lump Sum	All	\$1,340.98	\$1,340.98
20358	Removal of corrugated metal pipe, disposal Method (a)	Each	2	\$276.86	\$553.72
20419A	Drainage excavation, type roadway ditch	Foot*	450	\$1.74	\$783.00
20419B	Drainage excavation, type outlet ditch	Foot*	45	\$7.91	\$355.95
25101	Placed riprap, class 4	Cubic Yard*	3	\$151.59	\$454.77
30359	Roadway Reconditioning, compaction E	Mile	3.35	\$877.53	\$2,939.73
32232	Haul and place stockpiled aggregate, compaction method B	Cubic Yard*	340	\$53.78	\$18,285.20
40451	ODOT 3/8- inch dense graded HMAc, level II, asphalt cement PG 64 - 22	Ton	20.47	\$243.60	\$4,986.49
60276A	24-inch corrugated aluminized steel pipe, 0.064-inch thickness, method B	Foot	38	\$50.09	\$1,903.42
60276B	36-inch corrugated aluminized steel pipe, 0.079-inch thickness, method B	Foot	36	\$81.83	\$2,945.88
60710	Reconditioning drainage structures, culvert inlet/outlet	Each	4	\$105.60	\$422.40
62509	Mulching, dry method	Lump Sum	All	\$652.83	\$652.83
				Total	\$52,088.27
	*Denotes contract quantity				

Saddle Timber Sale

SCHEDULE OF ITEMS					
ROAD 300 Reconstruction					
PROJECT LENGTH			0.72 miles		
ITEM NO.	DESCRIPTION	PAY UNIT	QTY.	UNIT COST	TOTAL
20103B	Clearing and grubbing, disposal of tops and limbs (g), logs (i), stumps (f)	Mile	0.72	\$10,017.60	\$7,212.67
20479	Drainage excavation, type roadway ditch	Mile	0.72	\$9,770.04	\$7,034.43
30359	Roadway Reconditioning, compaction E	Mile	0.72	\$3,654.41	\$2,631.18
32211	Aggregate surface course, grading T, compaction method B	Cubic Yard*	480	\$41.24	\$19,795.20
				total	\$36,673.48
	*Denotes contract quantity				