

Attached to the INTEGRATED RESOURCE TIMBER CONTRACT PROPSPECTUS for BP Roadside Stew

20. General

There is one mandatory and one optional stewardship project. It consists of felling dead trees and hazard trees from 7.0 to 11.9 inch dbh and leaving in place. This project is to be done in conjunction with Included Timber removal as much as possible to limit the number of entries into the subdivisions.

See A.4.3 and K-G.9# in the sample contract for more information

Project #	Mandatory or Optional (M or O)	Description	Unit of Measure	Quantity
001	M	Felling of Non-Sawtimber Material in Conjunction with Commercial Sawtimber Harvest	Acres	216
002	O	Felling of Non-Sawtimber Material in Conjunction with Commercial Sawtimber Harvest	Acres	982

Subdivision numbers in the sample contract are different from subdivision numbers on the ground. Subdivisions on the ground with tags GW # are the same as a plain #, i.e., GW 1 on the ground is subdivision 1 in the sample.

There are areas of limited operating periods for one subdivision. If the Forest Service determines nesting has not occurred by a specified date, restriction may be waived. See K-G.3.1.5# and the Contract Area Map for more information.

Table of Restricted Operating Periods Applicable to Operations 1/

Subdivision #	Restriction 1/	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
102	Woodpecker					X	X	X	X				
314, 315	Goshawk			X	X	X	X	X	X				

1/ Refer to contract provisions K-G.2.4# and K-G.3.1.5# in the sample contract for specific dates and restrictions.

There are road segments prohibiting road maintenance from January 15th to August 31st or March 1st to August 31st. See K-F.1.2# for the restricted road list and more information.

Table 1. Subdivision Volume for Included Timber

Unit	Gross MBF	Net MBF	Gross CCF	Net CCF
1	152.461	102.611	256.97	172.93
2	52.506	36.398	86.18	59.35
12	26.253	18.199	43.09	29.67
17	87.51	60.664	143.64	98.91
37	52.506	36.398	86.18	59.35
50	136.413	91.81	229.92	154.72
74	26.253	18.199	43.09	29.67
86	35.004	24.266	57.45	39.56
101	657.99	442.846	1109.01	746.31
102	184.558	124.213	311.06	209.33
103	794.403	534.655	1338.92	901.03
120	8.751	6.066	14.36	9.89
121	43.755	30.332	71.82	49.46
125	24.073	16.202	40.57	27.3
152	569.723	383.44	960.24	646.2
153	160.485	108.011	270.49	182.03
154	256.777	172.818	432.78	291.24
156	152.461	102.611	256.97	172.93
183	17.502	12.133	28.73	19.78
184	35.004	24.266	57.45	39.56
190	32.097	21.602	54.1	36.41
201	288.785	200.191	474	326.41
208	315.038	218.39	517.09	356.08
209	288.785	200.191	474	326.41
210	70.008	48.531	114.91	79.13
211	210.025	145.594	344.73	237.39
214	253.78	175.926	416.54	286.84
215	26.253	18.199	43.09	29.67
244	52.506	36.398	86.18	59.35
304	17.502	12.133	28.73	19.78
305	200.607	135.014	338.11	227.53
306	297.536	206.258	488.36	336.3
307	105.013	72.797	172.36	118.69
308	64.194	43.204	108.2	72.81
309	24.073	16.202	40.57	27.3
310	26.253	18.199	43.09	29.67
311	52.506	36.398	86.18	59.35
312	131.266	90.996	215.45	148.37
313	52.506	36.398	86.18	59.35
314	472.557	327.586	775.64	534.12

315	428.801	297.254	703.82	484.67
365	345.044	232.224	581.55	391.36
370	64.194	43.204	108.2	72.81
383	272.825	183.619	459.83	309.45
413	43.755	30.332	71.82	49.46
422	43.755	30.332	71.82	49.46
423	52.506	36.398	86.18	59.35
428	232.704	156.616	392.21	263.94
433	113.764	78.863	186.73	128.58
454	78.759	54.598	129.27	89.02
646	8.751	6.066	14.36	9.89
TOTALS	8140.537	5555.852	13552.23	9218.16

Tractor logging system(s) were used by the Forest Service in calculating the stump-to-truck cost in the appraisal. **Tractor logging systems are not required by the contract.** However, the contractor is to describe logging systems and yarding methods that will meet the end results as part of their Technical Proposal.

Timber Subject to Agreement

Timber Subject to Agreement consists of other fire salvage subdivisions as shown on the Contract Area Map. Individual subdivisions can be agreed to. The agreement will include utilization specifications for A.2, contract rates for A.4, and all other provisions associated with the agreed to products and/or subdivisions.

The agreement will include all contract provisions pertaining to Included Timber removal in the contract and additional provisions as agreed to by the Forest Service. Additional information on these subdivisions is available upon request.