

Table 5-1

## CIP LIST

## Arterial Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
4300000	2	H/F	A	I/B/C	9	Needs aggregate surfacing or paving from Hwy 97 to MP 5, turnouts, hazard tree removal, asphalt apron at jct. With Hwy 97, and corner at 4.5 mile post needs clearing. Current RAC project for fish passage improvement to replace existing culverts with open bottom structure. Completed RAC project to improve water quality by paving bridge approaches.
4400000	2	F	G	B	9	Hazard tree removal. Completed RAC project to reconstruct sag curve.
4900000	2	F	G	C	9	Fix drainage problems @ Long Prairie culverts, bridge approaches need paving, road junctions with 49 need brush cut, and hazard tree removal.
7000000	1	H/C/F	G	I/B	9	Fix drainage construct lead off ditches, turnouts, hazard tree removal, surface native segment 3.9 miles, and asphalt apron at jct. With Hwy 97.
8300000	1	F	G/C	I	9	Fix sediment problem @ Mosquito cr. Crossing, protect well just west of Jack creek, bridge approaches need paving, hazard tree removal, and brush cut.
8600000	1	F/C	G/C	I	9	Fix sediment problem @ Mosquito and God creek crossing, and decommissioning or rehabilitating old water source, correct under cutting of culvert @ Lost creek near 8607 jct., bridge approaches need paving, asphalt apron at jct. With Hwy 97, hazard tree removal, and brush cut.
8800000	1	F	E/G/C	B	9	Reconstruct crossing @ Round Meadow, road is blocking drainage, Fix road washout @ spring between the 8821 and 390 spur, and construct permeable fill @ crossing near 390 jct., construct permeable fill at Parker Meadow, bridge approaches need paving, surface native segment 9.0 miles, hazard tree removal, and brush cut.
9400000	1	F/C	G	G/B	9	Fix hillside stabilization, Fix sediment problem @ Jack creek between 450 and 460 jct., and 640 road drainage, asphalt apron at jct. with Hwy 97, surface native segment 2.9 miles, road surface stabilization, and brush cut.

Table 5-1

## CIP LIST

## Arterial Roads

[illegible]

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
3300000	3	H	G/J	I	9	Proposed PFSR project to straighten horizontal alignment, replace steep road fill sections and construct additional turnouts.
3334000	3	F	G	B	9	Hazard tree removal. Current road and trailhead project to reconstruct 1.5 miles surfacing and drainage improvements for sediment control.
3413000	3	F	G/C/D	I	9	Fix sediment in Threemile creek. Bull Trout, Key water shed, bridge approaches need paving, and hazard tree removal.
3484000	3	F	G	B	9	Improve trailhead parking area, hazard tree removal, and surfacing.
4465000	2	F	G	B	9	Surface native segment 8.6 miles and hazard tree removal. Completed RAC project to reconstruct sag curves at 4 sites.
4582000	2	H	G	B/I	9	Cut vegetation @ jct. 4990/4582, and surface native segment 8.7 miles. Completed ERO project at Telephone Draw crossing permeable fill constructed to improve meadow surface flow. Current RAC project Buckhorn Spring Camp/cattle water issue install cattle guard..
6210000	2	H	G	B	9	Surface 2.4 miles of native segment and widen through cuts. Completed RAC project, replaced existing culvert with several pipes to distribute flows throughout crossing, raised the elevation of road fill and armored culverts.
8802000	1	F	G	B	9	Replace smashed culvert, fix road drainage, surface native segment 3.4 miles and hazard tree removal.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
8821000	1	F	G	I/B	9	Fix road drainage problems consider possible road relocation, surface native segment 2.3 miles and hazard tree removal.
9418000	1	F	G	B	9	Reconstruct Johnson meadow crossing, Jack cr. culvert, and water chance, surface native segment 2.6 miles and hazard tree removal.
9732000	2	F	G	B/I	9	Winter range, Fisheries, hard to maintain steep grades, signing needs, possible site for ODOT weather station and hazard tree removal.
2220000	2	H	G		8	Construct turnouts, and correct drainage at T.35 R.8 Sec 12 and 13.
3414000	3	F		I	8	Hazard tree removal and surfacing.
3651000	3	F	G/C		8	Realign creek/culvert at Lost creek crossing, bridge approaches need paving, and hazard tree removal.
3664000	3	F	G		8	Hazard tree removal and install additional culverts.
4522000	2	H	G		8	Fix drainage in Sec. 33, reshape template at jct. With Williamson River road.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
5806000	2	F	G		8	Hazard tree removal and drainage work.
7015000	1	H	G		8	Fix drainage and needs brush cut at jct. With Hwy 138.
8677000	1	F	G		8	Fix drainage @ south end of road and brush cut.
9740000	1	F/C	G		8	Fix drainage, asphalt apron at jct. With Hwy 97, and hazard tree removal.
3200000	3	C		B	6	Pothole patching. Proposed PFSR project to convert from paved to aggregate surface to improve driver comfort and safety.
3610000	3	F		I/B	6	Surfacing, hazard tree removal, and turnouts
3660000	3	F		B	6	Surfacing and hazard tree removal.
3852000	3	H/F		B	6	Realign road segment in sec. 35, surfacing, hazard tree removal, and brush cut.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
4542000	2	H/F		B	6	Stabilize road, and hazard tree removal
4650000	2	F		B	6	Surface native segment 2.1 miles, hazard tree removal, and brush cut.
5810000	2	F		B	6	Surfacing and hazard tree removal.
8604000	1	F		I	6	Fix drainage @ Halfway Spring, hazard tree removal, and brush cut.
9718000	2	F/H		B/C	6	Proposed PFSR project to install guard rail. needs brush cut, hazard tree removal, turnouts, surface native segment 1.8 miles, crack fill, patching, and chip seal.
9772000	1	F		C	6	Crack filling, chip seal, line striping, hazard tree removal, and brush cut.
2300000	1	F			5	Hazard tree removal.
3450000	3	F			5	Hazard tree removal and brush cut.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
3637000	3	F			5	Hazard tree removal.
3661000	3	F			5	Hazard tree removal.
3828000	3	F			5	Hazard tree removal.
4554000	2	F			5	Hazard tree removal.
4556000	2	F			5	hazard tree removal and brush cut.
7645000	1	F			5	Hazard tree removal and brush cut.
7646000	2	F			5	Hazard tree removal.
9715000	2	F/C			5	Hazard tree removal, brush cut, and asphalt apron at jct with Hwy 97.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
9774000	1	F/C			5	Hazard tree removal and asphalt apron at jct with Hwy 97.
7649000	1	F			5	Needs vegetation cut at jct with Silver lk rd.
8819000	1	F			5	Brush cut.
8834000	1	F			5	Brush cut.
2228000	2		G	I	4	Right size culvert on south fork of Trout creek at beaver dam, and decommission road from 900 spur to end.
4331000	2		G	I	4	Construct permeable fill. Possible need to reduce haul season.
4526000	2		G/H	I/B	4	Reconstruct Hog creek crossing. Private land issue and surface native segment 4.4 miles.
4591000	2		G	I	4	Fix drainage, reinforce closure.



Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
4922000	2		I	I	4	Road is adjacent to fishery it should be looked at because it proximity to Williamson River, possible wildlife issues.
4983000	2		G	I	4	Fix wet spots. Possible wildlife concern.
5802000	2		G	I	4	Fix road grade and slope erosion. Primary access for private land.
5805000	2		G	I	4	Reconstruct two drainage crossings. Road management and signing issue Edison Special Trust Lands.
5808000	2		G	I	4	Fix erosion first 0.4 miles. EA may plan to obliterate.
5812000	2		G	B	4	Fix drainage and surfacing.
7638000	1		G	I	4	Evaluate drainage problems along entire road. Road may not be necessary since other access exist. Closure may be an alternative way to correct drainage concerns..
8310000	1		G	I	4	Fix drainage, and realignment of east jct. with 83.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
8312000	1		G	I	4	Fix drainage @ Deer Scaffold Spring consider closing road.
8672000	1		G	I	4	Fix drainage, and or possible closure due to Eagles, Heritage, and drainage concerns.
8801000	1		G	I	4	Elevate or relocate road, road is in bottom of drainage.
8817000	1		G	I	4	Evaluate Dempsey spring riparian concern, possible road relocation.
8820000	1		G	I	4	Relocate gate, the gate is currently in a drainage. Evaluate road drainage problems and consider closing a segment and using alternative route.
9407000	1		G	I	4	Fix drainage, possible relocation.
9450000	1		G	I	4	Elevate or relocate North end of road, road is in bottom of drainage.
9730000	2		C	G/I	4	Stabilize road surface, pave bridge approaches. Priority to improve road surface rideability, expecting road use to increase.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
3601000	3		G	C	4	Crack filling, patching, sealing, line striping, shoulder rock and brush cut.
3704000	3		A	C	4	Crack filling, patching, sealing, line striping, and brush cut. Current RAC project to replace multiple culverts with multiple open bottom structures to improve fish passage.
1119000	2		I		3	Gate closure was proposed at junction with Squaw Flat road.
1370000	1		G		3	Reconstruct crossing @Tiny cr.
1390000	1		G		3	Correct drainage at Tiny cr. Crossings.
2242000	2		G		3	Fix erosion problems.
2304000	1		G		3	Fix road drainage its causing erosion near the edge of the gorge.
2308000	1		G		3	Fix washed out culvert@ 140 jct.,crossing at head of Scott cr., road drainage West of Scout Hill, and road drainage at Bear cr. Draw.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
2309000	1		G		3	Fix road drainage into Cavern cr.
2330000	1		G		3	Fix road drainage and soft spots.
3208000	3		G/D		3	Fix crossing at Dry Creek.
3449000	3		G/J		3	Fix drainage, remove ditch sluff, and repair soft spots.
3456000	3		I		3	Need to evaluate all spur roads for decommissioning eagle/spotted owl area.
3639000	3		G		3	Boat launch needs paving.
3659000	3		G		3	Harden Ford.
3732000	3		G		3	Construct additional drainage.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
3750000	3		G		3	Fix Rainbow creek crossing, and drainage in sec. 35.
3787000	3		G/J		3	Fix drainage, wet areas and subgrade slumps.
4083000	2		E/G		3	Replace culvert at end of road, and construct permeable fill at Whiskey creek meadow.
4342000	2		G		3	Fix erosion on grades in sec. 22.
4430000	2		B/G		3	Fix wet areas possible spot surfacing.
4432000	2		B/G		3	Fix wet areas possible spot surfacing.
4437000	2		G		3	Construct permeable fill/culvert at jct. With 4433.
4452000	2		G		3	Fix erosion problems and cut brush.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
4464000	2		B/G		3	Fix drainage and surfacing.
4466000	2		G		3	Fix wet areas.
4469000	2		G		3	Fix wet areas.
4503000	2		G		3	Fix drainage.
4510000	2		G		3	Fix wet areas.
4516000	2		G		3	Fix wet areas in sec. 5..
4519000	2		G		3	Fix low areas @ T. 33 R. 8 Sec. 11 near Slabhouse Spring, construct permeable fill at Slabhouse Spring.
4520000	2		G		3	Completed RAC project, construction of a low water crossing to enhance aquatic habitat.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
4528000	2		G		3	Fix riparian area road crossing @ T.33 R.9 Sec. 9.
4530000	2		G/J		3	Fix subgrade failure in Sec. 15 & 16.
4536000	2		G		3	Fix wet areas south of Beaver Dam Spring Sec. 10 & 11.
4541000	2		G		3	RAC project in progress to remove an existing culvert and road fill section and replace with a permeable fill to eliminate the stream channelization into the meadow.
4552000	2		G		3	Realign road out of drainage.
4584000	2	F	G		3	Fix crossing in Sec. 32 and hazard tree removal.
4648000	2		A/G		3	Current RAC project to replace existing culvert with open bottom structure to improve fish passage at deep creek. Completed RAC project road was reconstructed for 0.5 miles to reduce sediment into the springs at Head of The Williamson river.
4652000	2		G		3	Fix wet areas on East two miles of road.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
4656000	2		E		3	Construct permeable fill at meadow.
4670000	2		G		3	Completed RAC project, construction of a permeable fill across the meadow areas and additional drainage features to reduce sediment into the Sycan River.
4680000	2		E		3	Construct permeable fill at meadow.
4682000	2		E		3	Construct permeable fill at meadow.
4685000	2		G/B		3	Fix drainage and wet spots and bridge approaches.
4947000			G		3	Some ERO projects, remaining crossings should be looked at.
4972000	1		G		3	Fix drainage, and install culvert up hill from 230 jct.
4973000	1		G		3	Fix drainage @ jct with 4972.



Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
4975000	1		G		3	Construct permeable fill at North end crossing.
4975000	1		G		3	Reconstruct Night cr. Crossing.
4990000	2		G		3	Completed ERO project, installed multiple culverts to improve meadow surface flow
5825000	2		G		3	Fix drainage.
5850000	2		A/G		3	Current RAC project on the North Fork Trout Creek to replace existing culvert with open bottom structure to improve fish passage and South Fork to replace existing low-water ford with open bottom structure to reduce sedimentation and provide fish passage.
6215000	2		G		3	Completed RAC project, reconstruction of 0.5 miles of road to provide proper drainage to restore hydrologic function of the wet meadow.
6237000	3		G		3	Needs asphalt berm at edge of pavement to reduce erosion caused from parking lot. Relocate approximately 0.25 miles, rip and recontour existing section.
7001000	1		G		3	Fix drainage.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
7003000	1		G		3	Fix drainage.
7004000	1		G		3	Fix drainage.
7006000	1		G		3	Reconstruct Bear cr. crossing.
7009000	1		G		3	Fix drainage.
7641000	2		E		3	Reconstruct meadow crossing @ far east Sec. 7.
7650000	1		G		3	Fix drainage.
8310000	1		G/E		3	Reconstruct Mosquito cr. crossing.
8601000	1		G		3	Fix drainage and erosion.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
8605000	1		G		3	Reconstuct crossings @ Shoestring creek, Alberta Camp drainage, Lost creek, Spring creek, and drainage crossing @ NW corner of Sec 30.
8606000	1		G		3	Fix drainage on south half of road near Shoestring cr.
8607000	1		G		3	Fix drainage.
8608000	1		G		3	Fix drainage.
8675000	1		G		3	Reconstuct drainage crossing approximately half mile in.
8676000	1		G		3	Completed project at Jack creek, placed crushed rock over Jack creek culvert to protect structure and placed riprap around pipe inlet and outlet for slope protection and stabilization.
8678000	1		G		3	Fix drainage @ upper end of road.
8816000	1		G		3	Fix drainage.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
8821000	1		G		3	Fix road drainage problems to eliminate sediment in Jack creek by constructing additional drainage features and spot surfacing.
8827000	1		G/E		3	Construct permeable fill.
8829000	1		G		3	Fix drainage near road 8821 and cattleguard approaches.
8840000	1		G		3	Reconstruct crossing at South Parker meadow.
8840000	1		G		3	Reconstruct Rock creek Ford.
8850000	1		G		3	Reconstuct drainage crossing.
9401000	1		G		3	Fix drainage @ south half of road.
9405000	1		G		3	Widen Sellers creek crossing and fix drainage on hill.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
9406000	1		G		3	Fix drainage.
9407000	1		G		3	Fix drainage near 9409 road.
9409000	1		G		3	Reconstruct Seller creek. crossing the fill is raveling.
9410000	1		G		3	Fix drainage.
9411000	1		G		3	Reconstruct Cannon well crossing.
9415000	1		G		3	Fix drainage on hill.
9450000	1		G		3	Fix drainage at South end near Cannon well.
9714000	2		G		3	Fix wet spots.

Table 5-1

## CIP LIST

## Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
9717000	2		G		3	Fix drainage.
9731000	2		G		3	Fix drainage.
9741000	1		G		3	Fix drainage @ south end of road.
9770000	1		G		3	Reconstruct Miller creek Culvert.
2310000	1			B	1	Surface native segment 2.0 miles.
3625000	3			B	1	Revert to aggregate.
3633000	3			C	1	Crack filling.
4356000	2			B	1	Cut brush for site distance, and surface.

Table 5-1

## CIP LIST

Collector Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
4502000	2			B	1	Surface native segment 2.9 miles.
6520000	2			B	1	Surfacing.
8610000	1			I	1	Need to protect Well across from water source.
9412000	1			I	1	Evaluate Waterhole well concern.
9711000	2			I	1	15% grade should be looked at.

Table 5-1

## CIP LIST

## Local Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
2308060	1	H	G		8	Reconstruct crossing @ Scott creek.
2228250	2		A		3	The middle fork of Trout Creek, this is a closed road and the stream drains a seasonal meadow, remove culvert.
3732010	3		G		3	Install culvert and spot surfacing.
3800800	3		G		3	Harden existing ford and revegetate banks.
4483-280	2		G		3	Completed RAC project, crushed rock surfacing applied to reduce sediment transport to Sycaan River.
4971230	1		G		3	Project to correct drainage problems.
9732300	2		G		3	Completed RAC project, constructed permeable low water crossing to alleviate sedimentation into meadow.
9772600	1		G		3	Project to further improve drainage.
9772610	1		G		3	Project to further improve drainage.
9772620	1		G		3	Project to further improve drainage.
9772625	1		G		3	Project to further improve drainage.
2300960	2			C	1	Crack filling, chip seal, line striping, brush cut, and parking bumpers.



Table 5-1

## CIP LIST

Local Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
3600480	3			C	1	Parking area needs reconstruction.
3650010	3			C	1	Crack filling and sealing.
3689020	3			I	1	Relocate and obliterate road is partially on private land.
3689025	3			I	1	Relocate and obliterate road is partially on private land.
3700240	3			B/C	1	Crack filling, sealing, line striping and shoulder rock.
3700245	3			B/C	1	Crack filling, sealing, line striping and shoulder rock.
3700370	3			B/C	1	Crack filling, sealing, line striping and shoulder rock.
3704060	3			B/C	1	Crack filling, sealing, line striping and shoulder rock.
3704065	3			B/C	1	Crack filling, sealing, line striping and shoulder rock.
3704080	3			B/C	1	Crack filling, sealing, line striping and shoulder rock.
3704110	3			B/C	1	Crack filling, sealing, line striping and shoulder rock.

Table 5-1

## CIP LIST

Local Roads

ID						Project Description
	Dist.	H&S	RES	MISS	Rating	
3704112	3			B/C	1	Crack filling, sealing, line striping and shoulder rock.
9700100	3			C	1	Crack filling, sealing.
9700330	2			C	1	Crack filling, sealing.
9700890	1			C	1	Crack filling, sealing.
9700900	1			C	1	Crack filling, sealing.
9700900	1			C	1	Crack filling, sealing.
9772060	1			I	1	Crack fill, seal line strip, and install gate across from snow park at water tower for compound.